

City of Box Elder Standard Construction Details

Table of Contents

2025 REVISIONS

DETAIL W01-GATE VALVE & BOX	6
DETAIL W02-HYDRANT WITH GATE VALVE & BOX	7
DETAIL W03-FLUSH RISER.....	8
DETAIL W04-AIR VACUUM RELEASE VALVE PIT	9
DETAIL W05-AIR VACUUM RELEASE PIT-COVER.....	10
DETAIL W06-WATER SERVICE METER PIT	11
DETAIL S01-STANDARD SEWER MANHOLE.....	12
DETAIL S02-SHALLOW MANHOLE SECTION	13
DETAIL S03-TYPICAL DROP MANHOLE	14
DETAIL S04-SEWER MAIN CLEANOUT	15
DETAIL S05-SANITARY SEWER CLEANOUT IN TRAVEL SURFACE	16
DETAIL S06-SEWER SERVICE RISER	17
DETAIL S07-SEWER SERVICE CONNECTION STUB	18
DETAIL S08-SEWER SERVICE CLEANOUT	19
DETAIL S09-SEWER SERVICE CLEANOUT AT BEND	20
DETAIL M01-TRENCH-TYPICAL & ALTERNATE.....	21
DETAIL M01A-TRENCH DETAIL FOR PVC WATER AND SEWER PIPE	22
DETAIL M01B-TRENCH DETAIL FOR RCP STORM SEWER.....	23
DETAIL M02-THRUST BLOCK SETTINGS	24
DETAIL M03-UTILITY MARKER & INSTALLATION	25
DETAIL M04-HIGHWAY CROSSING	26
DETAIL M05-GEOGRID FABRIC UTILITY TRENCH PATCH	27
DETAIL M06-UTILITY TRENCH DETAIL	28
DETAIL M07-TYPICAL TRENCH CHECK DAM	29
DETAIL M08-SPALL REPAIR	30
DETAIL M08A-SPALL REPAIR.....	31
DETAIL M09-CONCRETE PAVING REPAIR	32
DETAIL M11-WATER AND SEWER INSULATION DETAIL	33
DETAIL RC001-CULVERT-RCP-ROUND	34
DETAIL RC002-CULVERT-RCP-ARCH	35
DETAIL RC003-CULVERT-RCP BEND-ROUND (SHORT)	36
DETAIL RC004-CULVERT-RCP BEND-ROUND (LONG)	37
DETAIL RC005-CULVERT-RCP FLARED ENDS-ROUND.....	38
DETAIL RC006-CULVERT-RCP FLARED ENDS-ARCH	39
DETAIL RC007-CULVERT-RCP SAFETY ENDS.....	40


DETAIL RC008-CULVERT-RCP SLOPED ENDS-ROUND	41
DETAIL RC009-CULVERT-RCP SLOPED ENDS-ARCH	42
DETAIL RC010-CULVERT-RCP SLOPED END BAR ASSEMBLY-1	43
DETAIL RC011-CULVERT-RCP SLOPED END BAR ASSEMBLY-2	44
DETAIL RC012-CULVERT-RCP SECTIONAL ENDS-ROUND	45
DETAIL RC013-CULVERT-RCP SECTIONAL ENDS-ARCH	46
DETAIL RC014-CULVERT-RCP TIE BOLTS	47
DETAIL RC020-CULVERT-CMP-ARCH	48
DETAIL RC021-CULVERT-CMP SLOTTED DRAIN-1	49
DETAIL RC022-CULVERT-CMP SLOTTED DRAIN-2	50
DETAIL RC023-CULVERT-CMP ELBOWS.....	51
DETAIL RC024-CULVERT-CMP FLARED ENDS-ROUND	52
DETAIL RC025-CULVERT-CMP FLARED ENDS-ARCH	53
DETAIL RC026-CULVERT-CMP SLOPED ENDS-1	54
DETAIL RC027-CULVERT-CMP SLOPED ENDS-2	55
DETAIL RC028-CULVERT-CMP-RCP TRANSITIONS	56
DETAIL RC029-CULVERT-CMP SMOOTH TAPERED SLEEVE	57
DETAIL RC040-CULVERT-PRECAST BOX BARREL TIE.....	58
DETAIL RC041-CULVERT-PRECAST BOX TIE BOLT ASSEMBLY	59
DETAIL RC042-CULVERT-PRECAST BOX SLOPED END SECTION.....	60
DETAIL RC045-CULVERT-PRECAST DOUBLE BOX WITH SLOPED END-2' CUTOFF WALL	61
DETAIL RC046-CULVERT-PRECAST DOUBLE BOX WITH SLOPED END-4' CUTOFF WALL	62
DETAIL RC050-CULVERT-SLOPE TRANSITIONS-TYPE-1	63
DETAIL RC051-CULVERT-SLOPE TRANSITIONS-TYPE-2.....	64
DETAIL RD001-DROP INLET-CONCRETE-TYPE B (2X3)-1	65
DETAIL RD002-DROP INLET-CONCRETE-TYPE B (2X3)-2	66
DETAIL RD003-DROP INLET-CONCRETE-TYPE B (3X4)-1	67
DETAIL RD004-DROP INLET-CONCRETE-TYPE B (3X4)-2	68
DETAIL RD005-DROP INLET-CONCRETE-TYPE B (3X5.5)-1	69
DETAIL RD006-DROP INLET-CONCRETE-TYPE B (3X5.5)-2	70
DETAIL RD007-DROP INLET-CONCRETE-TYPE B (4X4)-1	71
DETAIL RD008-DROP INLET-CONCRETE-TYPE B (4X4)-2	72
DETAIL RD009-DROP INLET-CONCRETE-TYPE B (5.5X3)-1	73
DETAIL RD010-DROP INLET-CONCRETE-TYPE B (5.5X3)-2	74
DETAIL RD011-DROP INLET-CONCRETE-TYPE B (5.5X5.5)-1	75
DETAIL RD012-DROP INLET-CONCRETE-TYPE B (5.5X5.5)-2	76
DETAIL RD013-DROP INLET-CONCRETE-TYPE B (4X3)-1	77
DETAIL RD014-DROP INLET-CONCRETE-TYPE B (4X3)-2	78
DETAIL RD015-DROP INLET-CONCRETE-TYPE C (3X4)-1	79

DETAIL RD016-DROP INLET-CONCRETE-TYPE C (3X4)-2	80
DETAIL RD017-DROP INLET-CONCRETE-TYPE C (4X5)-1	81
DETAIL RD018-DROP INLET-CONCRETE-TYPE C (4X5)-2	82
DETAIL RD019-DROP INLET-CONCRETE-TYPE S (4X6)-1	83
DETAIL RD020-DROP INLET-CONCRETE-TYPE S (4X6)-2	84
DETAIL RD021-DROP INLET-CONCRETE-TYPE S (4X6)-3	85
DETAIL RD022-DROP INLET-CONCRETE-TYPE S (4X11)-1	86
DETAIL RD023-DROP INLET-CONCRETE-TYPE S (4X11)-2	87
DETAIL RD024-DROP INLET-CONCRETE-TYPE S (4X11)-3	88
DETAIL RD025-DROP INLET-CONCRETE-TYPE S (7X11)-1	89
DETAIL RD026-DROP INLET-CONCRETE-TYPE S (7X11)-2	90
DETAIL RD027-DROP INLET-CONCRETE-TYPE S (7X11)-3	91
DETAIL RD028-DROP INLET-CONCRETE-TYPE S (7X11)-4	92
DETAIL RD029-DROP INLET-CONCRETE-TYPE S-INSTALLATION-1	93
DETAIL RD030-DROP INLET-CONCRETE-TYPE S-INSTALLATION-2	94
DETAIL RD031-DROP INLET-CONCRETE-TYPE B-INSTALLATION	95
DETAIL RD032-DROP INLET-CONCRETE-TYPE B-FRAME AND GRATE ASSEMBLY	96
DETAIL RD033-DROP INLET-CONCRETE-TYPE C-FRAME AND GRATE ASSEMBLY	97
DETAIL RD034-DROP INLET-CONCRETE-TYPE E-FRAME AND GRATE ASSEMBLY.....	98
DETAIL RD040-DROP INLET-CONCRETE-PERMANENT COVERS-1.....	99
DETAIL RD040-DROP INLET-CONCRETE-PERMANENT COVERS-2.....	100
DETAIL RD042-DROP INLET-CONCRETE-PRECAST COLLAR.....	101
DETAIL RD050-DROP INLET-MANHOLE FRAME AND LID-TYPE A.....	102
DETAIL RD051-DROP INLET-MANHOLE FRAME AND LID-TYPE B.....	103
DETAIL RD060-HEADWALL-CONCRETE-UNDERDRAIN	104
DETAIL RD062-UNDER DRAIN CONNECTION DETAIL	105
DETAIL RD063-UNDER DRAIN DETAIL	106
DETAIL RE001-EROSION CONTROL-BLANKET	107
DETAIL RE002-EROSION CONTROL-BALES.....	108
DETAIL RE003-EROSION CONTROL-ROCK CHECK DAM	109
DETAIL RE004-EROSION CONTROL-SILT FENCE-1	110
DETAIL RE005-EROSION CONTROL-SILT FENCE-2	111
DETAIL RE006-EROSION CONTROL-WATTLE-1.....	112
DETAIL RE007-EROSION CONTROL-WATTLE-2.....	113
DETAIL RE008-EROSION CONTROL-INLETS-1	114
DETAIL RE009-EROSION CONTROL-INLETS-2	115
DETAIL RE020-EROSION CONTROL-GABION-1	116
DETAIL RE021-EROSION CONTROL-GABION-2	117
DETAIL RE022-EROSION CONTROL-GABION-3	118

DETAIL RE030-EROSION CONTROL-DITCH	119
DETAIL RE031-EROSION CONTROL-SLOPE DRAIN	120
DETAIL RE032-EROSION CONTROL-SURFACE ROUGHENING	121
DETAIL RF001-FENCING-RIGHT-OF-WAY	122
DETAIL RF002-FENCING INSTALLATION	123
DETAIL RF003-FENCING-BRACE PANEL AND APPLICATIONS	124
DETAIL RF004-FENCING-BRACE PANEL APPLICATIONS AT STRUCTURES	125
DETAIL RF005-FENCING-WIDE DEPRESSIONS AND STREAM CROSSINGS	126
DETAIL RF006-FENCING-GROUNDING	127
DETAIL RF010-FENCING-WIRE GATES	128
DETAIL RF011-FENCING-TUBULAR FRAME GATES	129
DETAIL RF020-FENCING-ANCHORS FOR BOX CULVERT WING WALLS	130
DETAIL RF021-FENCING-ANCHORS FOR BRIDGE ABUTMENT WING WALLS (>6')	131
DETAIL RF022-FENCING-ANCHORS FOR BRIDGE ABUTMENT WING WALLS (≤6')	132
DETAIL RF023-FENCING-ANCHORS FOR BRIDGE ABUTMENT WITH SWEEPED BACK WINGS	133
DETAIL RG001-CURB & GUTTER-TYPE B	134
DETAIL RG002-CURB & GUTTER-TYPE BL	135
DETAIL RG003-CURB & GUTTER-TAPER	136
DETAIL RG004-CURB & GUTTER-TYPE P	137
DETAIL RG005-CURB & GUTTER-VALLEY	138
DETAIL RG006-CURB & GUTTER-JOINTS-1	139
DETAIL RG007-CURB & GUTTER-JOINTS-2	140
DETAIL RG010-CURB & GUTTER-CURB RAMP-PERPENDICULAR-1	141
DETAIL RG011-CURB & GUTTER-CURB RAMP-PERPENDICULAR-2	142
DETAIL RG012-CURB & GUTTER-CURB RAMP-PERPENDICULAR-3	143
DETAIL RG013-CURB & GUTTER-CURB RAMP-DIRECTIONAL-1	144
DETAIL RG014-CURB & GUTTER-CURB RAMP-DIRECTIONAL-2	145
DETAIL RG015-CURB & GUTTER-CURB RAMP-DIRECTIONAL-3	146
DETAIL RG016-CURB & GUTTER-CURB RAMP-PARALLEL-1	147
DETAIL RG017-CURB & GUTTER-CURB RAMP-PARALLEL-2	148
DETAIL RG018-CURB & GUTTER-CURB RAMP-PARALLEL-3	149
DETAIL RG030-CURB & GUTTER-OPENING AND TRANSITIONS FOR FUTURE CURB RAMP-1 ...	150
DETAIL RG031-CURB & GUTTER-OPENING AND TRANSITIONS FOR FUTURE CURB RAMP-2 ...	151
DETAIL RL001-LIGHTING-DETECTOR LOOP-PREFORMED	152
DETAIL RL002-LIGHTING-DETECTOR LOOP-SAWED IN	153
DETAIL RL003-LIGHTING-DETECTOR LOOP-SAWED IN PCC	154
DETAIL RL004-LIGHTING-CONDUCTOR CABLES-CONDUIT	155
DETAIL RL005-LIGHTING-CONDUCTOR CABLES-DIRECT BURY	156
DETAIL RR001-RAILROAD-PAVEMENT MARKINGS AT CROSSINGS	157

DETAIL RR002-RAILROAD-TYPICAL APPROACH	158
DETAIL RR003-RAILROAD-EXCAVATION PROFLES	159
DETAIL RR010-RAILROAD-DETECTABLE SIDEWALK WARNINGS ADJACENT TO CROSSINGS-1	160
DETAIL RR011-RAILROAD-DETECTABLE SIDEWALK WARNINGS ADJACENT TO CROSSINGS-2	161
DETAIL RS001-SIDEWALK-CONCRETE-1	162
DETAIL RS002-SIDEWALK-CONCRETE-2	163
DETAIL RS010-SIDEWALK-DRAIN	164
DETAIL RS011-REINFORCED CONCRETE SIDEWALK ADJACENT TO PRECAST CONCRETE TYPE S DROP INLET	165
DETAIL RS012-SIDEWALK-ADJACENT TO TYPE S DROP INLET LID-2	166
DETAIL RS013-RESIDENTIAL DRIVEWAY APPROACH (PROPERTY LINE SIDEWALK)	167
DETAIL RS014-6" REINFORCED DRIVEWAY APPROACH AND SIDEWALK	168
DETAIL RS015-RESIDENTIAL APPROACH (CURBSIDE SIDEWALK)	169
DETAIL RS016-DRIVEWAY PROFILE GRADE	170
DETAIL RS017-RESIDENTIAL DRIVEWAY APPROACH	171
DETAIL RW001-CONCRETE RETAINING WALL-TYPE C-1	172
DETAIL RW002-CONCRETE RETAINING WALL-TYPE C-2	173

DETAIL W01-GATE VALVE & BOX




GATE VALVE & BOX
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL W01
GATE VALVE & BOX



DETAIL W02-HYDRANT WITH GATE VALVE & BOX



HYDRANT WITH GATE VALVE & BOX

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL W02
HYDRANT WITH GATE VALVE & BOX



2" GALVANIZED FITTINGS AND PIPE
NIPPLE PAINTED WITH RED ENAMEL

2-1/2" NST
OUTLET

6" DIA. x 6' LONG
TREATED
WOODEN
POST

CONCRETE SLAB REINFORCED WITH
6" - 6" x 10 x 10 WIRE MESH
36" x 24" AND 4" THICK MIN.

24" APPROX.

36"

2" FLUSH RISER
(DEPTH OF WATERLINE)

CONCRETE THRUST BLOCK

2" INLET

4" x 8" x 16" SOLID CONCRETE
BLOCK SET ON UNDISTURBED
EARTH

2" PVC SCH. 40 PIPE

2" BRASS PACK
JOINT COUPLING

CRUSHED ROCK
(8 CUBIC FEET)

EXPANSION SEAL

CURBSTOP AND LOCKWING

MINNEAPOLIS PATTERN
EXTENSION BOX WITH
S.S. STATIONARY ROD

2" BALL VALVE
CURB STOP


2" PVC SCH. 40 PIPE (5' MIN.)

COMPRESSION
CONNECTIONS

FLUSH RISER
NOT TO SCALE



DETAIL W04-AIR VACUUM RELEASE VALVE PIT




AIR / VACUUM RELEASE VALVE PIT INSTALLATION
NOT TO SCALE


CITY OF BOX ELDER
STANDARD DETAIL W04
AIR/VACUUM RELEASE VALVE PIT



DETAIL W05-AIR VACUUM RELEASE PIT-COVER



TOP VIEW



SECTION

*NOTE: ALL SURFACES OF COVER REQUIRE SURFACE PREPARATION TO
SSPC-SP6 AND POLYAMIDE EPOXY COATING OF 4.0 TO 6.0 MILS
THICKNESS*

CITY OF BOX ELDER

STANDARD DETAIL W05

AIR/VACUUM REL. VALVE PIT-COVER





DETAIL W06-WATER SERVICE METER PIT

ITEM NO.	DESCRIPTION
1	15" TILE (.300 THICK WALL)
2	LOWER PLATE STOP
3	RIVET
4	MOUNTING PLATE
* 5	INSULATING DISC
6	NUT
* 7	LOCKING LID
8	LID LOCKING BRACKET
9	INSERT, 3/4 CTS #51 (NOT SHOWN)
10	WASHER
11	3/4" COIL TUBE
12	3/4" COIL TUBE
13	70 DEG INLET ASSEMBLY
14	3/4" 60 DEGREE END PIECE
15	NUT ASSY
16	70 DEG OUTLET ASSEMBLY
♦ 17	PVC IDLER
18	METER GASKET

* ORDERED SEPARATELY, BUT REQUIRED.
♦ IDLER TO BE REMOVED UPON INSTALLATION OF METER PIT.

METER PIT SHALL BE:
FORD PFCBHH-288-15-XX-FP-R-NL
5/8" x 3/4" COIL PITSETTER, FP BV INLET, HHA
OUTLET (CHARTED FOR 36" TO 96" PIT DEPTH)
AS SHOWN OR APPROVED EQUAL.

MUST BE ALIGNED WITH
INLET/OUTLET CENTERLINE
BRACKET MUST BE INSTALLED
FLUSH WITH TOP OF TILE



WATER SERVICE METER PIT
NOT TO SCALE

SECTION A-A
SCALE 1 : 10

CITY OF BOX ELDER
STANDARD DETAIL W06
WATER SERVICE METER PIT




DETAIL S01-STANDARD SEWER MANHOLE

NOTE: NON-VENTED COVER WITH
CONCEALED PICK HOLE
AND LETTERING -SEWER-

MANHOLE FRAME & COVER
~~NEENAH 1733, DEETER 1259, OR~~
EQUAL SET IN MASTIC SEAL.

Neenah 1733-1
or Deeter 1259



STANDARD SEWER MANHOLE
NOT TO SCALE

CITY OF BOX ELDER


STANDARD DETAIL S01

STANDARD SEWER MANHOLE



DETAIL S02-SHALLOW MANHOLE SECTION


- NOTE:** 1. NON-VENTED COVER WITH CONCEALED PICK HOLE AND LETTERING-SEWER.
2. INSTALL EXTERIOR JOINT COLLAR ON MANHOLE SECTION JOINTS.



CITY OF BOX ELDER STANDARD DETAIL S02 SHALLOW MANHOLE SECTION




DETAIL S03-TYPICAL DROP MANHOLE



CITY OF BOX ELDER
STANDARD DETAIL S03
TYPICAL DROP MANHOLE



DETAIL S05- SANITARY SEWER CLEANOUT IN TRAVEL SURFACE



Note:

1. This detail shall be used when sanitary sewer service cleanouts are located in concrete or asphalt surfaced areas, or as shown in plans.

N.T.S.


CITY OF BOX ELDER

STANDARD DETAIL S05 - SANITARY

SEWER CLEANOUT IN TRAVEL SURFACE



DETAIL S04-SEWER MAIN CLEANOUT




SEWER MAIN CLEANOUT
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL S04
SEWER MAIN CLEANOUT



DETAIL S06-SEWER SERVICE RISER




SEWER SERVICE RISER
NOT TO SCALE


CITY OF BOX ELDER
STANDARD DETAIL S06
SEWER SERVICE RISER



DETAIL S07-SEWER SERVICE CONNECTION STUB



NOTE: IF SEWER SERVICE IS STUBBED OUT FROM HOUSE, CONNECTION THERETO SHALL BE MADE BY CONTRACTOR.




SEWER SERVICE CONNECTION STUB NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL S07
SEWER SERVICE CONNECTION STUB



DETAIL S08-SEWER SERVICE CLEANOUT





NOTE: THE 4" PVC SEWER SERVICE SHALL BE SCHEDULE 40 DWV PIPE FOR INDIVIDUAL WASTE DISPOSAL SYSTEM. WHERE 4" PVC ASTM D-3034 PIPE IS ALLOWED FOR CONNECTION TO COMMUNITY SEWER SYSTEM, PVC ADAPTER BUSHINGS ARE REQUIRED ON THE WYE.

SEWER SERVICE CLEANOUT
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL S08
SEWER SERVICE CLEANOUT



DETAIL S09-SEWER SERVICE CLEANOUT AT BEND




SEWER SERVICE CLEANOUT AT BEND
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL S09
SEWER SERVICE CLEANOUT AT BEND




DETAIL M01-TRENCH-TYPICAL & ALTERNATE

SECTION 31.23.16.12 HAUNCHING AND INITIAL BACKFILL



TYPICAL TRENCH
NOT TO SCALE

SECTION 31.23.16.11 BEDDING




ALTERNATE TRENCH BOTTOM PREPARATION
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL M01
SHALLOW MANHOLE SECTION



DETAIL M01A - TRENCH DETAIL FOR PVC WATER AND SEWER MAINS



*In some circumstances, larger foundation material may be necessary and in these cases stabilization Rock may be used Per Standard Specifications, 31.23.16.11. If Stabilization Rock is used, then a minimum 6 inches of Class 3 Foundation Material shall be placed directly above the material and prior to the placement of the Type 1 Bedding Material.


N.T.S.

CITY OF BOX ELDER STANDARD DETAIL M01A

TRENCH DETAIL FOR PVC WATER AND SEWER MAINS



DETAIL M01B - TRENCH DETAIL FOR RCP STORM SEWER MAINS



*In some circumstances, larger foundation material may be necessary and in these cases stabilization Rock may be used Per Standard Specifications, 31.23.16.11. If Stabilization Rock is used, then a minimum 6 inches of Class 3 Foundation Material shall be placed directly above the material and prior to the placement of the granular material.



** Granular material shall be per Standard Specifications, 31.23.16. Bedding thickness below the pipe in inches shall be the outer pipe diameter (OD) in inches divided by 24 ($OD/24$) and no less than 3". Bedding beneath the pipe shall be in contact with the pipe for a distance no less than $1/3$ the outer diameter ($OD/3$). The bedding shall extend the full width of the trench. Compaction above the bedding shall be per Standard Specifications, 31.23.16.13.

N.T.S.

CITY OF BOX ELDER
STANDARD DETAIL M01B
TRENCH DETAIL FOR RCP STORM SEWER MAINS



DETAIL M02-THRUST BLOCK SETTINGS




THRUST BLOCK SETTINGS **NOT TO SCALE**

Thrust blocks do not replace Mech. Joint Restraints

CITY OF BOX ELDER
STANDARD DETAIL M02
THRUST BLOCK SETTINGS



DETAIL M03-UTILITY MARKER & INSTALLATION



INSTALL PLASTIC MARKERS WITH FLAT SIDES POINTED IN DIRECTION OF VALVE OR MANHOLE. LOCATE MARKERS AT DISTANCES FROM THE VALVE OR MANHOLE TO FORM A 45° RIGHT TRIANGLE WITH ONE SHORT SIDE PERPENDICULAR TO THE VALVE OR MANHOLE. THE CONVERGING ANGLE OF THE MARKER SHALL POINT AT THE LINE AND ALSO IN THE FLOW DIRECTION. PLASTIC MARKER POST SHALL BE EQUAL TO 62" COLORED CARSONITE UTILITY MARKER AS MANUFACTURED BY AMETEK, INC., CARSON CITY, NEVADA. USE BLUE MARKERS FOR INLINE GATE VALVES AND AIR RELEASE MANHOLES ON WATER TRANSMISSION LINES. USE GREEN MARKERS FOR INLINE GATE VALVE AND AIR RELEASE MANHOLES ON SEWER FORCE MAINS. MARKERS (GREEN) CAN ALSO BE USED FOR SEWER MANHOLES FOR SPECIAL CIRCUMSTANCES.


UTILITY MARKER & INSTALLATION **NOT TO SCALE**

CITY OF BOX ELDER
STANDARD DETAIL M03
UTILITY MARKER & INSTALLATION



DETAIL M04-HIGHWAY CROSSING

- NOTE: 1. LENGTH OF BORE SHALL BE A MINIMUM OF 5' BEYOND THE OUTSIDE SHOULDER WITH A MINIMUM COVER AS SPECIFIED.
2. ALL BORES SHALL BE MADE PERPENDICULAR TO ROADWAY UNLESS APPROVED BY RESIDENT PROJECT REPRESENTATIVE.
3. INSTALL CASING SPACERS AND END SEALS.




HIGHWAY CROSSING
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL M04
HIGHWAY CROSSING



DETAIL M05- GEOGRID FABRIC UTILITY TRENCH PATCH



Notes:

1. All saw cuts to be full depth.
2. Patch material shall match the existing pavement material (eg. PCC pavement shall be patched with PCC and existing asphalt pavement with asphalt).
3. For asphalt patches base course & asphalt concrete thickness to match existing but in no case will be less than 6" base & 5" asphalt concrete. The existing vertical asphalt face shall be tacked.
4. For PCC pavement patches - see Section 31.23.16.05.
5. PCC pavement removals shall be per Section 31.23.16.05.
6. Trenches are shown to diagram patching requirements and at a minimum meet the minimum trench width table below. Trenches shall be constructed to meet OSHA requirements.
7. Pavement removal between first and second saw cut shall be removed at time of patching.

TABLE 11-1 MINIMUM TRENCH WIDTH TABLE


Pipe Diameter	Minimum Width
<8 in.	24"
8in. - 12in.	30"
14in. - 18in.	36"
20in. - 21in.	42"
24in. - 36in.	1.25 (Pipe O.D.) Plus 12in.
>36in.	Per Plans

N.T.S.

CITY OF BOX ELDER STANDARD DETAIL M05 - GEOGRID FABRIC UTILITY TRENCH PATCH



DETAIL M06- UTILITY TRENCH DETAIL



Notes:

1. All saw cuts to be full depth.
2. Patch material shall match the existing pavement material (eg. PCC pavement shall be patched with PCC and existing asphalt pavement with asphalt).
3. For asphalt patches base course & asphalt concrete thickness to match existing but in no case will be less than 6" base & 5" asphalt concrete. The existing vertical asphalt face shall be tacked.
4. For PCC pavement patches - see Section 31.23.16.05.
5. PCC pavement removals shall be per Section 31.23.16.05.
6. Trenches are shown to diagram patching requirements and at a minimum meet the minimum trench width table below. Trenches shall be constructed to meet OSHA requirements.
7. Pavement removal between first and second saw cut shall be removed at time of patching.


TABLE 11-1 MINIMUM TRENCH WIDTH TABLE	
Pipe Diameter	Minimum Width
<8 in.	24"
8in. - 12in.	30"
14in. - 18in.	36"
20in. - 21in.	42"
24in. - 36in.	1.25 (Pipe O.D.) Plus 12in.
>36in.	Per Plans

N.T.S.

CITY OF BOX ELDER
STANDARD DETAIL M05
UTILITY TRENCH DETAIL



DETAIL M07- TYPICAL TRENCH CHECK DAM DETAIL FOR WATER & SEWER MAINS



Note:

Check dam installation locations shall be as indicated on the plans. However during construction, check dam installation locations may be moved due to field conditions. The check dam shall extend from the bottom of the excavation through the bedding material to the "Normal Backfill" and shall extend completely to each trench sidewall. Do not construct check dam around pipe joint.



N.T.S.

CITY OF BOX ELDER

**STANDARD DETAIL M07 - TYPICAL TRENCH
CHECK DAMS FOR WATER & SEWER MAINS**



DETAIL M08- SPALL REPAIR



N.T.S.

CITY OF BOX ELDER
STANDARD DETAIL M08
SPALL REPAIR



DETAIL M08A - SPALL REPAIR

Notes:

1. Spall quantities shown in the plans are approximate and are based on field measurements at the time of plans preparation. Spall repairs shall be marked in the field by the engineer and may vary from the plans based on field conditions.
2. Spalls will be marked out to the nearest whole foot. Removal is to extend 6 inches beyond the spall on transverse joints. Minimum length of removal shall be 3'. Joints containing spalls closer than 4' shall have the removal limits combined. Multiple milling passes may be required in areas where existing spalls are too wide to remove in one pass.
3. Spall repair areas shall be removed thru the use of a vertical edge milling machine. The milled width shall be a minimum of 12" and shall have a uniform depth of 2.5" over the area to be removed. An initial saw cut will be required around the perimeter of the removal area. The saw cut shall be a minimum of 1.5" depth to control edge chipping beyond the area to be repaired.
4. Prior to the placement of concrete the surface of the milled area shall be sand blasted to remove any additional unsound concrete and free latances. Compressed air shall then be used for the final cleaning of the surface. After final cleaning of the spall a bonding mortar shall be mixed and applied to all existing concrete surfaces (horizontal and vertical) to receive the spall fill material. The bonding mortar shall consist of the following proportions: 2 parts portland cement to 1 part sand. The portland cement and sand shall be mixed with enough water to form a thick creamy consistency. The Contractor may propose to utilize other commercially available bonding agents thru the submittal process.
5. The surface temperature shall be 40 degrees and rising prior to the placement of the bonding agent and concrete fill material. The concrete fill material shall be consolidated by the use of a small spud vibrator.
6. The final finishing procedure is to paint a sand-cement grout, the same grout used for the bonding mortar, at the edges of the repair to impede delamination of the patch. This ensures that a high percentage of cementitious material is available to glue the edges of the patch material to the existing concrete, helping to prevent the infiltration of moisture that can lead to delamination if water at the interface freezes in cold weather. The final surface shall be a broomed finish.
7. Joints shall be sawed to match existing joints and shall be sawed to the depth of the spall material plus 0.25". The sawed joint shall be sealed using hot tar.
8. Linseed oil cure shall be applied at a rate of 1 gallon per 75 SF. The repair areas shall be covered for 48 hours following the application of cure. Cold weather concreting procedures shall be followed during the 48 hour covering period, as needed.
9. Fill material for the spall areas shall be a commercially supplied redi-mix concrete conforming to the following proportions:


Cement	750 lbs
Course agg	1330 lbs
Fine agg	1330 lbs
Air	4.5% to 7.5%
Slump	1" to 4"
Max w/c ratio	0.42
Water reducer	As Needed
10. Course aggregate shall be 3/8 chip rock. Fly ash will not be allowed. A concrete mix design shall be submitted for acceptance prior to use on the project.
11. Payment for the spall repair will be by the square foot (SF) of repair. Payment shall include all work required to mill and remove existing, saw cutting to control edge chipping, final saw cutting, sealing, concrete placement and all associated items.
12. Processes and procedures for spall repair within this detail are from the National Concrete Pavement Technology Centers guide for partial depth repair of concrete pavements dated April 2012.

N.T.S.

CITY OF BOX ELDER STANDARD DETAIL M08A SPALL REPAIR



DETAIL M09 - CONCRETE PAVING REPAIR



PLAN VIEW

Steel Bars for Transverse Joints

- Drilled epoxy coated plain round dowel bar 12" center to center. (See chart for size.)
- Drilled epoxy coated deformed tie bar 18" center to center. (See chart for size.)

DBA Dowel Basket Assembly (See chart for size.)

Steel Bars for Longitudinal Joints

- No. 5 x 30" epoxy coated deformed tie bars. Placed in monolithic pavement centered on joint - spaced 48" center to center.
- No. 5 x 24" epoxy coated deformed tie bars. Drilled and epoxied 9" minimum depth into existing concrete - spaced 30" center to center.

Steel Bars for Curb and Gutter and Concrete Fillets

- No. 5 x 24" epoxy coated deformed tie bars. Drilled and epoxied 9" minimum depth into existing curb and gutter.
- No. 5 x 24" epoxy coated smooth dowel bars. Drilled and epoxied 9" minimum depth into existing curb and gutter.
- No. 5 x 30" epoxy coated deformed tie bars. Placed in monolithic pavement centered on joint - spaced 48" center to center.
- No. 5 x 24" epoxy coated deformed tie bars. Drilled and epoxied 9" minimum depth into existing concrete - spaced 30" center to center.
- No. 4 x 24" epoxy rebar. Drilled and epoxy 9" minimum depth into existing concrete. See Section 32.13.13.14 details for spacing.

PCC Pavement Repair Areas, Full Depth

- (A) Half panel repair, transverse. Only half panels will be allowed. See detail.
- (B) Full panel repair.
- (C) Multiple full panels. Dowel basket assemblies shall be used for new transverse joints.
- (D) Half panel repair, longitudinal. Only half panels will be allowed.

PCC Pavement Spall Repair Areas, Partial Depth

- (E) Spall repair areas. See detail.

Curb and Gutter and Concrete Fillet

- (F) See Section 32.13.13.14

PAVEMENT THICKNESS	EPOXY COATED BAR SIZE
7" to 7½"	1" x 18" Smooth Bar or No. 8 Deformed Bar
8" to 10"	1¼" x 18" Smooth Bar or No. 9 Deformed Bar
10½" to 13"	1½" x 18" Smooth Bar or No. 10 Deformed Bar

Notes:


- Concrete shall be sawed full depth. Final removal limits are shown. A second saw cut is required for all concrete removals.
- Joints, both transverse and longitudinal, shall be constructed to match existing joints unless directed by the Engineer.
- Joints shall be sawed and sealed as per details.

N.T.S.

**CITY OF BOX ELDER
STANDARD DETAIL M09
CONCRETE PAVING REPAIR**



DETAIL M11- WATER AND SEWER INSULATION DETAIL



INSULATION WIDTH FOR PIPE DEPTH			
Water		Sewer	
D (Feet)	W (Feet)	D (Feet)	W (Feet)
3	8	2.5	8
4	6	3	6
5	4	3.5	4

Water mains 20 inch diameter and larger -
insulation not required for 5 foot bury depths.

Note:

1. The use of insulation requires prior approval by the Public Works Director.
2. Refer to 31.23.16.14

N.T.S.

CITY OF BOX ELDER
STANDARD DETAIL M11
WATER & SEWER INSULATION



DETAIL RC001-CULVERT-RCP-ROUND

TOLERANCES IN DIMENSIONS


Diameter: $\pm 1.5\%$ for 24" Dia. or less and $\pm 1\%$ or $3/8"$ whichever is more for 27" Dia. or greater.

Diameters at joints: $\pm 3/16"$ for 30" Dia. or less and $\pm 1/4"$ for 36" or greater.


Length of joint (j): $\pm 1/4"$.

Wall thickness (T): not less than design T by more than 5% or $3/16"$, whichever is greater.

Laying length: shall not underrun by more than $1/2"$.



LONGITUDINAL SECTION



END VIEW

GENERAL NOTES:

Not more than 2 four-foot sections shall be permitted near the ends of any culvert. Four-foot lengths shall be used only to secure the required length of culvert.

Diam. (in.)	Approx. Wt. /Ft. (lb.)	T (in.)	J (in.)	D1 (in.)	D2 (in.)	D3 (in.)	D4 (in.)
12	92	2	13/4	131/4	135/8	137/8	141/4
15	127	21/4	2	161/2	167/8	171/4	175/8
18	168	21/2	21/4	195/8	20	203/8	203/4
21	214	23/4	21/2	227/8	231/4	233/4	241/8
24	265	3	23/4	26	263/8	27	273/8
27	322	31/4	3	291/4	295/8	301/4	305/8
30	384	31/2	31/4	323/8	323/4	331/2	337/8
36	524	4	33/4	383/4	391/4	40	401/2
42	685	41/2	4	451/8	455/8	461/2	47
48	867	5	41/2	511/2	52	53	531/2
54	1070	51/2	41/2	577/8	583/8	593/8	597/8
60	1296	6	5	641/4	643/4	66	661/2
66	1542	61/2	51/2	705/8	711/8	721/2	73
72	1810	7	6	77	771/2	79	791/2
78	2098	71/2	61/2	833/8	837/8	855/8	861/8
84	2410	8	7	893/4	901/4	921/8	925/8
90	2740	81/2	7	953/4	961/4	981/8	985/8
96	2950	9	7	1021/8	1025/8	1041/2	105
102	3075	91/2	71/2	109	1091/2	1111/2	112
108	3870	10	71/2	1151/2	116	118	1181/2


REINFORCED CONCRETE PIPE-ROUND

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RC001
CULVERT-RCP-ROUND



DETAIL RC002-CULVERT-RCP-ARCH



TOLERANCES IN DIMENSIONS

Radial dimensions at joints: $\pm 1/8"$ for 65" span or less and $\pm 1/4"$ for longer spans.
 Rise and Span: $\pm 2\%$ of tabular values.
 Length of Joint (J): $\pm 1/4"$.
 Wall thickness (T): not less than design T by more than 5% or $3/16"$, whichever is greater.
 Laying length: shall not underrun by more than $1/2"$.

Gravel Bedding Material shall be supplied for 102" to 169" spans. It shall be placed to a thickness of 6" (Min.) x 85% of the Span x Length of culvert and shall conform to the gradation requirements for gravel surfacing except material may be screened or may be plan provided material.

* Size (in.)	Approx. Wt./Ft. (lb.)	Rise (in.)	Span (in.)	T (in.)	a (in.)	b (in.)	c (in.)	j (in.)	e (in.)	f (in.)	g (in.)	R1 (in.)	R2 (in.)	R3 (in.)
18	170	131/2	22	21/2	13/8	3/8	3/4	2	11/8	3/8	1	271/2	133/4	51/4
24	320	18	281/2	31/2	15/8	1/2	13/8	3	13/8	1/2	15/8	4011/16	143/4	45/8
30	450	221/2	361/4	4	113/16	5/8	19/16	31/2	19/16	5/8	113/16	51	183/4	61/8
36	600	265/8	433/4	41/2	2	3/4	13/4	4	13/4	3/4	2	62	221/2	61/2
42	740	315/16	511/8	41/2	2	3/4	13/4	4	13/4	3/4	2	73	261/4	73/4
48	890	36	581/2	5	21/4	3/4	2	5	2	3/4	21/4	84	30	87/8
54	1100	40	65	51/2	21/2	3/4	21/4	5	21/4	3/4	21/2	921/2	333/8	10
60	1400	45	731/2	6	35/16	3/4	115/16	5	23/4	3/4	21/2	105	371/2	11
72	1900	54	88	7	313/16	1	23/16	6	31/4	1	23/4	126	45	135/16
84	2500	62	102	8	41/8	1	27/8	6	31/2	1	31/2	1621/2	52	141/2
96	3300	78	1223/8	9	41/2	1	31/2	7	4	1	4	218	62	20
108	4200	88	1381/2	10	5	1	4	7	41/2	1	41/2	269	70	22
120	5100	967/8	154	11	51/2	1	41/2	7	5	1	5	3013/8	78	24
132	5100	1061/2	1683/4	10		1	4	7	41/2	1	41/2	329	855/8	267/8

* Equivalent Diameter of Circular R. C. P.

GENERAL NOTES:


Not more than 2 four-foot sections shall be permitted near the ends of any culvert. Four-foot lengths shall be used only to secure the required length of culvert.

REINFORCED CONCRETE PIPE-ARCH **NOT TO SCALE**

CITY OF BOX ELDER
STANDARD DETAIL RC002
CULVERT-RCP-ARCH



DETAIL RC003-CULVERT-RCP BEND-ROUNDING (SHORT)



D (in.)	Laying Length at Center of Pipe (in.)	Laying Length at Outside of Curve (in.)	T (in.)	A (in.)	B (in.)	C (in.)	E (in.)	Radius of Curve (ft.)	Weight of Section (lbs.)
12	7 3/4	8	2	4 3/4	2	5 3/4	3	4.9	70
15	11 1/4	12 1/2	2 1/4	5 1/4	4 3/4	6 1/2	6	7.2	120
18	12 1/8	13 5/8	2 1/2	5 1/2	5 1/8	7	6 5/8	7.7	170
21	9 1/2	11 1/4	2 3/4	5 1/2	2 1/4	7 1/4	4	6.1	170
24	9 13/16	11 3/4	3	5 9/16	2 5/8	7 1/2	4 1/4	6.2	215
27	9 11/16	12 1/8	3 1/4	5 7/16	2 5/16	7 5/8	4 1/2	6.2	260
30	10	12 3/8	3 1/2	5 5/16	2 5/16	7 11/16	4 11/16	6.4	320
33	11 3/16	13 7/8	3 3/4	5 15/16	2 9/16	8 5/8	5 1/4	7.1	420
36	12 3/16	15 1/16	4	6 1/2	2 5/16	9 3/8	5 11/16	7.7	530
42	14 1/16	17 1/2	4 1/2	6 13/16	3 13/16	10 5/16	7 3/16	8.9	800
48	16 1/16	20 1/4	5	7 15/16	4 11/16	11 3/4	8 1/2	10.5	1190
54	18 1/16	22 5/16	5 1/2	7 5/8	6 3/16	11 7/8	10 7/16	11.5	1600
60	20 1/2	25 1/4	6	8 5/8	7 1/8	13 3/8	11 7/8	13.0	2210
66	21 5/8	26 15/16	6 1/2	9	7 3/8	14 5/16	12 5/8	13.8	2790
72	22 5/8	28 1/4	7	9 3/8	7 5/8	13 1/4	15	14.4	3420

REINFORCED CONCRETE PIPE BEND-ROUND (SHORT RADIUS) NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RC003

CULVERT-RCP BEND-ROUND (SHORT)



DETAIL RC004-CULVERT RCP- BEND-ROUND (LONG)



GENERAL NOTE:

Centerline laying length: 4'-0"
Radius of Curve: 30.5'

D (in.)	T (in.)	A (in.)	B (in.)	C (in.)	E (in.)	Weight of Section (lbs.)
12	2	36 15/32	10 15/32	37 17/32	11 17/32	368
15	2 1/4	36 1/2	10 1/4	37 3/4	11 1/2	508
18	2 1/2	24 1/2	22	26	23 1/2	672
21	2 3/4	24 1/2	21 3/4	26 1/4	23 1/2	856
24	3	25 1/32	21 1/32	26 31/32	22 31/32	1060
27	3 1/4	25 1/32	20 25/32	27 7/32	22 31/32	1288
30	3 1/2	25 1/32	20 17/32	27 15/32	22 31/32	1536
33	3 3/4	24 15/16	20 7/16	27 9/16	23 1/16	1808
36	4	24 13/16	20 5/16	27 11/16	23 3/16	2096
42	4 1/2	24 27/32	19 27/32	28 5/32	23 5/32	2740
48	5	24 19/32	19 19/32	28 13/32	23 13/32	3468
54	5 1/2	24 5/8	19 1/8	29 11/32	23 3/8	4280
60	6	24 21/32	18 21/32	29 11/32	23 11/32	5184
66	6 1/2	24 11/16	18 3/16	29 13/16	23 5/16	6168
72	7	24 1/8	18 1/8	29 7/8	23 7/8	7240
84	8	24 1/4	17 1/4	30 3/4	23 3/4	9640
96	9	23 5/16	17 5/16	30 11/16	24 11/16	12400

REINFORCED CONCRETE PIPE BEND-ROUND (LONG RADIUS)

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RC004


CULVERT-RCP BEND-ROUND (LONG)



DETAIL RC005-CULVERT-RCP FLARED ENDS-ROUND



TOP VIEW




SLOPE DETAIL


GENERAL NOTES:

Lengths of concrete pipe shown on plan sheets are between flared ends only.

Construction of R.C.P. Flared End shall conform to the requirements of Section 990 of the Specifications.



LONGITUDINAL SECTION



END VIEW

Dia. (in.)	Approx. Wt. of Section (lbs.)	Approx. Slope (X to Y)	T (in.)	A (in.)	B (in.)	C (in.)	D (in.)	E (in.)	G (in.)	R (in.)
12	530	2.4: 1	2	4	24	48 7/8	72 7/8	24	2	11 1/2
15	740	2.4: 1	2 1/4	6	27	46	73	30	2 1/4	11 1/2
18	990	2.3: 1	2 1/2	9	27	46	73	36	2 1/2	11 1/2
21	1280	2.4: 1	2 3/4	9	36	37 1/2	73 1/2	42	2 3/4	11 1/2
24	1520	2.5: 1	3	9 1/2	43 1/2	30	73 1/2	48	3	11 1/2
27	1930	2.5: 1	3 1/4	10 1/2	49 1/2	24	73 1/2	54	3 1/4	11 1/2
30	2190	2.5: 1	3 1/2	12	54	19 3/4	73 3/4	60	3 1/2	11 1/2
36	4100	2.5: 1	4	15	63	34 3/4	97 3/4	72	4	11 1/2
42	5380	2.5: 1	4 1/2	21	63	35	98	78	4 1/2	11 1/2
48	6550	2.5: 1	5	24	72	26	98	84	5	11 1/2
54	8240	2: 1	5 1/2	27	65	33 1/4	98 1/4	90	5 1/2	11 1/2
60	8730	1.9: 1	6	35	60	39	99	96	5	11 1/2
66	10710	1.7: 1	6 1/2	30	72	27	99	102	5 1/2	11 1/2
72	12520	1.8: 1	7	36	78	21	99	108	6	11 1/2
78	14770	1.8: 1	7 1/2	36	90	21	111	114	6 1/2	11 1/2
84	18160	1.6: 1	8	36	90 1/2	21	111 1/2	120	6 1/2	11 1/2
90	20900	1.5: 1	8 1/2	41	87 1/2	24	111 1/2	132	6 1/2	6

REINFORCED CONCRETE PIPE FLARED ENDS-ROUND

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RC005


CULVERT-RCP FLARED ENDS-ROUND




DETAIL RC006-CULVERT-RC FLARED ENDS-ARCHED




TOP VIEW



SLOPE DETAIL



LONGITUDINAL SECTION



END VIEW

GENERAL NOTES:

Lengths of concrete pipe shown on plan sheets are between flared ends only.

Construction of R. C. P. Arch Flared End shall conform to the requirements of Section 990 of the Specifications.

* Size (in.)	Approximate Weight of Section (lbs.)	Rise (in.)	Span (in.)	Slope (X: Y)	T (in.)	A (in.)	B (in.)	C (in.)	D (in.)	E (in.)	R (in.)
18	1100	131/2	22	3: 1	21/2	7	27	45	72	36	2
24	1750	18	281/2	3: 1	31/2	81/2	39	33	72	48	3
30	3300	221/2	361/4	3: 1	4	91/2	50	46	96	60	3
36	4350	265/8	433/4	3: 1	41/2	111/8	60	36	96	72	6
42	5250	315/16	511/8	3: 1	41/2	1513/16	60	36	96	78	6
48	6400	36	581/2	3: 1	5	21	60	36	96	84	6
54	7850	40	65	3: 1	51/2	251/2	60	36	96	90	6
60	9500	45	731/2	3: 1	6	31	60	36	96	96	6
72	13550	54	88	2: 1	7	31	60	39	99	120	6
84	17950	62	102	2: 1	8	281/2	83	19	102	144	6

*Equivalent Diameter of Circular R. C. P.

REINFORCED CONCRETE PIPE FLARED ENDS-ARCH **NOT TO SCALE**


CITY OF BOX ELDER

STANDARD DETAIL RC006

CULVERT-RCP FLARED ENDS-ARCH




DETAIL RC007-CULVERT-RCP SAFETY ENDS




TOP VIEW

If bars are specified in the plans then provide HSS 2.5X2.5X.1875 Structural Steel Tubing in conformance with ASTM A500, Grade B or 3" Diameter Schedule 40 Pipe in conformance with ASTM A53, Grade B.



SIDE VIEW



ELEVATION VIEW

Dia. (in.)	T (in.)	R (in.)	A (in.)	B (in.)	C (in.)	D (in.)	E (in.)	F (in.)	No. Sections	No. Bars
FOR CIRCULAR PIPE										
15	21/4	3	6	48	9	57	6	18	1	3
18	21/2	3	6	69	9	78	9	24	1	3
*24	3	3	6	111	9	120	6	24	1 or 2	5
FOR ARCH PIPE										
**18	21/2	1	6	39	33	72	6	24	1	2

* The use of 2 sections must be an approved design.
 ** Equivalent Diameter of Circular R. C. P.

GENERAL NOTES:

The length of concrete pipe shown on the plans is between safety ends.

Safety ends without bars are acceptable with or without the bar notches.


Bars shall be galvanized after fabrication in accordance with ASTM A123.

REINFORCED CONCRETE PIPE SAFETY ENDS **NOT TO SCALE**

CITY OF BOX ELDER
 STANDARD DETAIL RC007
 CULVERT-RCP SAFETY ENDS



DETAIL RC008-CULVERT-RCP SLOPED ENDS-ROUND



Dia. (in.)	T (in.)	A (in.)	B (in.)	C (in.)	D (in.)	E (in.)	F (in.)	G (in.)
36	4	12	86.5	57.5	144	72	72	
42	4.5	12	110.5	33.5	144	72	72	
48	5	12	134.5	33.5	168	96	72	
54	5.5	12	158.5	33.5	192	96	96	
60	6	12	182.5	33.5	216	72	72	72

GENERAL NOTE:


The length of concrete pipe shown in the construction plans is between sloped ends. If bars are specified in the plans, then the bar assemblies shall be constructed in accordance with Standard Plate 450.15.

REINFORCED CONCRETE PIPE SLOPED ENDS-ROUND NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RC008
CULVERT-RCP SLOPED ENDS-ROUND




DETAIL RC009-CULVERT-RCP SLOPED ENDS-ARCH



Dia. (in.)	T (in.)	A (in.)	B (in.)	C (in.)	D (in.)	R (in.)
FOR CIRCULAR PIPE						
24	3	6	72	12	84	3
30	3 1/2	7 1/2	90	12	102	3 1/2
FOR ARCH PIPE						
* 24	3	6	48	12	60	3
* 30	3 1/2	7 1/2	60	12	72	3 1/2
* 36	4 1/2	8 5/8	66	30	96	0
* 42	4 1/2	10	77 1/4	48 3/4	96	0

Dia. (in.)	T (in.)	A (in.)	B (in.)	C (in.)	D (in.)	R (in.)
FOR CIRCULAR PIPE						
24	3	9	72	12	84	0
30	3 1/2	11	90	12	102	0
FOR ARCH PIPE						
* 24	3	9	48	12	60	0
* 30	3 1/2	11	60	12	72	0

- * Equivalent Diameter of Circular R.C.P.
 ** Acceptable Flat Bottom Alternate.



GENERAL NOTE:


The length of concrete pipe shown in the construction plans is between sloped ends.

REINFORCED CONCRETE PIPE SLOPED ENDS-ARCH NOT TO SCALE

CITY OF BOX ELDER
 STANDARD DETAIL RC009
 CULVERT-RCP SLOPED ENDS-ARCH



DETAIL RC010-CULVERT-RCP SLOPED END BAR ASSEMBLY-1



GENERAL NOTES:

The bar assembly shall be fabricated from steel in accordance with ASTM A53, Grade B or ASTM A500, Grade B.

The schedule 40 pipe sizes on the bar assembly drawings indicate sizes in regards to specification ASTM A53, Grade B. The allowable ASTM A500, Grade B sizes are HSS 3.5X.216 (for 3" schedule 40 pipe) and HSS 3X.25 (for 2.5" schedule 40 pipe).

Welding shall be accomplished by a certified welder.

The bar assembly shall be galvanized after fabrication in accordance with ASTM A123.

Cost for all work and materials required for fabrication and installation of the bar assembly shall be incidental to the bid items for the various sizes of sloped ends.

REINFORCED CONCRETE PIPE SLOPED END BAR ASSEMBLY-1

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RC010

CULVERT-RCP SLOPED END BAR ASSEMBLY-1



DETAIL RC011-CULVERT-RCP SLOPED END BAR ASSEMBLY-2




REINFORCED CONCRETE PIPE SLOPED END BAR ASSEMBLIES-2
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RC011
CULVERT-RCP SLOPED END BAR ASSEMBLY-2



DETAIL RC012-CULVERT-RCP SECTIONAL ENDS-ROUND



Dia. (in.)	T (in.)	L (ft.)	INLET END			OUTLET END		
			A (in.)	B (in.)	C (in.)	A (in.)	B (in.)	C (in.)
96	9	12	42	104	40	44	99	45
108	10	16	42	128	64	44	123	69
120	11	16	42	152	40	44	147	45

GENERAL NOTES:

Reinforcement per Class 2 RCP with double reinforcement in the upper 120 degrees of pipe.

Lengths of concrete pipe shown on plan sheets are between sectional ends only. the full barrel portion.

REINFORCED CONCRETE PIPE SECTIONAL ENDS-ROUND **NOT TO SCALE**

CITY OF BOX ELDER
STANDARD DETAIL RC012
CULVERT-RCP SEC. ENDS-ROUND




DETAIL RC013-CULVERT-RCP SECTIONAL ENDS-ARCH


GENERAL NOTES:

Construction of R.C.P. Arch Sectional Ends shall conform to the requirements of Section 990 of the Specifications.


Lengths of concrete pipe shown on plan sheets are between sectional ends only.




TOP VIEW



DETAIL A



SIDE VIEW



END VIEW

* Size (in.)	Approx. Weight Sect. 1 (lbs.)	Approx. Weight Sect. 2 (lbs.)	Approx. Weight Sect. 3 (lbs.)	Rise (in.)	Span (in.)	T (in.)	L (in.)	W (in.)	X (in.)	Y (in.)	Z (in.)
90	19100	3950		72	1151/2	81/2	1021/4	72	301/4	377/8	48
96	22000	6050		78	1223/8	9	1121/2	72	401/2	39	54
108	23000	15800		88	1381/2	10	1291/2	48	811/2	423/8	66
120	27000	24600		967/8	154	11	144	48	96	467/8	78
132	27950	25260	13640	1061/2	1683/4	10	144	48	96		90

- *Equivalent Diameter of Circular R. C. P.
 **2'-0" for Groove End and 2'-7" for Tongue End.
 ***Section 3 available for 132" size only.

REINFORCED CONCRETE PIPE SECTIONAL ENDS-ARCH

NOT TO SCALE

CITY OF BOX ELDER
 STANDARD DETAIL RC013
 CULVERT-RCP SEC. ENDS-ARCH



DETAIL RC014-CULVERT-RCP TIE BOLTS


Wall "t" (in.)	Rod Dia. (in.)	Pipe Sleeve Dia. (nominal)
$\leq 3\frac{1}{4}$	$\frac{5}{8}$	$\frac{3}{4}$
$3\frac{1}{2}$ – $6\frac{1}{2}$	$\frac{3}{4}$	1
≥ 7	1	$1\frac{1}{4}$

GENERAL NOTES:

Tie bolts shall conform to ASTM F1554 Grade 36 or ASTM A36. Nuts shall be heavy hex conforming to ASTM A563. Washers shall conform to ASTM F436.

Pipe Sleeve shall conform to ASTM A500 or A53, Grade B.

Galvanize adjustable eye bolt tie assembly in accordance with ASTM A153.



ADJUSTABLE EYE BOLT TIE


Pipe Dia. (in.)	"L" (in.)	Bolt Dia. (in.)
≤ 48	4	$\frac{3}{4}$
> 48	6	1

GENERAL NOTES:

Angles shall conform to ASTM A36.

Bolts shall conform to ASTM A307. Nuts shall be heavy hex conforming to ASTM A563. Washers shall conform to ASTM F436.

Galvanize angles, bolts, nuts, and washers in accordance with ASTM A153.




ANGLE AND BOLT TIE

GENERAL NOTES:


In lieu of the tie bolts detailed above other types of tie bolt connections may be installed as approved by the Office of Bridge Design.

All pipe sections of R.C.P. and R.C.P. Arch shall be tied with tie bolts except for pipe located between drop inlets, manholes, and junction boxes. All pipe sections of pipes that only enter or exit drop inlets, manhole, and junction boxes shall be tied with tie bolts.

There will be no separate measurement or payment for the tie bolts. The cost for furnishing and installing the tie bolts shall be incidental to the contract unit price per foot for the corresponding bid item for R.C.P. or R.C.P. Arch.



END VIEW
"CIRCULAR"



END VIEW
"ARCH"

REINFORCED CONCRETE PIPE TIE BOLTS

NOT TO SCALE


CITY OF BOX ELDER
STANDARD DETAIL RC014
CULVERT-RCP TIE BOLTS



DETAIL RC020-CULVERT-CMP-ARCH

	2 $\frac{2}{3}$ " x $\frac{1}{2}$ " CORRUGATIONS			3" X 1" CORRUGATIONS		
* Dia. (in.)	S Span (in.)	H Rise (in.)	Area (Sq. Ft.)	S Span (in.)	H Rise (in.)	Area (Sq. Ft.)
15	17	13	1.1			
18	21	15	1.6			
21	24	18	2.2			
24	28	20	2.8			
30	35	24	4.4			
36	42	29	6.4	40	31	7.0
42	49	33	8.7	46	36	9.4
48	57	38	11.4	53	41	12.3
54	64	43	14.3	60	46	15.6
60	71	47	17.6	66	51	19.3
66	77	52	21.3	73	55	23.2
72	83	57	25.3	81	59	27.4
78				87	63	32.1
84				95	67	37.0
90				103	71	42.4
96				112	75	48.0
102				117	79	54.2
108				128	83	60.8
114				137	87	67.4
120				142	91	74.5

* Equivalent diameter of circular C.M.P.



GENERAL NOTE:

All dimensions measured from inside crest.


CORRUGATED METAL PIPE ARCH CULVERT **NOT TO SCALE**

CITY OF BOX ELDER
STANDARD DETAIL RC020
CULVERT-CMP-ARCH




DETAIL RC021-CULVERT-CMP SLOTTED DRAIN-1


TYPICAL COUPLING BAND



TOP VIEW




FRONT VIEW




SECTION A-A


$\frac{2}{3}$ " x $\frac{1}{2}$ " Corrugations



TYPICAL SECTION



SECTION D-D



GRATE SLOT WELDING DETAIL

CORRUGATED METAL PIPE SLOTTED DRAIN-1

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RC021

CULVERT-CMP SLOTTED DRAIN 1



DETAIL RC022-CULVERT-CMP SLOTTED DRAIN-2



SLOTTED C.M.P. DRAIN

GENERAL NOTES:

A typical length of Slotted Drain is twenty (20) feet. Installation should be in multiples of ten (10) feet unless situations dictate otherwise.

All Slotted Drain materials and hardware shall be galvanized.

Metal end caps shall be provided for the closed end of each installation. The end caps shall be the same gage as the pipe.

All joints and end caps shall be watertight.

Close riveted soldered annular or continuously welded helical pipe shall be used and shall be watertight.

Units on which the spelter coating has been burned by welding or otherwise damaged in fabrication or during installation shall be regalvanized or painted with one full brush coat of zinc-rich paint conforming to Military Specification Mil-P-21035 or with at zinc-dust, zinc-oxide paint conforming to Federal Specification TT-P-641-B, Type III. Prior to painting, the surface shall be properly cleaned and approved.

Two gaskets will be required for each coupling band or joint and shall be rendered watertight by methods approved by the Engineer.

The slot shall be covered with an acceptable material during paving operations and/or installation of curb and gutter.

Anchors shall be " Dia. x 3" galvanized bolts and nuts. The nuts shall be welded to the slot at two (2) foot spacing. Bolts shall be added just prior to installation to avoid damage.

A trapezoidal design for spacer bars, either vertical or slanted, may be an alternate for the vertical bars shown on the details. The Slotted Drain with slanted spacer bars shall be installed with the slanted spacer bars oriented toward the flow.

A Heel Guard (1/2 inch #13 expanded metal mesh) shall be furnished when called for in the plans and shall be welded to the grating before delivery to the project.

Slotted Drain will be measured along the centerline of the pipe. The length shall be the overall installed length from end to end including any coupling bands that may be between sections. The outlet pipe will be paid for as CMP and End Sections.

Slotted Drain will be paid for at the contract unit price per Foot of Slotted C.M.P. Payment will be full compensation for materials, labor, equipment, and incidentals required.

CORRUGATED METAL PIPE SLOTTED DRAIN-2

NOT TO SCALE




CITY OF BOX ELDER

STANDARD DETAIL RC022

CULVERT-CMP SLOTTED DRAIN 2



DETAIL RC023-CULVERT-CMP ELBOWS

 2 Piece 5 to 45° Elbow			 2 Piece 50 to 90° Elbow			 3 Piece 90° Elbow				
Diameter	A	L	Diameter	A	L	Diameter	A	B	C	L
Inches	Feet	Feet	Inches	Feet	Feet	Inches	Inches			Feet
12	1	2	12	2	4	12	25?	11	18?	4
15	1	2	15	2	4	15	26?	12	18	4
18	1	2	18	2	4	18	27	14	17	4
21	2	4	21	2	4	21	27	15	16?	4
24	2	4	24	2	4	24	27?	16	16	4
27	2	4	27	2	4	27	27?	17	15?	4
30	2	4	30	3	6	30	40	19	26?	6
33	2	4	33	3	6	33	40	20	26	6
36	2	4	36	3	6	36	40?	21	25?	6
42	2	4	42	3	6	42	41	23	24?	6
48	2	4	48	4	8	48	53?	26	35	8
54	3	6	54	4	8	54	54	28	34	8
60	3	6	60	4	8	60	54?	31	32?	8
66	3	6	66	4	8	66	54	33	31?	8
72	3	6	72	5	10	72	67?	36	42	10
78	3	6	78	5	10	78	68	39	40?	10
84	3	6	84	5	10	84	68?	41	39?	10
90	3	6	90	6	12	90	70	46	37	10
96	3	6	96	6	12	96	82	46	49	12

FABRICATED ELBOW LENGTHS FOR ALL CORRUGATIONS

GENERAL NOTES:

All dimensions shown are nominal.

L = Linear Feet of C.M.P. required to fabricate fitting.




CORRUGATED METAL PIPE FABRICATED LENGTHS FOR ELBOWS **NOT TO SCALE**

CITY OF BOX ELDER
STANDARD DETAIL RC023
CULVERT-CMP ELBOWS




DETAIL RC024-CULVERT-CMP FLARED ENDS-ROUND

Alternate Type Connector Sections may be used with approval of the Engineer.



TUBING ATTACHMENT DETAILS SECTION A-A



TYPICAL CROSS-SECTION

GENERAL NOTES:



All 3 pc. bodies shall have 12 Ga. sides and 10 Ga. center panels. Width of center panels shall be greater than 20% of the pipe periphery. Multiple panel bodies to have lap seams tightly joined by ... Dia. galvanized rivets or bolts.

For 60" through 84" sizes, reinforced edges shall be supplemented with galvanized stiffener angles. The angles will be 2" x 2" x " for 60" through 72" diameters and 2" x 2" x " for 78" and 84" diameters. The angles shall be attached by ... diameter galvanized nuts and bolts.




Rivets and Bolts shall be ... Dia. Min. for 10 Ga. and 12 Ga. sheet, and 5" Dia. Min. for 14 Ga. and 16 Ga. sheets. Tighten nuts with torque wrench to 25 lbs. torque.

Dia. D (in.)	Ga.	DIMENSIONS (in.)					Approx. Slope	Body
		A	B	H	L	W		
12	16	6	6	6	21	24	2?:1	1 Pc.
15	16	7	8	6	26	30	2?:1	1 Pc.
18	16	8	10	6	31	36	2?:1	1 Pc.
21	16	9	12	6	36	42	2?:1	1 Pc.
24	16	10	13	6	41	48	2?:1	1 Pc.
30	14	12	16	8	46	60	2?:1	1 Pc.
36	14	14	19	9	51	72	2?:1	2 Pc.
42	12	16	22	11	60	84	2?:1	2 Pc.
48	12	18	27	12	69	90	2?:1	2 Pc.
54	12	18	30	12	78	102	2:1	3 Pc.
60	12	18	33	12	84	114	1?:1	3 Pc.
66	12	18	36	12	87	120	1?:1	3 Pc.
72	12	18	39	12	87	126	1 1/3:1	3 Pc.
78	12	18	42	12	87	132	1?:1	3 Pc.
84	12	18	45	12	87	138	1 1/6:1	3 Pc.

STANDARD CONNECTIONS



NOTE:
Tubing is slipped over the sheet and rivets or lugs prior to forming operations of the apron.



CORRUGATED METAL PIPE FLARED ENDS-ROUND

NOT TO SCALE




CITY OF BOX ELDER

STANDARD DETAIL RC024


CULVERT-CMP FLARED ENDS-ROUND



DETAIL RC025-CULVERT-CMP FLARED ENDS-ARCH



... x " Gal. Buttonhead Rivets spaced 6" C. to C. Overall length of rivets=0.78"
TUBING ATTACHMENT DETAILS SECTION A-A



GENERAL NOTES:


All 3 pc. bodies shall have 12 Ga. sides and 10 Ga. center panels. Width of center panels shall be greater than 20% of the pipe periphery. Multiple panel bodies shall have lap seams tightly joined by ... Dia. galvanized rivets or bolts.

For 77" x 52" and 83" x 57" sizes, reinforced edges shall be supplemented with galvanized stiffener angles. The angles will be 2" x 2" x 1/4" for both the 77" x 52" size and the 83" x 57" size. The angles shall be attached by ... Dia. galvanized nuts and bolts.

Rivets and Bolts shall be ... Dia. Min. for 10 Ga. and 12 Ga. sheet, and 5/8" Dia. Min. for 14 Ga. and 16 Ga. sheets. Tighten nuts with torque wrench to 25 lbs. torque.

Span x Rise (in.)x(in.)	Equiv. Dia. (in.)	Ga.	APPROX. DIMENSIONS (in.)					Approx. Slope	Body
			A	B	H	L	W		
17x13	15	16	7	9	6	19	30	2?:1	1 Pc.
21x15	18	16	7	10	6	23	36	2?:1	1 Pc.
24x18	21	16	8	12	6	28	42	2?:1	1 Pc.
28x20	24	16	9	14	6	32	48	2?:1	1 Pc.
35x24	30	14	10	16	6	39	60	2?:1	1 Pc.
42x29	36	14	12	18	8	46	75	2?:1	1 Pc.
49x33	42	12	13	21	9	53	85	2?:1	2 Pc.
57x38	48	12	16	26	12	63	90	2?:1	2 Pc.
64x43	54	12	18	30	12	70	102	2?:1	2 Pc.
71x47	60	12	18	33	12	77	114	2?:1	3 Pc.
77x52	66	12	18	36	12	77	126	2:1	3 Pc.
83x57	72	12	18	39	12	77	133	2:1	3 Pc.


STANDARD CONNECTIONS




① For 17" through 28" span pipe—arches a flat strap connector may be used in place of the rod connection. Strap connector shall be 1" wide, 12 ga. strap with standard 6" long x " dia. bond bolt and nut.

NOTE:

Tubing is slipped over the sheet and rivets or lugs prior to forming operations of the apron.



SECTION A-A (alternate)



SECTION A-A (alternate)

CORRUGATED METAL PIPE FLARED ENDS-ARCH

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RC025

CULVERT-CMP FLARED ENDS-ARCH










DETAIL RC026-CULVERT-CMP SLOPED ENDS-1




* Number of bars required will vary depending on the length of the end section.

When bars are specified in the plans, the cross drainage bar is required when span is over 30". Cross bar to be welded to parallel bars to make one piece unit.



(For 30" and Larger)
(For 21" X 15" and Larger)

1/2" x 6" Culvert bolt with flanged nut



(For 15" Through 24")

CORRUGATED METAL PIPE SLOPED ENDS-1 **NOT TO SCALE**

CITY OF BOX ELDER
STANDARD DETAIL RC026
CULVERT-CMP SLOPED ENDS 1



DETAIL RC027-CULVERT-CMP SLOPED ENDS-2

ARCH C.M.P. SLOPED ENDS										
Equiv. Dia. (Inch)	(Inches)		Min. Thick.		Dimensions (Inches)				L Dimensions	
	Span	Rise	Inch	Gage	A	H	W	Overall Width	Slope	Length (Inch)
18	21	15	.064	16	8	6	27	43	4:1	20
21	24	18	.064	16	8	6	30	46	4:1	32
24	28	20	.064	16	8	6	34	50	4:1	40
30	35	24	.079	14	12	9	41	65	4:1	56
36	42	29	.109	12	12	9	48	72	4:1	76
42	49	33	.109	12	16	12	55	87	4:1	92
48	57	38	.109	12	16	12	63	95	4:1	112
54	64	43	.109	12	16	12	70	102	4:1	132
60	71	47	.109	12	16	12	77	109	4:1	148
72	83	57	.109	12	16	12	89	121	4:1	188

CIRCULAR C.M.P. SLOPED ENDS								
Pipe Dia. (Inch)	Min. Thick.		Dimensions (Inches)				L Dimensions	
	Inch	Gage	A	H	W	Overall Width	Slope	Length (Inch)
15	.064	16	8	6	21	37	4:1	20
18	.064	16	8	6	24	40	4:1	32
21	.064	16	8	6	27	43	4:1	44
24	.064	16	8	6	30	46	4:1	56
30	.109	12	12	9	36	60	4:1	80
36	.109	12	12	9	42	66	4:1	104
42	.109	12	16	12	48	80	4:1	128
48	.109	12	16	12	54	86	4:1	152
54	.109	12	16	12	60	92	4:1	176
60	.109	12	16	12	66	98	4:1	200

GENERAL NOTES:

Safety bars shall be attached to sloped ends over 30" in diameter only when specified in the plans.

Sloped ends shall be fabricated from galvanized steel and shall conform to the requirements of the Specifications.

Safety bars shall be fabricated from steel schedule 40 pipe in conformance with ASTM A53, grade B or HSS 3.5X.216 in conformance with ASTM A500, grade B.

Slotted holes for safety bar attachment shall be provided for all end sections.


Attachment to circular pipes 15" through 24" diameter shall be made with Type #1 straps. All other sizes shall be attached with Type #2 rods and lugs.

When stated in the plans, optional toe plate extension shall be punched and bolted to end section apron lip with 3/8" diameter galvanized bolts. Steel for toe plate extension shall be same gauge as end section. Dimensions shall be overall width less 6" by 8" high.

Cost of all work and materials required for fabrication and installation of sloped ends shall be incidental to the bid items for the various sizes of sloped ends.

CORRUGATED METAL PIPE SLOPED ENDS-2**NOT TO SCALE****CITY OF BOX ELDER****STANDARD DETAIL RC027****CULVERT-CMP SLOPED ENDS 2**

DETAIL RC028-CULVERT CMP-RCP TRANSITIONS



GENERAL NOTE:


Arch pipe transitions shall be fabricated similar to the round transition shown above.

**CORRUGATED METAL PIPE (CMP) TO REINFORCED CONCRETE PIPE (RCP)
AND RCP TO CMP TRANSITIONS**
NOT TO SCALE



DETAIL RC029-CULVERT-CMP SMOOTH TAPERED SLEEVE

Bolt Sleeve at outlet only in 4 places at 90° to each other with 1/2" Hex Head bolts, 2 round washers, and nut. Place Mastic over each bolt head on the inside.



SMOOTH TAPERED SLEEVE DETAIL

GENERAL NOTE:

Metal shall be 12 gauge smooth Galvanized in accordance with AASHTO M218.

CORRUGATED METAL PIPE SMOOTH TAPERED SLEEVE

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RC029

CULVERT-CMP SMOOTH TAPERED SLEEVE



DETAIL RC040-CULVERT-PRECAST BOX BARREL TIE




TYPICAL SINGLE BARREL VIEW A - A

ELEVATION

LEGEND FOR PLACING RE-STEEL

I. F. W. - Inside Face Wall

RISE	"X"
3'- 0"	3"
4'- 0"	9"
5'- 0"	6"
6'- 0"	3"
7'- 0"	9"
8'- 0"	6"
9'- 0"	3"
10'- 0"	9"
11'- 0"	6"
12'- 0"	3"



TYPICAL MULTIPLE BARREL VIEW A - A

GENERAL NOTES:

1. z1 bars shall be placed in the middle of the 2" x 3" keyway in the top and bottom slabs. z1 bars shall be lapped with the longitudinal p bars in the inside face of the wall for outside walls and in either face for interior walls. z1 bars are listed and included elsewhere in plans.
2. Drainage Fabric Protection shall be placed in accordance with Section 422 or Section 560, whichever is applicable.

CULVERT-PRECAST BOX BARREL TIE REINFORCEMENT NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RC040

CULVERT-PRECAST BOX BARREL TIE



DETAIL RC041-CULVERT-PRECAST BOX TIE BOLT ASSEMBLY



TIE BOLT ASSEMBLY

GENERAL NOTES:

1. All holes for tie bolts shall be cast-in-place, 16 inches from outside edge of joint. Cast in inserts or sleeves, if used, shall be made of a corrosion resistant material.
2. Ties shall be 1 inch ϕ and conform to the requirements of ASTM A36, ASTM A307, or ASTM F1554, Gr. 36. Nuts shall be heavy hex in conformance with ASTM A563. Washers shall conform to ASTM F436, Type 1. The welded pipe sleeve shall conform to ASTM A53, Grade B.
3. Welding and weld inspection shall be in conformance with AWS/ANSI D1.1 - (Current Year) Structural Welding Code - Steel.
4. Tie Bolt Assembly shall be galvanized in accordance with ASTM A153 or ASTM F2329 as applicable.
5. Tie Bolt Assembly details may vary from that shown, but alternate tie bolt assemblies are subject to testing to demonstrate equal strength. Submit details, through proper channels, to the Office of Bridge Design for approval.
6. All costs for furnishing and installing the precast box culvert tie bolt assembly shall be incidental to the contract unit price per Foot for "Precast Concrete Box Culvert, Furnish".


PRECAST BOX CULVERT TIE BOLT ASSEMBLY

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RC041
CULVERT-PRECAST BOX TIE BOLT ASSEMBLY





DETAIL RC042-CULVERT-PRECAST BOX SLOPED END SECTION





CUTOFF WALL

1. All costs associated with furnishing and installing the Cutoff Wall, whether precast or cast-in-place, shall be incidental to the contract unit price per each for "Precast Box Culvert End Section, Furnish".
2. Concrete for cast-in-place cutoff wall shall be Class M6 concrete in accordance with Section 462 of the Specifications.
3. All reinforcing steel shall conform to ASTM A615 Grade 60.
4. Alternate details will be allowed, subject to the approval of the Bridge Construction Engineer.



NOTE: Joint details may vary from that shown, according to the manufacturer's design. Submit details with shop plans for approval.



LEGEND

W = Width of Opening
H = Height of Opening
Tt = Thickness of Top Slab
Tb = Thickness of Bottom Slab
Ts = Thickness of Side Wall
L = Length of End Section




NOTES:
See GENERAL DRAWING for W and H dimensions.
Tt, Tb, L, and Ts dimensions shall be furnished by the Contractor.
× Length and number of units may vary from that shown.

PRECAST BOX CULVERT WITH SLOPED END SECTION NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RC042
CULVERT-PRECAST BOX SLOPED END SECTION




DETAIL RC045-CULVERT-PRECAST DOUBLE BOX WITH SLOPED END-2' CUTOFF WALL




PRECAST DOUBLE BOX CULVERT WITH SLOPED END (2' CUTOFF WALL)
NOT TO SCALE

CUTOFF WALL

1. All costs associated with furnishing and installing the Cutoff Wall, whether precast or cast-in-place, shall be incidental to the contract unit price per each for "Precast Box Culvert End Section, Furnish".
2. Concrete for cast-in-place cutoff wall shall be Class M6 concrete in accordance with Section 462 of the Specifications.
3. All reinforcing steel shall conform to ASTM A615 Grade 60.
4. Alternate details will be allowed, subject to the approval of the Bridge Construction Engineer.



NOTE: Joint details may vary from that shown, according to the manufacturer's design. Submit details with shop plans for approval.



LEGEND

W = Width of Opening
H = Height of Opening
Tt = Thickness of Top Slab
Tb = Thickness of Bottom Slab
Ts = Thickness of Side Wall
Tm = Thickness of Middle Wall
L = Length of End Section

NOTES:
See GENERAL DRAWING for W and H dimensions.
Tt, Tb, Tm, L, and Ts dimensions shall be furnished by the Contractor.
* Length and number of units may vary from that shown.


CITY OF BOX ELDER

STANDARD DETAIL RC045


CULVERT-PRECAST DOUBLE BOX-2'




DETAIL RC046-CULVERT-PRECAST DOUBEL BOX WITH SLOPED END-4' CUTOFF WALL



PLAN
(Inlet or Outlet)




ELEVATION
(Inlet or Outlet)



VIEW A - A


CUTOFF WALL

1. All costs associated with furnishing and installing the Cutoff Wall, whether precast or cast-in-place, shall be incidental to the contract unit price per each for "Precast Box Culvert End Section, Furnish".
2. Concrete for cast-in-place cutoff wall shall be Class M6 concrete in accordance with Section 462 of the Specifications.
3. All reinforcing steel shall conform to ASTM A615 Grade 60.
4. Alternate details will be allowed, subject to the approval of the Bridge Construction Engineer.



DETAIL "X"

NOTE: Joint details may vary from that shown, according to the manufacturer's design. Submit details with shop plans for approval.



SEC. C - C

LEGEND

- W = Width of Opening
H = Height of Opening
Tt = Thickness of Top Slab
Tb = Thickness of Bottom Slab
Ts = Thickness of Side Wall
Tm = Thickness of Middle Wall
L = Length of End Section

NOTES:
See GENERAL DRAWING for W and H dimensions.
Tt, Tb, Tm, L, and Ts dimensions shall be furnished by the Contractor.
× Length and number of units may vary from that shown.


PRECAST DOUBLE BOX CULVERT WITH SLOPED END (4' CUTOFF WALL)

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RC046
CULVERT-PRECAST DOUBLE BOX-4'



DETAIL RC050-CULVERT-SLOPE TRANSITIONS TYPE-1



GENERAL NOTES:

This Type 1 Inslope Transition is used when the specified inslope at the drainage structure is flatter than the typical inslope and the inslope at the drainage structure is between a 4:1 slope and 6:1 slope.

Line B-B represents the clear zone line, the location where soil intercepts the parapet on an RCBC, the location where the soil intercepts the top of the pipe adjacent to the opening of the pipe end section, or may represent a change in slope.

* Transition from the typical inslope to the inslope at the drainage structure. Within the clear zone (area from edge of subgrade shoulder to line B-B) use 100' length for each 1:1 slope change. Example: transition from a 4:1 to a 6:1 would require a 200' length transition. The typical inslope outside of the clear zone will be transitioned gradually to the slope necessary adjacent to the RCBC wing wall or pipe culvert end section within the transition length necessary for the transition within the clear zone.

SLOPE TRANSITIONS AT PIPE CULVERTS OR REINFORCED CONCRETE BOX CULVERTS-TYPE 1

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RC050

CULVERT-SLOPE TRANSITIONS-1



DETAIL RC051-CULVERT-SLOPE TRANSITIONS-TYPE-2



GENERAL NOTES:

This Type 2 Inslope Transition is used when the specified inslope at the pipe or RCBC is flatter than a 6:1 slope.

Line B-B represents the clear zone line, the location where soil intercepts the parapet on an RCBC, the location where the soil intercepts the top of the pipe adjacent to the opening of the pipe end section, or may represent a change in slope.

Transition from Inslope at drainage structure to a 6 : 1 inslope and 3:1 inslope.


- * Transition from typical inslope to the inslopes adjacent to the drainage structure. Within the clear zone (area from edge of subgrade shoulder to line B-B) use 100' length for each 1:1 slope change. Example: transition from a 4:1 to a 6:1 would require a 200' length
- ** transition. The typical inslope outside of the clear zone will be transitioned to a 3:1 inslope within the transition length necessary for the transition within the clear zone.

SLOPE TRANSITIONS AT PIPE CULVERTS OR REINFORCED CONCRETE BOX CULVERTS-TYPE 2 NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RC051
CULVERT-SLOPE TRANSITIONS-2



DETAIL RD001-DROP INLET-CONCRETE-TYPE B (2X3)-1



ESTIMATED QUANTITIES			
ITEM	UNIT	CONSTANT QUANTITY	VARIABLE QUANTITY
Class M6 Concrete	Cu. Yd.	0.26	0.22H
Reinforcing Steel	Lb.	83.03	28.97H
Frame and Grate Assembly	Each	1	

DROP INLETS FOR 12" TO 24" DIAMETER PIPE

SPECIFICATIONS

Design Specifications: AASHTO LRFD Bridge Design Specifications, current edition.

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, Current Edition and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES:

Design Live Load: HL-93. No construction loading in excess of legal load was considered.

Reinforcing steel shall conform to ASTM A615 grade 60. The d bars shall be lapped 12 inches with the b and c bars. Cut and bend reinforcing steel as required to place pipe(s) through the drop inlet wall.

Drop inlet may be precast. If precast drop inlet details differ from this standard plate, submit a checked design done by a SD registered P.E. and shop plan to the Engineer for approval.

Reduce total quantities of concrete by the amount of concrete displaced by the pipe(s). The total quantity of concrete shall be computed to the nearest hundredth of a cubic yard. The total quantity of reinforcing steel shall be computed to the nearest pound.

Drop inlet shown may be modified by the addition or omission of connecting pipes as noted elsewhere in the plans. All pipes entering drop inlet must fit between the inside face of walls and shall not enter through the corners.

Maximum R.C.P. diameter shall not exceed 18 inches on the 2-foot wide side and shall not exceed 24 inches (24 inches for R.C. arch) on the 3-foot wide side of the drop inlet.

The dimension of H is in feet. Maximum H is 10 feet.


PIPE DISPLACEMENT REDUCTIONS		
Diameter (Inches)	Wall T (Inches)	Class M6 Concrete (Cu. Yd.)
12	2	0.03
15	2 1/4	0.04
18	2 1/2	0.05
24	3	0.09
18	2 1/2	0.05
24	3 1/2	0.09

DROP INLET-CONCRETE-TYPE B (2'X3') NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD001
DROP INLET-CONC.-TYPE B-2X3-1



DETAIL RD002-DROP INLET-CONCRETE-TYPE B (2X3)-2




REINFORCING SCHEDULE											
Mk.	No.	Size	Length	Type	Bending Details						
a	2.67H	4	8' - 0"	17	Type 17						
b	5	5	6' - 3"	17							
c	6	4	5' - 3"	17							
d	22	4	H - 2"	Str.							
NOTE: All dimensions are out to out of bars.											
					<table><tr><td>a</td><td>2' - 2 1/2"</td></tr><tr><td>b</td><td>1' - 3 1/2"</td></tr><tr><td>c</td><td>1' - 3 1/2"</td></tr></table>	a	2' - 2 1/2"	b	1' - 3 1/2"	c	1' - 3 1/2"
a	2' - 2 1/2"										
b	1' - 3 1/2"										
c	1' - 3 1/2"										

DROP INLET-CONCRETE-TYPE B (2'X3')
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD002
DROP INLET-CONC.-TYPE B-2X3-2



DETAIL RD003-DROP INLET-CONCRETE-TYPE B (3X4)-1



ESTIMATED QUANTITIES			
ITEM	UNIT	CONSTANT QUANTITY	VARIABLE QUANTITY
Class M6 Concrete	Cu. Yd.	0.72	0.30H
Reinforcing Steel	Lb.	130.93	36.54H
Frame and Grate Assembly	Each	1	

DROP INLETS FOR 12" TO 36" DIAMETER PIPE

SPECIFICATIONS

Design Specifications: AASHTO LRFD Bridge Design Specifications, current edition.

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, Current Edition and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES:

Design Live Load: HL-93. No construction loading in excess of legal load was considered.

Reinforcing steel shall conform to ASTM A615 grade 60. The d bars shall be lapped 12 inches with the b and c bars. Cut and bend reinforcing steel as required to place pipe(s) through the drop inlet wall.

Drop inlet may be precast. If precast drop inlet details differ from this standard plate, submit a checked design done by a SD registered P.E. and shop plans to the Engineer for approval.

Reduce total quantities of concrete by the amount of concrete displaced by the pipe(s). The total quantity of concrete shall be computed to the nearest hundredth of a cubic yard. The total quantity of reinforcing steel shall be computed to the nearest pound.

Drop inlet shown may be modified by the addition or omission of connecting pipes as noted elsewhere in the plans. All pipes entering drop inlet must fit between the inside face of walls and shall not enter through the corners.

Maximum R.C.P. diameter shall not exceed 24 inches (24 inches for R. C. arch) on the 3-foot wide side and shall not exceed 36 inches (30 inches for R. C. arch) on the 4-foot wide side of the drop inlet.

The dimension of H is in feet. Maximum H is 10 feet.

PIPE DISPLACEMENT REDUCTIONS		
Diameter (Inches)	Wall T (Inches)	Class M6 Concrete (Cu. Yd.)
12	2	0.03
15	2 1/4	0.04
18	2 1/2	0.05
24	3	0.09
30	3 1/2	0.14
36	4	0.20
18	2 1/2	0.05
24	3 1/2	0.09
30	4	0.14


DROP INLET-CONCRETE-TYPE B (3'X4')

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD003
DROP INLET-CONC.-TYPE B-3X4-1



DETAIL RD004-DROP INLET-CONCRETE-TYPE B (3X4)-2




REINFORCING SCHEDULE				
Mk.	No.	Size	Length	Type
a	2.67H	4	10'-0"	17
b	7	4	7'-6"	17
c	7	4	6'-6"	17
d	28	4	H + 9"	S17
e	28	4	2'-3"	S19
f	2	4	7'-0"	17

NOTE:
All dimensions are out to out of bars.

Bending Details

Type S17

Type S19




DROP INLET-CONCRETE-TYPE B (3'X4')
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD004
DROP INLET-CONC.-TYPE B-3X4-2



DETAIL RD005-DROP INLET-CONCRETE-TYPE B (3X5.5)-1



ESTIMATED QUANTITIES			
ITEM	UNIT	CONSTANT QUANTITY	VARIABLE QUANTITY
* Class M6 Concrete	Cu. Yd.	1.02	0.35H
Reinforcing Steel	Lb.	130.93	31.2H
Frame and Grate Assembly	Each	1	

DROP INLETS FOR 12" TO 54" DIAMETER PIPE

SPECIFICATIONS

Design Specifications: AASHTO LRFD Bridge Design Specifications, current edition.

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, Current Edition and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES

Design Live Load: HL-93. No construction loading in excess of legal load was considered.

Reinforcing steel shall conform to ASTM A615 grade 60. The d and e bars shall be lapped 12 inches with the c and b bars, respectively. Cut and bend reinforcing steel as required to place pipe(s) through the drop inlet wall.

Drop inlet may be precast. If precast drop inlet details differ from this standard plate, submit a checked design done by a SD registered P.E. and shop plans to the Engineer for approval.

- * Reduce total quantities of concrete by the amount of concrete displaced by the pipe(s). The total quantity of concrete shall be computed to the nearest hundredth of a cubic yard. The total quantity of reinforcing steel shall be computed to the nearest pound.

Drop inlet shown may be modified by the addition or omission of connecting pipes as noted elsewhere in the plans. All pipes entering drop inlet must fit between the inside face of walls and shall not enter through the corners.

Maximum R.C.P. diameter shall not exceed 24 inches (24 inches for R. C. arch) on the 3-foot wide side and shall not exceed 54 inches (42 inches for R.C. arch) on the 5.5-foot wide side of the drop inlet.

The dimension of H is in feet. Maximum H is 10 feet.

PIPE DISPLACEMENT REDUCTIONS

	Diameter (Inches)	Wall T (Inches)	Class M6 Concrete (Cu. Yd.)
R.C.P.	12	2	0.03
	15	2 1/4	0.04
	18	2 1/2	0.05
	24	3	0.09
	30	3 1/2	0.14
	36	4	0.20
	42	4 1/2	0.26
R.C. ARCH	48	5	0.34
	54	5 1/2	0.43
	18	2 1/2	0.05
	24	3 1/2	0.09
	30	4	0.14
	36	4 1/2	0.19
	42	4 1/2	0.24

DROP INLET-CONCRETE-TYPE B (3'X5.5')

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RD005

DROP INLET-CONC.-TYPE B-3X5.5-1




DETAIL RD006-DROP INLET-CONCRETE-TYPE B (3X5.5)-2




SEC. A - A

SEC. B - B



DETAIL "X"



DETAIL "Y"

REINFORCING SCHEDULE

Mk.	No.	Size	Length	Type	Bending Details
a	2.67H	4	11' - 6"	17	16 3/4" e 7 3/4" d 3 1/2" d 3 1/2" e 4 3/8" 12 9 1'-6" Type S19 3 1/2" 1 10 1/2" Type S19 3'-6" 3'-6 1/2" 6'-0 1/2" 6'-0 1/2" a 2'-8 3/4" b 1'-5 3/4" c 1'-5 3/4" h 1'-9" Type 17
b	8	4	9' - 0"	17	
c	8	4	6' - 6"	17	
d	8	4	H + 9"	S17	
e	8	4	H + 18"	S17	
f	8	4	2' - 3"	S19	
g	8	4	2' - 9"	S19	
h	2	4	7' - 0"	17	

NOTE:
All dimensions are out to out of bars.

Type S17

Type S19

Type 17

DROP INLET-CONCRETE-TYPE B (3'X5.5')

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RD006

DROP INLET-CONC.-TYPE B-3X5.5-2



DETAIL RD007-DROP INLET-CONCRETE-TYPE B (4X4)-1



ESTIMATED QUANTITIES			
ITEM	UNIT	CONSTANT QUANTITY	VARIABLE QUANTITY
Class M6 Concrete	Cu. Yd.	0.98	0.33H
Reinforcing Steel	Lb.	180.69	43.67H
Frame and Grate Assembly	Each	1	—

DROP INLETS FOR 12" TO 36" DIAMETER PIPE

SPECIFICATIONS

Design Specifications: AASHTO LRFD Bridge Design Specifications, current edition.

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, Current Edition and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES:

Design Live Load: HL-93. No construction loading in excess of legal load was considered.

Reinforcing steel shall conform to ASTM A615 grade 60. The d bars shall be lapped 12 inches with the b and c bars. Cut and bend reinforcing steel as required to place pipe(s) through the drop inlet wall.

Drop inlet may be precast. If precast drop inlet details differ from this standard plate, submit a checked design done by a SD registered P.E. and shop plans to the Engineer for approval.

Reduce total quantities of concrete by the amount of concrete displaced by the pipe(s). The total quantity of concrete shall be computed to the nearest hundredth of a cubic yard. The total quantity of reinforcing steel shall be computed to the nearest pound.

Drop inlet shown may be modified by the addition or omission of connecting pipes as noted elsewhere in the plans. All pipes entering drop inlet must fit between the inside face of walls and shall not enter through the corners.

Maximum R.C.P. diameter shall not exceed 36 inches (30 inches for R. C. arch) on the 4-foot wide side of the drop inlet.

The dimension of H is in feet. Maximum H is 10 feet.


PIPE DISPLACEMENT REDUCTIONS		
Diameter (Inches)	Wall T (Inches)	Class M6 Concrete (Cu. Yd.)
12	2	0.03
15	2 1/4	0.04
18	2 1/2	0.05
24	3	0.09
30	3 1/2	0.14
36	4	0.20
18	2 1/2	0.05
24	3 1/2	0.09
30	4	0.14

DROP INLET-CONCRETE-TYPE B (4'X4') NOT TO SCALE

CITY OF BOX ELDER
 STANDARD DETAIL RD007
 DROP INLET-CONC.-TYPE B-4X4-1



DETAIL RD008-DROP INLET-CONCRETE-TYPE B (4X4)-2




REINFORCING SCHEDULE						
Mk.	No.	Size	Length	Type	Bending Details	
a	2.67H	4	11'- 0"	17		
b	18	4	7'- 6"	17		
c	18	4	H + 15"	S17		
d	18	4	H + 9"	S17		
e	18	4	2'- 6"	S19		
f	18	4	2'- 3"	S19		
g	2	4	7'- 0"	17		
NOTE: All dimensions are out to out of bars.						

DROP INLET-CONCRETE-TYPE B (4'X4') NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD008
DROP INLET-CONC.-TYPE B-4X4-2



DETAIL RD009-DROP INLET-CONCRETE- TYPE B (5.5X3)-1



ESTIMATED QUANTITIES			
ITEM	UNIT	CONSTANT QUANTITY	VARIABLE QUANTITY
Class M6 Concrete	Cu. Yd.	1.03	0.35H
Reinforcing Steel	Lb.	161.19	47.89H
Grate Assembly	Each	1	

DROP INLETS FOR 12" TO 54" DIAMETER PIPE

SPECIFICATIONS

Design Specifications: AASHTO LRFD Bridge Design Specifications, current edition.

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, Current Edition and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES:

Design Live Load: HL-93. No construction loading in excess of legal load was considered.

Reinforcing steel shall conform to ASTM A615 grade 60. The d bars shall be lapped 12 inches with the b and c bars. Cut and bend reinforcing steel as required to place pipe(s) through the drop inlet wall.

Drop inlet may be precast. If precast drop inlet details differ from this standard plate, submit a checked design done by a SD registered P.E. and shop plans to the Engineer for approval.

Reduce total quantities of concrete by the amount of concrete displaced by the pipe(s). The total quantity of concrete shall be computed to the nearest hundredth of a cubic yard. The total quantity of reinforcing steel shall be computed to the nearest pound.

Drop inlet shown may be modified by the addition or omission of connecting pipes as noted elsewhere in the plans. All pipes entering drop inlet must fit between the inside face of walls and shall not enter through the corners.

Maximum R.C.P. diameter shall not exceed 54 inches (42 inches for R. C. arch) on the 5.5-foot wide side and shall not exceed 24 inches (24 inches for R. C. arch) on the 3-foot wide side of the drop inlet.

The dimension of H is in feet. Maximum H is 10 feet.

PIPE DISPLACEMENT REDUCTIONS

	Diameter (Inches)	Wall T (Inches)	Class M6 Concrete (Cu. Yd.)
R.C.P.	12	2	0.03
	15	2 1/4	0.04
	18	2 1/2	0.05
	24	3	0.09
	30	3 1/2	0.14
	36	4	0.20
	42	4 1/2	0.26
R.C. ARCH	48	5	0.34
	54	5 1/2	0.43
	18	2 1/2	0.05
	24	3 1/2	0.09
	30	4	0.14
	36	4 1/2	0.19
	42	4 1/2	0.24

DROP INLET-CONCRETE-TYPE B (5.5'x3')

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RD009

DROP INLET-CONC.-TYPE B-5.5X3-1



DETAIL RD010-DROP INLET-CONCRETE-TYPE B (5.5X3)-2



REINFORCING SCHEDULE				
Mk.	No.	Size	Length	Type
a	2.67H	4	11'- 6"	17
b	8	4	9'- 0"	17
c	8	4	6'- 6"	17
d	16	4	H - 2"	Str.
e	16	5	H + 24"	S17
f	16	4	3'- 6"	S19
g	2	4	7'- 0"	17

Bending Details

g	c	b	a
3'- 6"	3'- 6 1/2"	6'- 0 1/2"	6'- 0 1/2"

NOTE:
All dimensions are out to out of bars.


a	2'- 8 3/4"
b	1'- 5 3/4"
c	1'- 5 3/4"
g	1'- 9"

Type 17

Type S17

Type S19

DETAIL RD011-DROP INLET-CONCRETE-TYPE B (5.5X5.5)-1



DROP INLETS FOR 12" TO 54" DIAMETER PIPE

SPECIFICATIONS

Design Specifications: AASHTO LRFD Bridge Design Specifications, current edition.

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, Current Edition and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES:

Design Live Load: HL-93. No construction loading in excess of legal load was considered.

Reinforcing steel shall conform to ASTM A615 grade 60. The c bars shall be lapped 12 inches with the b bars. Cut and bend reinforcing steel as required to place pipe(s) through the drop inlet wall.

Drop inlet may be precast. If precast drop inlet details differ from this standard plate, submit a checked design done by a SD registered P.E. and shop plans to the Engineer for approval.


- * Reduce total quantities of concrete by the amount of concrete displaced by the pipe(s). The total quantity of concrete shall be computed to the nearest hundredth of a cubic yard. The total quantity of reinforcing steel shall be computed to the nearest pound.

Apply a thin layer of grout between the drop inlet and cover to ensure uniform bearing. Grout shall conform to the specifications.

Drop inlet shown may be modified by the addition or omission of connecting pipes as noted elsewhere in the plans. All pipes entering drop inlet must fit between the inside face of walls and shall not enter through the corners.

Maximum R.C.P. diameter shall not exceed 54 inches (42 inches for R. C. arch) of the drop inlet.

The dimension of H is in feet. Maximum H is 10 feet.



DROP INLET-CONCRETE-TYPE B (5.5'X5.5')

NOT TO SCALE



CITY OF BOX ELDER

STANDARD DETAIL RD011

DROP INLET-CONC.-TYPE B-5.5X5.5-1



DETAIL RD012-DROP INLET-CONCRETE-TYPE B (5.5X5.5)-2



ESTIMATED QUANTITIES			
ITEM	UNIT	CONSTANT QUANTITY	VARIABLE QUANTITY
Class M6 Concrete	Cu. Yd.	2.46	0.44H
Reinforcing Steel	Lb.	380.09	58.37H
Frame and Grate Assembly	Each	1	—

REINFORCING SCHEDULE				
Mk.	No.	Size	Length	Type
a	2.67H	4	14'-0"	17
b	25	4	9'-0"	17
c	50	4	H + 9"	S17
d	50	4	2'-3"	S19
e	2	4	10'-6"	17
f	18	4	6'-0"	Str.
g	14	4	1'-9"	Str.
h	10	4	1'-3"	Str.
j	4	4	7'-0"	17

NOTE:
All dimensions are out to out of bars.

Bending Details				
	a	6'-0 1/2"	b	9'-5 3/4"
	e	2'-9"	j	1'-9"

Type 17

	c	7 3/4"	d	10 1/2"
	1		3 1/2"	

Type S19

	c	7 3/4"	d	10 1/2"
	1		3 1/2"	

Type S17

PIPE DISPLACEMENT REDUCTIONS		
Diameter (Inches)	Wall T (Inches)	Class M6 Concrete (Cu. Yd.)
12	2	0.03
15	2 1/4	0.04
18	2 1/2	0.05
24	3	0.09
30	3 1/2	0.14
36	4	0.20
42	4 1/2	0.26
48	5	0.34
54	5 1/2	0.43
18	2 1/2	0.05
24	3 1/2	0.09
30	4	0.14
36	4 1/2	0.19
42	4 1/2	0.24


DROP INLET-CONCRETE-TYPE B (5.5'X5.5')

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD012
DROP INLET-CONC.-TYPE B-5.5X5.5-2



DETAIL RD013-DROP INLET-CONCRETE-TYPE B (4X3)-1



ESTIMATED QUANTITIES			
ITEM	UNIT	CONSTANT QUANTITY	VARIABLE QUANTITY
* Class M6 Concrete	Cu. Yd.	0.58	0.33H
Reinforcing Steel	Lb.	116.24	39.21H
Frame and Grate Assembly	Each	1	—

DROP INLETS FOR 12" TO 36" DIAMETER PIPE

SPECIFICATIONS

Design Specifications: AASHTO LRFD Bridge Design Specifications, current edition.

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, Current Edition and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES:

Design Live Load: HL-93. No construction loading in excess of legal load was considered.

Reinforcing steel shall conform to ASTM A615 grade 60. The d and e bars shall be lapped 12 inches with the c and b bars, respectively. Cut and bend reinforcing steel as required to place pipe(s) through the drop inlet wall.

Drop inlet may be precast. If precast drop inlet details differ from this standard plate, submit a checked design done by a SD registered P.E. and shop plans to the Engineer.

- * Reduce total quantities of concrete by the amount of concrete displaced by the pipe(s). The total quantity of concrete shall be computed to the nearest hundredth of a cubic yard. The total quantity of reinforcing steel shall be computed to the nearest pound.

Drop inlet shown may be modified by the addition or omission of connecting pipes as noted elsewhere in the plans. All pipes entering drop inlet must fit between the inside face of walls and shall not enter through the corners.

Maximum R.C.P. diameter shall not exceed 36 inches (30 inches for R. C. arch) on the 4-foot wide side and shall not exceed 24 inches (24 inches for R. C. arch) on the 3-foot wide side of the drop inlet.

The dimension of H is in feet. Maximum H is 10 feet.

PIPE DISPLACEMENT REDUCTIONS		
Diameter (Inches)	Wall T (Inches)	Class M6 Concrete (Cu. Yd.)
12	2	0.03
15	2 1/4	0.04
18	2 1/2	0.05
24	3	0.09
30	3 1/2	0.14
36	4	0.20
R.C.P.		
18	2 1/2	0.05
24	3 1/2	0.09
30	4	0.14
R.C. ARCH		


DROP INLET-CONCRETE-TYPE B (4'X3')

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD013
DROP INLET-CONC.-TYPE B-4X3-1



DETAIL RD014-DROP INLET-CONCRETE-TYPE B (4X3)-2



REINFORCING SCHEDULE				
Mk.	No.	Size	Length	Type
a	2.67H	4	10'-0"	17
b	7	4	7'-6"	17
c	9	4	6'-6"	17
d	18	4	H-2"	Str.
e	14	4	H+15"	S17
f	14	4	2'-6"	S19
g	2	4	6'-9"	17

NOTE:
All dimensions are out to out of bars.

Bending Details

a 4'-6 1/2"

b 4'-7 1/2"

c 3'-7 1/2"

g 3'-3"

Type 17

a 2'-8 3/4"

b 1'-5 1/4"

c 1'-5 1/4"

g 1'-9"

3"

12

6


f 1'-3"

Type S19

e 13 3/4"

3 1/2"

Type S17




DROP INLET-CONCRETE-TYPE B (4'X3')
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD014
DROP INLET-CONC.-TYPE B-4X3-2



DETAIL RD015-DROP INLET-CONCRETE-TYPE C (3X4)-1



ESTIMATED QUANTITIES			
ITEM	UNIT	CONSTANT QUANTITY	VARIABLE QUANTITY
* Class M6 Concrete	Cu. Yd.	0.43	0.30H
Reinforcing Steel	Lb.	90.90	40.53H
Frame and Grate Assembly	Each	1	—

DROP INLETS FOR 12" TO 36" DIAMETER PIPE

SPECIFICATIONS

Design Specifications: AASHTO LRFD Bridge Design Specifications, current edition.

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, Current Edition and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES:

Design Live Load: HL-93. No construction loading in excess of legal load was considered.

Reinforcing steel shall conform to ASTM A615 grade 60. The d bars shall be lapped 12 inches with the b and c bars. Cut and bend reinforcing steel as required to place pipe(s) through the drop inlet wall.

Drop inlet may be precast. If precast drop inlet details differ from this standard plate, submit a checked design done by a SD registered P.E. and shop plans to the Engineer for approval.

- * Reduce total quantities of concrete by the amount of concrete displaced by the pipe(s). The total quantity of concrete shall be computed to the nearest hundredth of a cubic yard. The total quantity of reinforcing steel shall be computed to the nearest pound.

Drop inlet shown may be modified by the addition or omission of connecting pipes as noted elsewhere in the plans. All pipes entering drop inlet must fit between the inside face of walls and shall not enter through the corners.

Maximum R.C.P. diameter shall not exceed 24 inches (24 inches for R. C. arch) on the 3-foot wide side and shall not exceed 36 inches (30 inches for R. C. arch) on the 4-foot wide side of the drop inlet.

The dimension of H is in feet. Maximum H is 10 feet.

PIPE DISPLACEMENT REDUCTIONS		
Diameter (Inches)	Wall T (Inches)	Class M6 Concrete (Cu. Yd.)
12	2	0.03
15	2 1/4	0.04
18	2 1/2	0.05
24	3	0.09
30	3 1/2	0.14
36	4	0.20
18	2 1/2	0.05
24	3 1/2	0.09
30	4	0.14


DROP INLET-CONCRETE-TYPE C (3'X4')

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD015
DROP INLET-CONC.-TYPE C-3X4-1



DETAIL RD016-DROP INLET-CONCRETE-TYPE C (3X4)-2




REINFORCING SCHEDULE					
Mk.	No.	Size	Length	Type	Bending Details
a	2.67H	4	10' - 0"	17	c $3'-6\frac{1}{2}''$ b $4'-6\frac{1}{2}''$ a $4'-6\frac{1}{2}''$ a $2'-8\frac{3}{4}''$ b $1'-4\frac{1}{4}''$ c $1'-4\frac{1}{4}''$
b	7	5	7' - 3"	17	
c	10	4	6' - 3"	17	
d	34	4	H - 2"	Str.	
NOTE: All dimensions are out to out of bars.					
Type 17					

DROP INLET-CONCRETE-TYPE C (3'X4') NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD016
DROP INLET-CONC.-TYPE C-3X4-2



DETAIL RD017-DROP INLET-CONCRETE-TYPE C (4X5)-1



ESTIMATED QUANTITIES			
ITEM	UNIT	CONSTANT QUANTITY	VARIABLE QUANTITY
* Class M6 Concrete	Cu. Yd.	1.06	0.37H
Reinforcing Steel	Lb.	180.36	45.43H
Frame and Grate Assembly	Each	1	—

DROP INLETS FOR 12" TO 48" DIAMETER PIPE

SPECIFICATIONS

Design Specifications: AASHTO LRFD Bridge Design Specifications, current edition.

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, Current Edition and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES:

Design Live Load: HL-93. No construction loading in excess of legal load was considered.

Reinforcing steel shall conform to ASTM A615 grade 60. The d bars shall be lapped 12 inches with the b and c bars. Cut and bend reinforcing steel as required to place pipe(s) through the drop inlet wall.

Drop inlet may be precast. If precast drop inlet details differ from this standard plate, submit a checked design done by a SD registered P.E. and Engineer for approval.

- * Reduce total quantities of concrete by the amount of concrete displaced by the pipe(s). The total quantity of concrete shall be computed to the nearest hundredth of a cubic yard. The total quantity of reinforcing steel shall be computed to the nearest pound.

Drop inlet shown may be modified by the addition or omission of connecting pipes as noted elsewhere in the plans. All pipes entering drop inlet must fit between the inside face of walls and shall not enter through the corners.

Maximum R.C.P. diameter shall not exceed 36 inches (30 inches for R. C. arch) on the 4-foot wide side and shall not exceed 48 inches (36 inches for R. C. arch) on the 5-foot wide side of the drop inlet.

The dimension of H is in feet. Maximum H is 10 feet.

PIPE DISPLACEMENT REDUCTIONS

	Diameter (Inches)	Wall T (Inches)	Class M6 Concrete (Cu. Yd.)
R.C.P.	12	2	0.03
	15	2 1/4	0.04
	18	2 1/2	0.05
	24	3	0.09
	30	3 1/2	0.14
	36	4	0.20
	42	4 1/2	0.26
R.C. ARCH	48	5	0.34
	18	2 1/2	0.05
	24	3 1/2	0.09
	30	4	0.14
	36	4 1/2	0.19


DROP INLET-CONCRETE-TYPE C (4'X5')

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD017
DROP INLET-CONC.-TYPE C-4X5-1



DETAIL RD018-DROP INLET-CONCRETE-TYPE C (4X5)-2



REINFORCING SCHEDULE					Bending Details			
Mk.	No.	Size	Length	Type				
a	2.67H	4	12' - 0"	17				
b	9	4	8' - 6"	17				
c	9	4	7' - 6"	17				
d	36	4	H + 9"	S17				
e	36	4	2' - 3"	S19				
f	2	4	9' - 0"	17				


NOTE:
All dimensions are out to out of bars.

Type S17

Type S19

a	3' - 2 3/4"
b	1' - 5 3/4"
c	1' - 5 3/4"
f	2' - 3"

Type 17




DROP INLET-CONCRETE-TYPE C (4'X5')
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD018
DROP INLET-CONC.-TYPE C-4X5-2



DETAIL RD019-DROP INLET-CONCRETE-TYPE S (4X6)-1



SPECIFICATIONS:

1. Design Specifications: AASHTO LRFD Bridge Design Specifications current edition.
2. Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, Current Edition and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES:

1. Design Live Load: HL-93 loading. No construction loading in excess of legal load was considered.
2. Base is intended for use with a Precast Concrete Type S Drop Inlet Lid. Base may be precast. If precast base used, and details differ from that shown.
3. Design shall be by a South Dakota Registered Professional Engineer.
4. Reduce total quantities of concrete by the amount of concrete displaced by the pipe. The total quantity of concrete shall be computed to the nearest hundredth of a cubic yard. The total quantity of reinforcing steel shall be computed to the nearest pound.
5. Inlets shown may be modified by the addition or omission of connecting pipes as shown on the layouts. Connecting pipes shall not enter the inlet through the corners.
6. Maximum R.C.P. diameter shall not exceed 36 inches (30 inches for R.C. Arch) on the 4-foot wide side and shall not exceed 54 inches (48 inches for R.C. Arch) on the 6-foot wide side of the Drop Inlet.
7. Reinforcing steel shall conform to ASTM A615 Grade 60. Cut and bend reinforcing steel as required to place pipe(s) through the inlet wall.
8. Use 1 inch clear cover on all reinforcing steel unless otherwise noted.
9. The dimension of H is in feet. Maximum H is 8 feet.

DROP INLET-CONCRETE-TYPE S (4'X6')

NOT TO SCALE

CITY OF BOX ELDER

STANDARD DETAIL RD019

DROP INLET-CONC.-TYPE S-4X6-1



DETAIL RD020-DROP INLET-CONCRETE-TYPE S (4X6)-2

REINFORCING SCHEDULE

Mk.	No.	Size	Length	Type	Bending Details
a	14	5	9' - 6"	17	
b	10	5	11' - 6"	17	
c	2H	4	5' - 6"	17	
d	2H	4	7' - 6"	17	
e	44	4	H - 2"	Str.	


NOTE:
All dimensions are out to out of bars

ESTIMATED QUANTITIES


ITEM	UNIT	CONSTANT QUANTITY	VARIABLE QUANTITY
Class M6 Concrete	Cu. Yd.	0.97	0.41H
Reinforcing Steel	Lb.	253.77	46.76H

PIPE DISPLACEMENT REDUCTIONS

Diameter (Inches)	Wall T (Inches)	Class M6 Concrete (Cu. Yd.)
12	2	0.03
15	2 1/4	0.04
18	2 1/2	0.05
24	3	0.09
30	3 1/2	0.14
36	4	0.20
42	4 1/2	0.26
48	5	0.34
54	5 1/2	0.43
18	2 1/2	0.05
24	3 1/2	0.09
30	4	0.14
36	4 1/2	0.19
42	4 1/2	0.24
48	5	0.32



SEC. A - A



SEC. B - B

Floor elevation as referred to in plans.

Maximum H is 8' - 0"

DROP INLET-CONCRETE-TYPE S (4'X6')

NOT TO SCALE




CITY OF BOX ELDER

STANDARD DETAIL RD020

DROP INLET-CONC.-TYPE S-4X6-2



DETAIL RD021-DROP INLET-CONCRTE-TYPE S (4X6)-3



GENERAL NOTES:

1. The Precast Concrete Type S Drop Inlet Lid and the shims shall be submitted by a SD Registered Professional Engineer. Design shall be in accordance with the current edition of the AASHTO LRFD Bridge Design Specifications.
2. Design Live Load shall be HL - 93.
3. Concrete mix shall be as per fabricators design, however, minimum compressive strength shall not be less than 4500 psi. Type II Cement is required.
4. The Type S Manhole Frame and Lid shall conform to AASHTO M105, Class 30.
5. Structural Steel shall conform to ASTM A36. The 3/4 inch diameter Headed Type A Steel Studs shall conform to Section 7 of the current edition of AWS DI. I Structural Steel Welding Code.
6. The 3/4 inch diameter Concrete Inserts shall be galvanized or made of a corrosion resistant material. Provide 3/4 inch diameter x 1'-6" long dowels conforming to ASTM A615, Gr. 60 threaded to fit Inserts with each lid.
7. All costs associated with furnishing and installing the Precast Concrete Type S Drop Inlet Lid including the type S manhole frame and lid, shims, inserts, and dowels shall be included in the contract unit price per each for "4' x 6' Precast Concrete Type S Drop Inlet Lid".

TYPICAL SECTION THROUGH TYPE S MANHOLE FRAME AND LID

(Weight 140 Lbs.)

DROP INLET-CONCRETE-TYPE S (4'X6')

NOT TO SCALE




CITY OF BOX ELDER

STANDARD DETAIL RD021

DROP INLET-CONC.-TYPE S-4X6-3



DETAIL RD022-DROP INLET-CONCRETE-TYPE S (4X11)-1




GENERAL NOTES:

1. The Precast Concrete Type S Drop Inlet Lid and the shims shall be submitted by a SD Registered Professional Engineer. Design shall be in accordance with the current edition of the AASHTO LRFD Bridge Design Specifications.
2. Design Live Load shall be HL - 93.
3. Concrete mix shall be as per fabricators design, however, minimum compressive strength shall not be less than 4500 psi. Type II Cement is required.
4. The Type S Manhole Frame and Lid shall conform to AASHTO M105, Class 30.
5. Structural Steel shall conform to ASTM A36. The 3/4" inch diameter Headed Type A Steel Studs shall conform to Section 7 of the current edition of AWS D1.1 Structural Steel Welding Code.
6. The 3/4" inch diameter Concrete Inserts shall be galvanized or made of a corrosion resistant material. Provide 3/4" inch diameter x 1'-6" long dowels conforming to ASTM A615, Gr. 60 threaded to fit Inserts with each lid.
7. All costs associated with furnishing and installing the Precast Concrete Type S Drop Inlet Lid including the type S manhole frame and lid, shims, inserts, and dowels shall be included in the contract unit price per each for "4' x 6' Precast Concrete Type S Drop Inlet Lid".

SIDE VIEW

(With Sidewalk Inserts)



TYPICAL SECTION THROUGH TYPE S MANHOLE FRAME AND LID

(Weight 140 Lbs.)

DROP INLET-CONCRETE-TYPE S (4'X6')

NOT TO SCALE

CITY OF BOX ELDER

STANDARD DETAIL RD022

DROP INLET-CONC.-TYPE S-4X11-1



DETAIL RD023-DROP INLET-CONCRETE-TYPE S (4X11)-2

PIPE DISPLACEMENT REDUCTIONS

Diameter (Inches)	Wall T (Inches)	Class M6 Concrete (Cu. Yd.)
12	2	0.03
15	2 1/4	0.04
18	2 1/2	0.05
24	3	0.09
30	3 1/2	0.14
36	4	0.20
42	4 1/2	0.26
48	5	0.34
54	5 1/2	0.43
60	6	0.52
18	2 1/2	0.05
24	3 1/2	0.09
30	4	0.14
36	4 1/2	0.19
42	4 1/2	0.24
48	5	0.32
54	5 1/2	0.39
60	6	0.49
72	7	0.70
84	8	0.93

REINFORCING SCHEDULE


Mk.	No.	Size	Length	Type	Bending Details
a	24	5	9' - 6"	17	d 11' - 8"
b	10	5	16' - 6"	17	c 4' - 8"
c	2H	4	5' - 6"	17	b 11' - 10"
d	2H	4	12' - 6"	17	a 4' - 10"
e	64	4	H - 2"	Str.	

NOTE: All dimensions are out to out of bars.

Type 17

R.C.P.


R.C. ARCH



SEC. B - B

ESTIMATED QUANTITIES

ITEM	UNIT	CONSTANT QUANTITY	VARIABLE QUANTITY
* Class M6 Concrete	Cu. Yd.	1.67	0.59H
Reinforcing Steel	Lb.	402.77	66.80H



SEC. A - A

DROP INLET-CONCRETE-TYPE S (4'X11')

NOT TO SCALE

★ Maximum H is 8' - 0"





CITY OF BOX ELDER

STANDARD DETAIL RD023

DROP INLET-CONC.-TYPE S-4X11-2



DETAIL RD024-DROP INLET-CONCRETE-TYPE B (4X11)-3



GENERAL NOTES:

1. The Precast Concrete Type S Drop Inlet Lid and the shims shall be submitted by a SD Registered Professional Engineer. Design shall be in accordance with the current edition of the AASHTO LRFD Bridge Design Specifications.
2. Design Live Load shall be HL - 93.
3. Concrete mix shall be as per fabricators design, however, minimum compressive strength shall not be less than 4500 psi. Type II Cement is required.
4. The Type S Manhole Frame and Lid shall conform to AASHTO M105, Class 30.
5. Structural Steel shall conform to ASTM A36. The 3/4 inch diameter Headed Type A Steel Studs shall conform to Section 7 of the current edition of AWS D1. 1 Structural Steel Welding Code.
6. The 3/4 inch diameter Concrete Inserts shall be galvanized or made of a corrosion resistant material. Provide 3/4 inch diameter x 1' - 6" long dowels conforming to ASTM A615, Gr. 60 threaded to fit inserts with each lid.
7. All costs associated with furnishing and installing the Precast Concrete Type S Drop Inlet Lid including the type S manhole frame and lid, shims, inserts, and dowels shall be included in the contract unit price per each for "4' x 11' Precast Concrete Type S

DROP INLET-CONCRETE-TYPE S (4'X11')

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RD024

DROP INLET-CONC.-TYPE S-4X11-3



DETAIL RD025-DROP INLET-CONCRETE-TYPE S (7X11)-1



SPECIFICATIONS:

ELEVATION

1. Design Specifications: AASHTO LRFD Bridge Design Specifications, current edition.
2. Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, current edition, and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES:

1. Design Live Load: HL-93 loading. No construction loading in excess of legal load was considered.
2. Base is intended for use with a Precast Concrete Type S Drop Inlet Lid. Base may be precast. If precast based used, and details differ from that shown, the precast base shop plans must be submitted by a SD Registered PE for approval. Design shall be in accordance with the current edition of the AASHTO LRFD Bridge Design Specifications.
3. Reduce total quantities of concrete by the amount of concrete displaced by the pipe. The total quantity of concrete shall be computed to the nearest 0.01 cubic yard. The total quantity of reinforcing steel shall be computed to the nearest pound.
4. Inlets shown may be modified by the addition or omission of connecting pipes as shown on the layouts. Connecting pipes shall not enter the inlet through the corners.
5. Maximum R.C.P. diameter shall not exceed 66 inches (54 inches for R.C. Arch) on the 7-foot wide side of the Drop Inlet.
6. Reinforcing steel shall conform to ASTM A615 Grade 60. Cut and bend reinforcing steel as required to place pipe(s) through the inlet wall.
8. Use 1-inch clear cover on all reinforcing steel unless otherwise noted.
9. The dimension of H is in feet. Maximum H is 10 feet.

DROP INLET-CONCRETE-TYPE S (7'X11')

NOT TO SCALE



CITY OF BOX ELDER

STANDARD DETAIL RD025

DROP INLET-CONC.-TYPE S-7X11-1



DETAIL RD026-DROP INLET-CONCRETE-TYPE S (7X11)-2



T.T.S. - Top of Top Slab
B.T.S. - Bottom of Top Slab
T.B.S. - Top of Bottom Slab
B.B.S. - Bottom of Bottom Slab



DROP INLET-CONCRETE-TYPE S (7'X11')

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD026
DROP INLET-CONC.-TYPE S-7X11-2



DETAIL RD027--DROP INLET-CONCRETE-TYPE S (7X11)-3



T.T.S. - Top of Top Slab
 B.T.S. - Bottom of Top Slab
 T.B.S. - Top of Bottom Slab
 B.B.S. - Bottom of Bottom Slab

DROP INLET-CONCRETE-TYPE S (7'X11')

NOT TO SCALE

CITY OF BOX ELDER
 STANDARD DETAIL RD027
 DROP INLET-CONC.-TYPE S-7X11-3



DETAIL RD028-DROP INLET-CONCRETE-TYPE S (7X11)-4

REINFORCING SCHEDULE


Mk.	No.	Size	Length	Type	Bending Details
b	19 + 4H	4	11' - 9"	Str.	
c	15 + 2H	4	7' - 9"	Str.	
c1	2 + 2H	4	11' - 10"	17	
c2	11	4	2' - 10"	Str.	
g	15	5	11' - 9"	Str.	
g1	23	5	7' - 9"	Str.	
h	46	5	H + 5"	Str.	
k	40	5	H + 5"	Str.	
q	76	5	5' - 6"	17A	
q1	23	5	6' - 8"	17A	

NOTE:

All dimensions are out to out of bars

ESTIMATED QUANTITIES

ITEM	UNIT	CONSTANT QUANTITY	VARIABLE QUANTITY
Class M6 Concrete	Cu. Yd.	3.65	0.83H
Reinforcing Steel	Lb.	1266	147.26H



SEC. A - A
(Pipe Not Shown)

DROP INLET-CONCRETE-TYPE S (7'X11')

NOT TO SCALE

PIPE DISPLACEMENT REDUCTIONS

Diameter (Inches)	Wall T (Inches)	Class M6 Concrete (Cu. Yd.)
12	2	0.03
15	2 1/4	0.04
18	2 1/2	0.06
24	3	0.11
30	3 1/2	0.16
36	4	0.23
42	4 1/2	0.31
48	5	0.40
54	5 1/2	0.50
60	6	0.61
18	2 1/2	0.06
24	3 1/2	0.11
30	4	0.16
36	4 1/2	0.22
42	4 1/2	0.29
48	5	0.37
54	5 1/2	0.46
60	6	0.57
72	7	0.82
84	8	1.09



CITY OF BOX ELDER

STANDARD DETAIL RD028

DROP INLET-CONC.-TYPE S-7X11-4



DETAIL RD029-DROP INLET-CONCRETE-TYPE S INSTALLATION-1



DROP INLET-CONCRETE-TYPE S-INSTALLATION

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RD029

DROP INLET-CONC.-TYPE S-INST.-1



DETAIL RD030-DROP INLET-CONCRETE-TYPE S INSTALLATION-2



CURB AND GUTTER TRANSITION DETAILS

<i>Drop Inlet Base Unit Size</i>	<i>✕ Distance</i>
<i>4' x 6'</i>	<i>1' - 5 1/2\"</i>
<i>4' x 11'</i>	<i>1' - 5 1/2\"</i>
<i>7' x 11'</i>	<i>2' - 11 1/2\"</i>

GENERAL NOTES:

- 1. Dowels shall be used to anchor the precast concrete Type S drop inlet lid to the concrete gutter. If there is sidewalk adjacent dowels shall be used to anchor the precast concrete Type S drop inlet lid to the sidewalk. If there is sidewalk adjacent to the drop inlet, the precast lid shall match the finish elevations and cross slopes of the sidewalk.*
- 2. The sidewalk shall be steel reinforced when the sidewalk adjoins the precast lid.*

DROP INLET-CONCRETE-TYPE S-INSTALLATION

NOT TO SCALE

CITY OF BOX ELDER

STANDARD DETAIL RD030


DROP INLET-CONC.-TYPE S-INST.-2



DETAIL RD031-DROP INLET-CONCRETE-TYPE B INSTALLATION

GENERAL NOTE:

Top of grate elevation shall be 0.04' below theoretical elevation of gutter.



DROP INLET-CONCRETE-TYPE B-INSTALLATION

NOT TO SCALE









CITY OF BOX ELDER

STANDARD DETAIL RD031

DROP INLET-CONC.-TYPE B-INST.



DETAIL RD032-DROP INLET-CONCRETE-TYPE B-FRAME AND GRATE ASSEMBLY



GENERAL NOTE:

Total weight of the assembly shall be 490 Lbs. minimum and the curb box shall be adjustable 6" to 9".

DROP INLET-CONCRETE-TYPE B-FRAME AND GRATE ASSEMBLY

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RD032


DROP INLET-CONC.-TYPE B-FRAME AND GRATE ASSEMBLY



DETAIL RD033-DROP INLET-CONCRETE-TYPE C-FRAME AND GRATE ASSEMBLY




PLAN OF FRAME




PLAN OF GRATE


SECTION C-C




SECTION A-A



SECTION D-D



SECTION B-B



ASSEMBLED VIEW

DROP INLET-CONCRETE-TYPE C-FRAME AND GRATE ASSEMBLY

NOT TO SCALE




CITY OF BOX ELDER

STANDARD DETAIL RD033

DROP INLET-CONC.-TYPE C-FRAME AND GRATE ASSEMBLY



DETAIL RD034-DROP INLET-CONCRETE-TYPE E-FRAME AND GRATE ASSEMBLY



GENERAL NOTES:

The total weight of frame and grate shall be 810 pounds minimum.
The Type E frame and grate is used typically with valley gutter.

DROP INLET-CONCRETE-TYPE E-FRAME AND GRATE ASSEMBLY

NOT TO SCALE

CITY OF BOX ELDER

STANDARD DETAIL RD034

DROP INLET-CONC.-TYPE E-FRAME AND GRATE ASSEMBLY



DETAIL RD040-DROP INLET-CONCRETE-PERMANENT COVERS-1

INFORMATIONAL QUANTITIES			
ITEM	Class M6 Concrete	Reinforcing Steel	Install Dowel in Concrete
DROP INLET COVER SIZE	Cu. Yd.	Lb.	Each
4' - 0" x 11' - 0"	1.1	116	12
5' - 6" x 11' - 0"	1.5	153	12
7' - 0" x 11' - 0"	1.9	218	12

* Quantity of #1 Dowel Bars is not included in Reinforcing Steel.

SPECIFICATIONS

Design Specifications: AASHTO LRFD Bridge Design Specifications, current edition.

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, Current Edition and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES

Design Live Load: HL-93. No construction loading in excess of legal load was considered.

Drop inlet covers may be precast. If precast drop inlet cover details differ from this standard plate, submit a checked design done by a SD registered P.E. with shop plans to the Engineer for approval. If precast, top side of lid shall be marked.

Use 1 1/2 inch clear cover on all reinforcing steel except as shown.

All exposed edges shall be chamfered 3/4 inch.

Maximum fill over drop inlet cover shall be 3 feet, including surfacing.

Contractor shall break out drop inlet walls as necessary for the drop inlet cover to fit below roadway surfacing.

Apply a thin layer of grout between drop inlet and cover to ensure uniform bearing. Grout shall conform to the Specifications.

All costs involved in furnishing and installing the drop inlet cover including the epoxy resin and dowels shall be incidental to the contract unit price per Each for "4' x 11' Drop Inlet Cover", "5.5' x 11' Drop Inlet Cover, or "7' x 11' Drop Inlet Cover".

INSTALLING DOWELS IN CONCRETE

Holes drilled in the existing concrete shall be true and normal or as shown in the plans. Care shall be taken not to damage the existing reinforcing steel. It is very likely that some of the existing reinforcing steel shown in the original construction plans may have been placed out of position during original construction. In spite of this precaution, the Contractor can still expect to encounter and have to drill through reinforcing steel or shift the dowel spacing as approved by the Engineer to miss the existing reinforcing steel.

The epoxy resin mixture shall be of a type for bonding steel to hardened concrete and shall conform to AASHTO M235 Type IV, Grade 3 (Equivalent to ASTM C881, Type IV, Grade 3).

The diameter of the drilled holes shall not be less than 1/8 inch greater, nor more than 3/8 inch greater than the diameter of the dowels or as per the Manufacturer's recommendations. Use compressed air or other techniques to ensure that the hole is free of any loose material before epoxy resin is applied.

Mix epoxy resin as recommended by the Manufacturer and apply by an injection method as approved by the Engineer. Beginning at the bottom of the drilled holes, fill the holes 1/3 to 1/2 full of epoxy resin. Rotate the steel bar during installation to eliminate voids and ensure complete bonding of the bar. Insertion of the bars by the dipping method will not be allowed.

No loads shall be applied to the epoxy grouted dowel bars until the epoxy resin has had sufficient time to cure as specified by the epoxy resin manufacturer.

Embed dowels 9 inches into existing concrete.

DROP INLET-CONCRETE-PERMANENT COVERS (VARIOUS)

NOT TO SCALE





CITY OF BOX ELDER

STANDARD DETAIL RD040

DROP INLET-CONC.-PERM. COVERS-1



DETAIL RD041-DROP INLET-CONCRETE-PERMANENT COVERS-2



REINFORCING SCHEDULE (for one cover)					Bending Details	
Mk.	No.	Size	Length	Type		
4'-0" WIDTH						
A2	22	4	3'-11"	14A		
A3	8	4	10'-11"	14A		
z1	12	4	1'-3"	Str.		
5'-6"						
A2	22	4	5'-5"	14A		
A3	10	4	10'-11"	14A		
z1	12	4	1'-3"	Str.		
7'-0"						
A2	22	4	6'-11"	14A		
A3	16	4	10'-11"	14A		
z1	12	4	1'-3"	Str.		
* Dowel Bar						
					Type 14A	

DROP INLET-CONCRETE-PERMANENT COVERS (VARIOUS)

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RD041

DROP INLET-CONC.-PERM. COVERS-2



DETAIL RD042-DROP INLET-CONCRETE-PRECAST COLLAR



INFORMATIONAL QUANTITIES					
FRAME AND GRATE TYPE	L Ft-In	W Ft-In	T In	CLASS M6 CONCRETE CuYd	REINFORCING STEEL Lb
TYPE B	4'-0"	3'-0"	6	0.11	9
TYPE C	5'-0"	4'-0"	6	0.15	11
TYPE D	4'-0"	2'-6"	6	0.10	8

GENERAL NOTES:

All reinforcing steel shall conform to ASTM A615, Grade 60.

The reinforcement bar shall lap 6 inches and shall be centered in the concrete.

The cost of furnishing and installing Precast Drop Inlet Collars, including labor, materials, and incidentals shall be incidental to the contract unit price per Each for "Precast Drop Inlet Collar".

DROP INLET-CONCRETE-PRECAST COLLAR

NOT TO SCALE





CITY OF BOX ELDER

STANDARD DETAIL RD042

DROP INLET-CONC.-PRECAST COLLAR



DETAIL RD050-MANHOLE FRAME AND LID-TYPE A



TYPE	HEIGHT (Inches)	MINIMUM WEIGHT (Lb.)
A7	7	400
A8	8	440
A9	9	470
A10	10	480

GENERAL NOTE:

Geometric pattern on top of lid other than that shown shall be approved by the Engineer.

MANHOLE-FRAME AND LID-TYPE A

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RD050


MANHOLE FRAME AND LID-TYPE A




DETAIL RD051-MANHOLE FRAME AND LID-TYPE B



PLAN VIEW



ASSEMBLED VIEW



SECTION A-A

GENERAL NOTE:

Total weight of the frame and lid shall be 140 Lbs. minimum.


MANHOLE-FRAME AND LID-TYPE B

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RD051
MANHOLE FRAME AND LID-TYPE B



DETAIL RD060-HEADWALL-CONCRETE-UNDERDRAIN



GENERAL NOTES:

The concrete shall be Class M6. The concrete shall conform to the requirements of Section 462 of the Specifications except the minimum curing time shall be 72 hours. It is estimated that 0.55 cubic yards of concrete is required for each unit.

Four cast-in-place or drilled-in 1/4" galvanized anchors shall be placed in the headwall. Each galvanized anchor shall be placed approximately 1" from the outside corner of the rodent screen. It is preferred that the anchor location be centered at an opening in the rodent screen.

All reinforcing steel shall conform to ASTM A615 Grade 60. It is estimated that 25.7 pounds of reinforcing steel is required for each unit.

The underdrain pipe shall be placed in the concrete headwall with the pipe end flush with the concrete surface adjacent to the rodent screen.

The 8"x8" rodent screen shall be galvanized 13 Ga. steel with a diamond shaped flattened mesh pattern. The size shall be 1/2". The size refers to the measurement across the smallest diamond shaped opening measured from the centers of the wires. The rodent screen shall be centered about the hole in the headwall and fastened to the headwall with the appropriate bolts or nuts with washers.

A 4"x4"x6' marker post shall be placed at the approximate location as depicted in the above drawings for each concrete headwall. The marker post shall project 3'+ above the ground line. The marker post shall be cedar or treated with a wood preservative and shall be painted with two coats of white paint.

All costs for furnishing and installing the concrete headwall including equipment, labor, and materials including concrete, reinforcing steel, rodent screen, anchors, and marker post shall be incidental to the contract unit price per each for "Concrete Headwall for Underdrain".

HEADWALL-CONCRETE-UNDERDRAIN

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RD060




HEADWALL-CONC.-UNDERDRAIN



DETAIL RD062- UNDER DRAIN CONNECTION DETAIL



Note:
Underdrain connection into inlet
shall be made watertight using non-
shrink grout or approved equal.
(Typical All Connections)



N.T.S.


CITY OF BOX ELDER
STANDARD DETAIL RD062
UNDER DRAIN CONNECTION DETAIL




DETAIL RD063- UNDER DRAIN DETAIL

Note:

Drainage fabric material to totally enclose under drain pipe trench backfill material and pipe. Provide 12" minimum overlap on top and 12" minimum overlap end-to-end.



UNDER-DRAIN NEW CURB & GUTTER




UNDER-DRAIN EXISTING CURB & GUTTER N.T.S.


CITY OF BOX ELDER
STANDARD DETAIL RD063
UNDER DRAIN DETAIL




DETAIL RE001-EROSION CONTROL-BLANKET




STANDARD DITCH SECTION



SLOPED DITCH SECTION




MEDIAN SECTION




* Use a 4" (Min.) overlap wherever two widths of erosion control blanket are applied side by side.

* Use a 6" (Min.) overlap wherever one roll of erosion control blanket ends and another begins.

OVERLAP DETAIL



TRENCH DETAIL



PIPE END DETAIL

GENERAL NOTES:

Prior to placement of the erosion control blanket, the areas shall be properly prepared, shaped, seeded, and fertilized.

Erosion control blanket shall be unrolled in the direction of the flow of water when placed in ditches and on slopes. The upslope end of the erosion control blanket shall be buried in a trench 6" wide by 6" deep. There shall be at least a 6" overlap wherever one roll of erosion control blanket ends and another begins, with the upslope erosion control blanket placed on top of the downslope erosion control blanket.

The erosion control blanket shall be pinned to the ground according to the manufacturer's installation recommendations.

After the placement of the erosion control blanket, the Contractor shall fine grade along all edges of the blanket to maintain a uniform slope adjacent to the blanket and level any low spots which might prevent uniform and unrestricted flow of side drainage directly onto the erosion control blanket.

All ditch sections shall be shaped when installing the erosion control blanket. All costs for shaping the ditches shall be incidental to the contract unit price per foot for "Shaping for Erosion Control Blanket".


EROSION CONTROL-BLANKET

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RE001
EROSION CONTROL-BLANKET





DETAIL RE002-EROSION CONTROL-BALES



NORMAL DITCH SECTION FOR EROSION BALE INSTALLATION

**The maximum spacing between sediment barriers should be such that the toe of the upstream sediment barrier is at the same elevation as the top of the downstream sediment barrier.



EROSION BALE INSTALLATION

(This Ditch Section and Erosion Bale Installation Typically Used in Black Hills)

GENERAL NOTES:

The erosion bale sediment barrier must be entrenched and backfilled. A trench should be excavated the width of a bale and the length of the proposed sediment barrier to a minimum depth of 4 inches. After the bales are staked with rebar or wood stakes, the excavated soil must be backfilled against the sediment barrier. The sediment barrier must be extended to such a length that the bottoms of the end bales are higher in elevation than the top of the lowest middle bale.


EROSION CONTROL-BALES

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RE002
EROSION CONTROL-BALES



DETAIL RE003-EROSION CONTROL-ROCK CHECK DAM



GENERAL NOTES:

The elevation of Point A and Point B shall be the same. The distance L is the distance required such that Point A and Point B are at the same elevation.

All costs for constructing the Rock Check Dam including labor, equipment, excavation, and rock shall be incidental to the contract unit price per cubic yard for "Rock Check Dam".

EROSION CONTROL-ROCK CHECK DAM

NOT TO SCALE

CITY OF BOX ELDER




STANDARD DETAIL RE003

EROSION CONTROL-ROCK CHECK DAM



DETAIL RE004-EROSION CONTROL-SILT FENCE-1

MANUAL LOW FLOW SILT FENCE INSTALLATION



EROSION CONTROL-LOW FLOW SILT FENCE AND TRAP


NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RE004
EROSION CONTROL-SILT FENCE-1




DETAIL RE005-EROSION CONTROL-SILT FENCE-2

MACHINE SLICED LOW FLOW SILT FENCE INSTALLATION




- ① INSTALL SILT FENCE FABRIC BY MACHINE SLICING METHOD.

Silt fence fabric shall be overlapped a minimum of 2" at top of woven wire fence.





- ③ ATTACH 26" WOVEN WIRE FENCE TO POSTS AND ATTACH SILT FENCE FABRIC.



DRIVE STEEL T FENCE POSTS

- ② WHEEL COMPACT SOIL ABOVE SLICED IN PORTION OF FABRIC AND THEN DRIVE STEEL T FENCE POSTS.



The silt fence length and width may be adjusted due to a larger pipe, multiple pipe, or other circumstances during construction as determined by the Engineer.

The radius of the silt fence shall be the minimum capable by the slicing machine. The post spacing shall be 3' for these types of applications of silt fence. All the other components of the silt fence shall be the same as shown above.

GENERAL NOTES:

A silt trap shall be provided when specified by a plan note. All costs for constructing the silt trap shall be incidental to the contract unit price per cubic yard for "Silt Trap".

If a trench can not be dug or the silt fence fabric can not be sliced in due to the type of earthen material (such as rock), then a row of 30 to 40 pound sandbags butted end to end shall be provided on top of the extra length of silt fence fabric to prevent underflow.

EROSION CONTROL-LOW FLOW SILT FENCE AND TRAP

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RE005

EROSION CONTROL-SILT FENCE-2




DETAIL RE006-EROSION CONTROL-WATTLE-1




**ELEVATION VIEW
CUT OR FILL SLOPE INSTALLATION**


CUT OR FILL SLOPE INSTALLATION	
Slope	Spacing (Ft)
1:1	10
2:1	20
3:1	30
4:1	40




**DETAIL B
(TYPICAL OF ALL INSTALLATIONS)**



DETAIL C




**ISOMETRIC VIEW
DITCH INSTALLATION**



**PLAN VIEW
DITCH INSTALLATION**

DITCH INSTALLATION	
Grade	Spacing (Ft)
2%	150
3%	100
4%	75
5%	50



SECTION A-A

EROSION CONTROL-WATTLE
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RE006
EROSION CONTROL-WATTLE-1



DETAIL RE007-EROSION CONTROL-WATTLE-2

GENERAL NOTES:

At cut or fill slope installations, wattles shall be installed along the contour and perpendicular to the water flow.

At ditch installations, point A must be higher than point B to ensure that water flows over the wattle and not around the ends.

The Contractor shall dig a 3" to 5" trench, install the wattle tightly in the trench so that daylight can not be seen under the wattle, and then compact the soil excavated from the trench against the wattle on the uphill side. See Detail B.

The stakes shall be 1"x2" or 2"x2" wood stakes, however, other types of stakes such as rebar may be used only if approved by the Engineer. The stakes shall be placed 6" from the ends of the wattles and the spacing of the stakes along the wattles shall be 3' to 4'.

Where installing running lengths of wattles, the Contractor shall butt the second wattle tightly against the first and shall not overlap the ends. See Detail C.

The Contractor and Engineer shall inspect the erosion control wattles once every week and within 24 hours after every rainfall event greater than 1/2". The Contractor shall remove, dispose, or reshape the accumulated sediment when necessary as determined by the Engineer.

Sediment removal, disposal, or necessary shaping shall be as directed by the Engineer. All costs for removing accumulated sediment, disposal of sediment, and necessary shaping shall be incidental to the contract unit price per cubic yard for "Remove Sediment".

All costs for furnishing and installing the erosion control wattles including labor, equipment, and materials shall be incidental to the contract unit price per foot for the corresponding erosion control wattle bid item.

All costs for removing the erosion control wattle from the project including labor, equipment, and materials shall be incidental to the contract unit price per foot for "Remove Erosion Control Wattle".

EROSION CONTROL-WATTLE

NOT TO SCALE


CITY OF BOX ELDER
STANDARD DETAIL RE007
EROSION CONTROL-WATTLE-2



DETAIL RE008-EROSION CONTROL-INLETS-1

L = Length of Grate

W = Width of Grate



ISOMETRIC VIEW

GENERAL NOTES:

The grate and curb and gutter shown are for illustrative purposes only.

The sediment control at inlet with frame and grate shall be placed at locations stated in the plans or at locations determined by the Engineer.

The filter fabric shall be the type specified in the plans.

The filter fabric shall be placed in the inlet opening prior to placing the grate. Approximately 18 inches of excess filter fabric shall be wrapped around the 2"x4" and stapled securely to the 2"x4" after the grate has been placed.

The Contractor shall inspect and maintain the sediment control device once every week and within 24 hours after every rainfall event. The Contractor shall maintain the sediment control device by removing accumulated sediment and replacing torn filter fabric with new filter fabric.

The removed sediment shall be placed at a location away from the drop inlet where the sediment will not be washed back into the drop inlet or other storm sewer system.

All costs for furnishing, installing, inspecting, maintaining, removing, and replacing the sediment control device at the inlet including labor, equipment, and materials shall be incidental to the contract unit price per each for "Sediment Control at Inlet with Frame and Grate".


EROSION CONTROL-INLETS WITH FRAMES AND GRATES

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RE008
EROSION CONTROL-INLETS-1



DETAIL RE009-EROSION CONTROL-INLETS-2



ISOMETRIC VIEW

GENERAL NOTES:

The type of sediment control device shown is for illustrative purposes only.

The type of sediment control device used shall be one of the types as specified in the plans.

The sediment control device shall be placed at the drop inlets according to the manufacturers' installation instructions.

The sediment control at inlet for type S reinforced concrete drop inlet shall be placed at locations stated in the plans or at locations determined by the Engineer.

The Contractor shall inspect and maintain the sediment control device once every week and within 24 hours after every rainfall event. The Contractor shall maintain the sediment control device by removing the device, removing accumulated sediment, and resetting the device.

The removed sediment shall be placed at a location away from the drop inlet where the sediment will not be washed back into the drop inlet or other storm sewer system.

Payment for the "Sediment Control at Type S Drop Inlet" shall be based on the minimum length required at the drop inlets. Some of the sediment control devices specified in the plans will have to be longer due to available length.

All costs for furnishing, installing, inspecting, maintaining, removing, and resetting the sediment control device at the drop inlet including labor, equipment, and materials shall be incidental to the contract unit price per foot for "Sediment Control at Type S Reinforced Concrete Drop Inlet".


EROSION CONTROL-INLETS FOR TYPE S DROP INLETS

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RE009
EROSION CONTROL-INLETS-2



DETAIL RE020-EROSION CONTROL-GABION-1



GABION DETAILS STANDARD SIZES

SIZE	LENGTH	WIDTH	HEIGHT	NUMBER OF CELLS	CAPACITY, Cu. Yd.
A	6'-0"	3'-0"	3'-0"	2	2.0
B	9'-0"	3'-0"	3'-0"	3	3.0
C	12'-0"	3'-0"	3'-0"	4	4.0
D	6'-0"	3'-0"	1'-6"	2	1.0
E	9'-0"	3'-0"	1'-6"	3	1.5
F	12'-0"	3'-0"	1'-6"	4	2.0
G	6'-0"	3'-0"	1'-0"	2	0.7
H	9'-0"	3'-0"	1'-0"	3	1.0
I	12'-0"	3'-0"	1'-0"	4	1.3

Above Dimensions subject to mill tolerances.

GENERAL NOTES:

Lacing and internal connecting wire shall be 0.0866 inch diameter steel wire ASTM A641 Class 3 soft temper measured after galvanizing and for PVC coated gabions shall be 0.0866 inch diameter steel wire measured after galvanizing but before PVC coating.

The lacing procedure is as follows:

1. Cut a length of lacing wire approximately 1 times the distance to be laced but not exceeding 5 feet.
2. Secure the wire terminal at the corner by looping and twisting.
3. Proceed lacing with alternating single and double loops at a spacing not to exceed 6 inches.
4. Securely fasten the other lacing wire terminal.

Wire lacing or interlocking type fasteners shall be used for gabion assembly and final construction of gabion structures. Interlocking fasteners for galvanized gabions shall be high tensile 0.120 inch diameter galvanized steel wire measured after galvanizing. The galvanizing shall conform to ASTM A641-92 Class 3 coating. Fasteners shall also be in accordance with ASTM A764, Class II, Type III.

Interlocking fasteners for PVC coated gabions shall be high tensile 0.120 inch diameter stainless steel wire conforming to ASTM A313, Type 302, Class 1. The spacing of the interlocking fasteners during all phases of assembly and construction shall not exceed 6 inches. All fasteners shall be placed where the mesh weaves around the selvage wire at the vertical and horizontal joints.


EROSION CONTROL-GABION-BANK AND CHANNEL

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RE020
EROSION CONTROL-GABION-1



DETAIL RE021-EROSION CONTROL-GABION-2



EROSION CONTROL-GABION-UNDER PIPE SECTIONS

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RE021
EROSION CONTROL-GABION-2



DETAIL RE022-EROSION CONTROL-GABION-3

ESTIMATED QUANTITIES *				
	Detail	Pipe Diameter (Inches)	Gabion (Cu. Yd.)	Type B Drainage Fabric (Sq. Yd.)
RCP, RCP Arch, CMP, and CMP Arch	1	12, 18, and 24	4.5	15
	2	30 and 36	6.0	19
	3	42	10.0	29
	4	48 and 54	12.0	34
	5	60	15.5	43
	6	66	17.0	47
	7	72	21.5	57
	8	78	26.0	68
	9	84	27.0	70

GENERAL NOTES:

Gabions at outlets of CMP and RCP shall be placed under the end section a distance of 2' from the outlet end. For CMP end section installations, the upper fabric of the gabions shall be modified to accommodate the metal end section as approved by the Engineer.

*

Gabion and type B drainage fabric quantities on this standard plate are based on standard gabion sizes D, E, and F as depicted on Standard Plate 720.01.

Type B drainage fabric shall be placed under the gabions and around the exterior sides (perimeter) of the gabions as approved by the Engineer. The type B drainage fabric shall be in conformance with Section 831 of the Specifications. Measurement and payment of the type B drainage fabric shall be in conformance with Section 720 of the Specifications.


EROSION CONTROL-GABION-UNDER PIPE END SECTIONS

NOT TO SCALE


CITY OF BOX ELDER
STANDARD DETAIL RE022
EROSION CONTROL-GABION-3



DETAIL RE030-EROSION CONTROL-DITCH



ISOMETRIC VIEW



SECTION A-A

GENERAL NOTES:

The Contractor shall inspect the interceptor ditch once every week and within 24 hours after every rainfall event. The Contractor shall maintain the interceptor ditch by removing accumulated sediment once it has reached a depth of 1'.

The non-erodible material used shall be an erosion control blanket or a 2" thickness of shotrock, base course, or gravel cushion material.

The Engineer shall determine when or if the interceptor ditch shall be removed.

All costs for constructing, inspecting, and maintaining the interceptor ditch including labor, equipment, and materials shall be incidental to the contract unit price per foot for "Cut Interceptor Ditch".


EROSION CONTROL-CUT INTERCEPTOR DITCH

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RE030
EROSION CONTROL-DITCH



DETAIL RE031-EROSION CONTROL-SLOPE DRAIN



GENERAL NOTES:

The temporary slope drains shall be placed at locations stated in the plans or at locations deemed necessary by the Engineer.

The extra length of berm shown in the left side of the plan view illustrates an extension of the berm to alleviate erosion of the cut or fill slope. The length and locations of the berms shall be approved by the Engineer.

The corrugated polyethylene pipe shall be secured in place by wrapping 16 Ga. wire around the pipe and steel T fence posts multiple times as necessary and shall be approved by the Engineer.

The quantity of class A riprap shall be determined by the Engineer, however, the minimum quantity allowed is 1 cubic yard.

The temporary slope drain shall be measured to the nearest foot.

All costs for constructing and removing the temporary slope drains including labor, equipment, and materials which include the class A riprap, corrugated polyethylene pipe, steel T fence posts, wire, and necessary earthwork, shall be incidental to the contract unit price per foot for the corresponding temporary slope drain bid item.

EROSION CONTROL-TEMPORARY SLOPE DRAIN

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RE031

EROSION CONTROL-SLOPE DRAIN



DETAIL RE032-EROSION CONTROL-SURFACE ROUGHENING



GENERAL NOTES:

Where practical, surface roughening shall be done on slopes 3:1 and steeper and on slopes deemed necessary by the Engineer.

The equipment used for surface roughening shall be equipped with tracks that are capable of creating ridges in the soil that are perpendicular to the slope. The final condition of the surface roughening shall be approved by the Engineer.

Measurement for surface roughening shall be to the nearest tenth of an acre.

All costs associated with surface roughening including labor, equipment, and materials shall be incidental to the contract unit price per acre for "Surface Roughening".

EROSION CONTROL-SURFACE ROUGHENING

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RE032


EROSION CONTROL-SURFACE ROUGH




DETAIL RF001-FENCING-RIGHT-OF-WAY



ALL WOOD POSTS




ALTERNATE WOOD AND STEEL POSTS




TYPE 1

(3 Barbed Wires)




TYPE 2

(4 Barbed Wires)



TYPE 3

(5 Barbed Wires)



TYPE 4

(26" Woven Wire with 2 Barbed Wires)



TYPE 5

(26" Woven Wire with 4 Barbed Wires)



TYPE 6

(32" Woven Wire with 3 Barbed Wires)



TYPE OF FENCE		LINE POST SPACING	BARBED WIRE		WOVEN WIRE
TYPE	DESCRIPTION		WIRE GAGE	NUMBER AND SHAPE OF BARBS	STYLE OR DESIGN NO.
1	3 Barbed Wires	16'-6"	12 1/2	2 Point Round	—
2	4 Barbed Wires	16'-6"	12 1/2	2 Point Round	—
3	5 Barbed Wires	16'-6"	12 1/2	2 Point Round	—
4	26" Woven Wire with 2 Barbed Wires	14'-0"	12 1/2	2 Point Round	726-6-12 1/2
5	26" Woven Wire with 4 Barbed Wires	14'-0"	12 1/2	2 wires with 2 Pt. Rd. 2 wires with 4 Pt. Rd.	726-6-12 1/2
6	32" Woven Wire with 3 Barbed Wires	14'-0"	12 1/2	2 wires with 2 Pt. Rd. 1 wire with 4 Pt. Rd.	832-6-12 1/2

GENERAL NOTES:

Fence types designated on the plans that are followed by the letter S will have smooth (barbless) wires.

When type 5S or 6S is designated the bottom wire may be barbed, smooth, or left off.

All degrees of curvature stated for fence are at centerline of roadway.


FENCING-RIGHT-OF-WAY

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RF001
FENCING-RIGHT-OF-WAY



DETAIL RF002-FENCING-INSTALLATION



STAPLE INSTALLATION

GENERAL NOTES:

The Right-of-Way fence will consist of barbed wire or a combination of woven wire and barbed wire. The barbed wire and/or woven wire will be fastened to all wood posts or fastened to alternating wood and steel posts. Only wood posts will be used for brace panels. Gates will be of the type designated in the plans or as otherwise directed by the Engineer. Fence will be constructed conforming to the details on the standard plates and in the plans unless otherwise directed by the Engineer.

Right-of-Way fence on Interstate Projects will be constructed one foot within the Interstate Right-of-Way lines except at bridge openings, cattle passes, and as otherwise directed by the Engineer.

Right-of-Way fence other than on Interstate Projects will be constructed within one foot of the Right-of-Way on the Landowner's side except at bridge openings, cattle passes, and as otherwise directed by the Engineer.

Barbs will be fabricated from zinc coated 14 ga. wire. Two point barbs will be wrapped twice around one main strand at four-inch spacings and the four point barbs will be interlocked and wrapped around both main strands at five-inch spacings.

The gages of wire and wood post lengths and sizes are the minimum acceptable unless otherwise specified in the plans. The tolerances for steel posts will be as stated in AASHTO M281. Woven wire will conform to design and specifications of ASTM A116 and barbed wire will conform to ASTM A121.

FENCING-RIGHT-OF-WAY INSTALLATION

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RF002



FENCING-RIGHT-OF-WAY INSTALL






DETAIL RF003-FENCING-BRACE PANEL AND APPLICATIONS




ENTRANCE
(Not on corner)



Fence type will be same as adjacent fence type or as directed by the Engineer.



DOUBLE ENTRANCES



ENTRANCES AT CORNERS

GATES

- * If fence length is less than 600' to next corner use a 2 post panel.
- * If fence length is greater than 600' to next corner use a 3 post panel.

① See Detail B on Sheet 1 of 3.


FENCING-BRACE PANELS AND APPLICATIONS

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RF003
FENCING-BRACE PANEL APP.-1




DETAIL RF004-FENCING-BRACE PANEL APPLICATIONS AT STRUCTURES



**R.C. BOX CULVERT
OR CATTLE PASS**

**STRUCTURE WITH STREAM
CROSSING FENCE**



**R.C. BOX CULVERT
OR CATTLE PASS**

BRIDGE

- * If fence length is less than 600' to next corner use a 2 post panel.
- * If fence length is greater than 600' use a 3 post panel.


FENCING-BRACE PANEL APPLICATIONS AT STRUCTURES

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RF004
FENCING-BRACE PANEL APP.-2




DETAIL RF005-FENCING-WIDE DEPRESSIONS AND STREAM CROSSINGS



This installation will be made when requested by the Engineer.

FENCING AT WIDE DEPRESSION

(Subject to Flooding)



This installation will be made only when stated in the plans.

FENCING AT STREAM CROSSING

GENERAL NOTES:

There will be no extra payment for the additional work and materials required to construct the fencing at the wide depression(s) and/or the fencing at the stream crossing(s). The deadmen will be paid for in accordance with 620.5 A of the Specifications.

Measurement and payment for the fencing at the wide depression(s) and/or the fencing at the stream crossing(s) will be at the contract unit price per foot for the corresponding Right-of-Way fence contract item.

FENCING-WIDE DEPRESSIONS AND STREAM CROSSINGS

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RF005

FENCING-DEPRESSIONS/CROSSINGS



DETAIL RF006-FENCING-GROUNDING



GENERAL NOTES:

Details shown on this standard plate will apply to all types of Right-of-Way fence constructed with all wood posts or chain link fence.

Continuous fence in urban areas will be grounded at maximum intervals of 500 feet. Continuous fence in rural areas will be grounded at maximum intervals of 1000 feet. There will be a ground at a maximum of 100 feet from a gate in each adjacent section of fence.

Fence placed under a power line will be grounded with three grounds. One ground will be placed directly below the crossing and the other two will be placed 25 feet to 50 feet away, one on each side.

One ground will be placed directly below each telephone or cable crossing.

Ground rods will be located on the post side of the fence and will be as close as possible to the post and fence.

The cost of furnishing and placing all materials for grounding will be incidental to the contract unit price per foot for the respective Right-of-Way fence or chain link fence contract item.

The approximate quantities of materials per each installation of a ground are:

- 1 ground rod clamp.
- 1 $\frac{5}{8}$ " diameter x 8' long copper clad ground rod
- 1 #6 AWG bare copper wire; 7' long for Right-of-Way fence or 10' long for chain link fence.


Compression type or other type of connectors:

26" woven wire will have a total of two connectors, one secured to the top and one secured to the bottom.

32" woven wire will have a total of three connectors, one secured to the top, one secured to the middle, and one secured to the bottom.

One connector will be used for each strand of barbed wire.

A minimum of 3 connectors will be installed on chain link fence, the connectors will be placed vertically at every 2-foot increment and connectors will be placed on the top and bottom tension wires or top rail.




FENCING-GROUNDING

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RF006
FENCING-GROUNDING



DETAIL RF010-FENCING-WIRE-GATES



W Gate Width (Ft.)	S Post Spacing
16	3 @ 5'-0" ±
20	4 @ 4'-9" ±
24	4 @ 5'-9" ±
30	5 @ 5'-10" ±
40	6 @ 6'-6" ±

GENERAL NOTES:

Creosote treatment of the gate posts will not be accepted.

The type of fencing in the gate will be of the same type as specified for the adjacent Right-of-Way fence.

All costs for furnishing and constructing the wire gate(s) will be incidental to the contract unit price per foot for the respective Right-of-Way fence contract item.




FENCING-WIRE GATES

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RF010
FENCING-WIRE GATES



DETAIL RF011-FENCING-TUBULAR FRAME GATES



GENERAL NOTES:

Only single tubular frame gates are shown on this standard plate. If double tubular frame gates are specified, the gates will be of the same type and materials as shown above. Double tubular gates will swing toward the middle of the opening and will be secured by a chain, latch, or other suitable hardware.

Gate hardware will conform to the specific type of gate installed. The gate and gate hardware will either be painted or galvanized. The paint on the gates and hardware will be subject to approval by the Engineer.

The Steel Link Chain will be a minimum of 1/4", 4' long, rust resistant, and have electrically welded links. The chain will be wrapped around the gate hinge post and gate frame and the ends of the chain will be welded together with enough slack in the chain to provide free operation of the gate.


FENCING-TUBULAR FRAME GATES

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RF011
FENCING-TUBULAR FRAME GATES




DETAIL RF020-FENCING-ANCHORS FOR BOX CULVERT WING WALLS




DETAIL FOR FENCE ANCHORS

GENERAL NOTES:

1. The fence and post details shown are for illustrative purpose only. The fence shall be as specified elsewhere in the plans.
2. Eyebolts shall be placed on all of the box culvert wing walls.
3. Eyebolts shall be $\frac{5}{8}$ inch diameter and shall conform to ASTM A307.
4. Eyebolts, nuts, and concrete inserts shall be galvanized in accordance with AASHTO M232 (ASTM A153). Concrete inserts of corrosion resistant material need not be galvanized.
5. Cast-in-place eyebolts shall have a nut attached, be $4\frac{1}{2}$ inches (Min.) in length and shall be embedded such that the eye of the bolt is flush with the concrete surface. (See Eyebolt Details) As an alternate, cast-in-place concrete inserts, capable of developing the full strength of the $\frac{5}{8}$ inch diameter threaded eyebolt, may be used and shall be set in the concrete in accordance with the manufacturer's recommendations. The eyebolt shall be of sufficient length to develop its full strength. The eye of the eyebolt shall be flush with the concrete surface.
6. The cost for furnishing and installing eyebolts and/or concrete inserts shall be incidental to various contract items.



VIEW A - A



EYEBOLT DETAILS


FENCING-ANCHORS FOR BOX CULVERT WING WALLS

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RF020
FENCING-ANCHORS-1




DETAIL RF021-FENCING-ANCHORS FOR BRIDGE ABUTMENT WING WALLS (>6')




GENERAL NOTES:

DETAIL FOR FENCE ANCHORS

1. The fence and post details shown are for illustrative purpose only. The fence shall be as specified elsewhere in the plans.
2. Eyebolts shall be placed on all of the bridge abutment wings.
3. Eyebolts shall be $\frac{5}{8}$ inch diameter and shall conform to ASTM A307.
4. Eyebolts, nuts, and concrete inserts shall be galvanized in accordance with AASHTO M232 (ASTM A153). Concrete inserts of corrosion resistant material need not be galvanized.
5. Cast-in-place eyebolts shall have a nut attached, be $4\frac{1}{2}$ inches (Min.) in length and shall be embedded such that the eye of the bolt is flush with the concrete surface. (See Eyebolt Details) As an alternate, cast-in-place concrete inserts, capable of developing the full strength of the $\frac{5}{8}$ inch diameter threaded eyebolt, may be used and shall be set in the concrete in accordance with the manufacturer's recommendations. The eyebolt shall be of sufficient length to develop its full strength. The eye of the eyebolt shall be flush with the concrete surface.
6. The cost for furnishing and installing eyebolts and/or concrete inserts shall be incidental to various contract items.



VIEW A - A



EYEBOLT DETAILS

FENCING-ANCHORS FOR BRIDGE ABUTMENT WING WALLS (GREATER THAN 6')

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RF021

FENCING-ANCHORS-2





DETAIL RF022-FENCING-ANCHORS FOR BRIDGE ABUTMENT WING WALLS (≤6')



GENERAL NOTES:

1. The fence and post details shown are for illustrative purpose only. The fence shall be as specified elsewhere in the plans.
2. Eyebolts shall be placed on all of the bridge abutment wings.
3. Eyebolts shall be $\frac{5}{8}$ inch diameter and shall conform to ASTM A307.
4. Eyebolts, nuts, and concrete inserts shall be galvanized in accordance with AASHTO M232 (ASTM A153). Concrete inserts of corrosion resistant material need not be galvanized.
5. Cast-in-place eyebolts shall have a nut attached, be $4\frac{1}{2}$ inches (Min.) in length and shall be embedded such that the eye of the bolt is flush with the concrete surface. (See Eyebolt Details) As an alternate, cast-in-place concrete inserts, capable of developing the full strength of the $\frac{5}{8}$ inch diameter threaded eyebolt, may be used and shall be set in the concrete in accordance with the manufacturer's recommendations. The eyebolt shall be of sufficient length to develop its full strength. The eye of the eyebolt shall be flush with the concrete surface.
6. The cost for furnishing and installing eyebolts and/or concrete inserts shall be incidental to various contract items.



FENCING-ANCHORS FOR BRIDGE ABUTMENT WING WALLS (6' AND LESS)


NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RF022
FENCING-ANCHORS-3




DETAIL RF023-FENCING-ANCHORS FOR BRIDGE ABUTMENT WITH SWEEP BACK WINGS

See Detail X



Front Face of Abutment




DETAIL "X"


DETAILS FOR FENCE ANCHORS

GENERAL NOTES:

1. The fence and post details shown are for illustrative purpose only. The fence shall be as specified elsewhere in the plans.
2. Eyebolts shall be placed on all of the bridge abutment wings.
3. Eyebolts shall be $\frac{5}{8}$ inch diameter and shall conform to ASTM A307.
4. Eyebolts shall be galvanized in accordance with AASHTO M232 (ASTM A153).
5. Eyebolts shall be installed after abutment wings are backfilled and berm construction is complete. Drill-in and epoxy eyebolts into abutment such that the eye of the bolt is flush with the concrete surface.
6. The epoxy resin mixture shall be of a type for bonding steel to hardened concrete and shall conform to AASHTO M235 Type IV, Grade 3 (Equivalent to ASTM C881, Type IV, Grade 3).
7. The diameter of the drilled holes shall not be less than $\frac{1}{8}$ inch greater, nor more than $\frac{3}{8}$ inch greater than the diameter of the eyebolts or per manufacturer's recommendations. The drilled holes shall be blown out with compressed air using a device that will reach the back of the hole to be sure that all debris or loose material has been removed prior to epoxy injection.
8. Mix epoxy resin as recommended by the Manufacturer and apply by an injection method as approved by the Engineer. Beginning at the back of the drilled holes, fill the holes $\frac{1}{3}$ to $\frac{1}{2}$ full of epoxy, or as recommended by the Manufacturer, prior to insertion of the eyebolts. Care shall be taken to prevent epoxy from flowing out of the horizontal holes prior to eyebolt insertion. Rotate the eyebolt during installation to eliminate voids and ensure complete bonding of the bolt. Insertion of the eyebolts by the dipping or painting method will not be allowed.
9. Loads shall not be applied to the epoxy grouted eyebolts until the epoxy resin has had sufficient time to cure as specified by the epoxy resin man.
10. The cost for furnishing and installing the eyebolts shall be incidental to various contract items.



VIEW A - A



EYEBOLT DETAILS


FENCING-ANCHORS FOR BRIDGE ABUTMENTS WITH SWEEP BACK WINGS

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RF023
FENCING-ANCHORS-4



DETAIL RG001-CURB & GUTTER-TYPE B



Type	T ₁ (Inches)	T ₂ (Inches)	Cu. Yd. Per Lin. Ft.	Lin. Ft. Per Cu. Yd.
B66	6	51/16	0.057	17.7
B67	7	61/16	0.065	15.4
B68	8	71/16	0.073	13.7
B68.5	8.5	79/16	0.077	13.0
B69	9	81/16	0.081	12.3
B69.5	9.5	89/16	0.085	11.7
B610	10	91/16	0.090	11.2
B610.5	10.5	99/16	0.094	10.7
B611	11	101/16	0.098	10.2
B611.5	11.5	109/16	0.102	9.8
B612	12	111/16	0.106	9.4

GENERAL NOTES:

When concrete curb and gutter longitudinally adjoins new concrete pavement, the method of attachment shall be by one of the methods shown on Standard Plate 380.11.

See Standard Plate 650.90 for expansion and contraction joints in the curb and gutter.


CURB AND GUTTER-CONCRETE-TYPE B

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RG001
CURB & GUTTER-TYPE B



DETAIL RG002-CURB & GUTTER-TYPE BL



Type	T ₁ (Inches)	T ₂ (Inches)	Cu. Yd. Per Lin. Ft.	Lin. Ft. Per Cu. Yd.
BL66	6	65/8	0.063	15.9
BL67	7	75/8	0.071	14.1
BL68	8	85/8	0.080	12.5
BL68.5	8.5	91/8	0.084	11.9
BL69	9	95/8	0.088	11.4
BL69.5	9.5	101/8	0.092	10.9
BL610	10	105/8	0.096	10.4
BL610.5	10.5	111/8	0.100	10.0
BL611	11	115/8	0.104	9.6
BL611.5	11.5	121/8	0.108	9.3
BL612	12	125/8	0.112	8.9

GENERAL NOTES:

When concrete curb and gutter longitudinally adjoins new concrete pavement, the method of attachment shall be by one of the methods shown on Standard Plate 380.11.

See Standard Plate 650.90 for expansion and contraction joints in the curb and gutter.


CURB AND GUTTER-CONCRETE-TYPE BL

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RG002
CURB & GUTTER-TYPE BL



DETAIL RG003-CURB & GUTTER-TAPER




LONGITUDINAL SECTION OF CONCRETE CURB TAPER

CURB-CONCRETE-TAPER
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RG003
CURB & GUTTER-TAPER




DETAIL RG004-CURB & GUTTER-TYPE P



TRANSVERSE SECTION

 Type P Concrete
Gutter Limits

Type	T ₁ (Inches)	T ₂ (Inches)	Cu. Yd. Per Lin. Ft.	Lin. Ft. Per Cu. Yd.
P6	6	63/8	0.047	21.2
P7	7	73/8	0.055	18.1
P8	8	83/8	0.064	15.7
P8.5	8.5	87/8	0.068	14.8
P9	9	93/8	0.072	13.9
P9.5	9.5	97/8	0.076	13.2
P10	10	103/8	0.080	12.5
P10.5	10.5	107/8	0.084	11.9
P11	11	113/8	0.088	11.3
P11.5	11.5	117/8	0.092	10.8
P12	12	123/8	0.096	10.4



* Joint will not be needed if concrete curb and gutter and type P concrete gutter is placed at the same time. If the 1/2" Preformed Expansion Joint Filler is provided, then the joint shall be sealed.

GENERAL NOTES:

The concrete for the Type P Concrete Gutter shall comply with the requirements of the Specifications for Class M6 Concrete.

When concrete gutter longitudinally adjoins new concrete pavement, the method of attachment shall be in accordance with SDDOT requirements.

Transverse contraction joints shall be constructed at 10' intervals in the concrete gutter except when concrete gutter is constructed adjacent to mainline PCC pavement. When concrete gutter is constructed adjacent to mainline PCC pavement, a transverse contraction joint shall be constructed in the concrete gutter at each mainline PCC pavement transverse contraction joint location.

When concrete gutter is placed monolithically with mainline PCC pavement, the transverse contraction joints in the concrete gutter shall be sawed and sealed the same as the transverse contraction joints in the mainline PCC pavement.

When concrete gutter is not placed monolithically with the mainline PCC pavement and when the adjacent mainline surfacing is not PCC concrete, the transverse contraction joints in the concrete gutter shall be 11/2 inches deep if formed in the fresh concrete using a suitable grooving tool. If a saw is used to cut the contraction joints, then the depth of the joint shall be at least 1/4 the thickness of the concrete.


GUTTER-CONCRETE-TYPE P

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RG004
CURB & GUTTER-TYPE P



DETAIL RG005-CURB & GUTTER-VALLEY



GENERAL NOTES:

The concrete shall comply with the Specifications for Class M6 concrete.

The reinforcing steel shall comply with the requirements of the Specifications.

If a lap splice is provided the No. 4 rebar shall be lapped a minimum of 12".

** The sawed joints shall be spaced at 12' ; however, when the length of the valley gutter is 12' to 24' there shall be a joint at the midpoint of the length. The saw cut to control cracking shall be a minimum of 1/4 the thickness of the pavement.

All hot poured elastic joint sealer material spilled on the surface of the concrete pavement shall be removed as soon as the material has cooled. The extent of removal of material shall be to the satisfaction of the Engineer. All costs for removal of the spilled joint sealer material shall be borne by the Contractor.

The silicone sealant shall be bonded to the sides of a clean joint to completely seal the joint as approved by the Engineer.


GUTTER-CONCRETE-VALLEY

NOT TO SCALE


CITY OF BOX ELDER
STANDARD DETAIL RG005
CURB & GUTTER-VALLEY




DETAIL RG006-CURB & GUTTER-JOINTS-1




(Curb and Gutter Placed Monolithic with
Adjacent Mainline PCC Pavement)




SECTION A-A



(Curb and Gutter not Placed Monolithic with
Adjacent Mainline PCC Pavement or Mainline
Surfacing is not PCC Pavement)



SECTION B-B



* The silicone sealant shall be placed such
that it completely seals the joint and is
bonded to the sides of the clean joint
as approved by the Engineer.


CURB AND GUTTER-CONCRETE-JOINTS

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RG006
CURB & GUTTER-JOINTS 1



DETAIL RG007-CURB & GUTTER-JOINTS-2



* The silicone sealant shall be placed such that it completely seals the joint and is bonded to the sides of the clean joint as approved by the Engineer.

GENERAL NOTES:

For illustrative reason, only the type B curb and gutter is shown.

** A 1/2" preformed expansion joint filler shall be placed transversely in the curb and gutter at the following locations:

1. At each junction between the radius return of curb and gutter and curb and gutter which is parallel to the project centerline.
2. At each junction between new curb and gutter and existing curb and gutter.

Transverse contraction joints shall be constructed at 10' intervals in the concrete curb and gutter except when the concrete curb and gutter is constructed adjacent to mainline PCC pavement. When concrete curb and gutter is constructed adjacent to mainline PCC pavement, a transverse contraction joint shall be constructed in the concrete curb and gutter at each mainline PCC pavement transverse contraction joint location.

When concrete curb and gutter is not placed monolithically with the mainline PCC pavement or when the adjacent mainline surfacing is not PCC concrete, the transverse contraction joints in the concrete curb and gutter shall be 1 1/2 inches deep if formed in the fresh concrete using a suitable grooving tool. If a saw is used to cut the contraction joints, then the depth of the joint shall be at least 1/4 the thickness of the concrete and the joint shall be sealed in accordance with the details shown above.

CURB AND GUTTER-CONCRETE-JOINTS


NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RG007
CURB & GUTTER-JOINTS 2



DETAIL RG010-CURB & GUTTER-CURB RAMP-PERPENDICULAR-1


The turning space is 5' x 5' unless stated otherwise in the plans. (See Detail E)



1/2" Preformed Expansion Joint Filler (See Specifications and Standard Plate 651.75)


The edge of the curb and gutter concrete adjacent to the type 1 detectable warnings shall be straight, but may be curved when using type 2 detectable warnings.

Reference point for location of curb ramp as shown in the plans.



(If Turning Space concrete is placed monolithic with surrounding concrete, then this detail is not necessary.)

The turning space is 5' x 5' unless stated otherwise in the plans. (See Detail E)



No. 4 Rebar 1'-6" Length Drilled and Grouted (Typ.)

DETAIL E ISOMETRIC VIEW

(If Turning Space concrete is placed monolithic with surrounding concrete, then this detail is not necessary.)

1/2" Preformed Expansion Joint Filler (See Specifications and Standard Plate 651.75)

The edge of the curb and gutter concrete adjacent to the type 1 detectable warnings shall be straight, but may be curved when using type 2 detectable warnings.

Reference point for location of curb ramp as shown in the plans.

CURB AND GUTTER-CURB RAMP-PERPENDICULAR

NOT TO SCALE

CITY OF BOX ELDER

STANDARD DETAIL RG010

CURB & GUTTER-RAMP-PERP. 1



DETAIL RG011-CURB & GUTTER-CURB RAMP-PERPENDICULAR-2

Curb ramp slopes are designed at 7.5% unless stated otherwise in the plans. The curb ramp may have a maximum slope of 8.3% and shall not exceed 15' in length unless stated otherwise in the plans.


- * The curb ramp length may be computed based on the intersection of a continuous 1.5% theoretical slope from theoretical top of curb (TTOC) with the curb ramp using a continuous 7.5% curb ramp slope. The elevation of point TCR shall always be higher than the elevation of point TTOC unless specified otherwise in the plans. The curb ramp length dimension as shown in the plans shall be adjusted as necessary to meet all slope and length requirements based on field geometrics.

The cross slope of the ramp shall not be steeper than 2%. Plans are designed using a 1.5% slope unless stated otherwise in the plans.


- ** The slope in the turning space shall not be steeper than 2% in any direction of pedestrian travel. Plans are designed using a 1.5% slope unless stated otherwise in the plans.

- *** The curb transition shall be a minimum of 6' long, a maximum of 10' long, and the curb transition slope shall not be steeper than 10% unless stated otherwise in the plans. The curb transition length shall be adjusted as necessary to meet slope and length requirements based on field geometrics.


- **** The ramp width is 5' unless stated otherwise in the plans.




SECTION A-A



SECTIONAL VIEW B-B



DETAIL D



SECTIONAL VIEW C-C

CURB AND GUTTER-CURB RAMP-PERPENDICULAR

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RG011
CURB & GUTTER-RAMP-PERP. 2



DETAIL RG012-CURB & GUTTER-CURB RAMP-PERPENDICULAR-3

GENERAL NOTES:

For illustrative purpose only, type 1 detectable warnings are shown in the drawings.

For illustrative purpose only, PCC fillet sections are shown in the drawings. The curb ramp depicted on this standard plate may be used with a PCC fillet section or curb and gutter.

For illustrative purpose only, the curb ramp location is shown at the center of a PCC fillet section. The curb ramp shall be placed at the location stated in the plans.

Sidewalk shall not be placed adjacent to the curb ramp flares when a 2' curb transition is used unless shown otherwise in the plans.

- * Care shall be taken to ensure a uniform grade on the curb ramp, free of sags and short grade changes.

Surface texture of the curb ramp shall be obtained by coarse brooming transverse to the slope of the curb ramp.

The normal gutter line profile shall be maintained through the area of the ramp opening.

Joints shall be sawed or tooled into the concrete adjacent to the detectable warnings to alleviate possible corner cracking.

Care shall be taken to ensure that the surface of the detectable warnings are clean and maintains a uniform color.

The detectable warnings shall be cut as necessary to fit the plan specified limits of the detectable warnings. Cost for cutting the detectable warnings shall be incidental to the corresponding detectable warning bid item.

There will be no separate payment for curb ramps. The curb ramp shall be measured and paid for at the contract unit price per square foot for the corresponding concrete sidewalk bid item. The square foot area of the detectable warnings shall be included in the measured and paid for quantity of sidewalk.

If rebar is placed in the Turning Space as depicted in DETAIL E, the cost of the materials, labor, and equipment to furnish and install the rebar shall be incidental to the contract unit price per square foot for the corresponding concrete sidewalk bid item.

The curb transitions and ramp opening shall be measured and paid for at the contract unit price per foot for the corresponding curb and gutter bid item when curb and gutter is used. The curb transitions and ramp opening shall be measured and paid for at the contract unit price per square yard for the corresponding PCC fillet section bid item when a PCC fillet section is used.

The type 1 detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type 1 detectable warnings including labor, equipment, materials, and incidentals shall be paid for at the contract unit price per square foot for "Type 1 Detectable Warnings".

The type 2 detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type 2 detectable warnings including labor, equipment, and materials, including adhesive, necessary sealant or grout, and necessary grinding shall be paid for at the contract unit price per square foot for "Type 2 Detectable Warnings".


CURB AND GUTTER-CURB RAMP-PERPENDICULAR

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RG012
CURB & GUTTER-RAMP-PERP. 3




DETAIL RG013-CURB & GUTTER-CURB RAMP-DIRECTIONAL-1



- ☒ The slope within the transition area shall not be steeper than 5%. The concrete within the transition shall be placed monolithic with the curb and gutter or fillet section concrete. The concrete thickness within the transition shall be the same as the curb and gutter or fillet section concrete thickness.

*** The curb transition shall be a minimum of 6' long, a maximum of 10' long, and the curb transition slope shall not be steeper than 10% unless stated otherwise in the plans. The curb transition length shall be adjusted as necessary to meet slope and length requirements based on field geometrics.




CURB AND GUTTER-CURB RAMP-DIRECTIONAL

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RG013
CURB & GUTTER-RAMP-DIRECT. 1



DETAIL RG014-CURB & GUTTER-CURB RAMP-DIRECTIONAL-2



Curb ramp slopes are designed at 7.5% unless stated otherwise in the plans. The curb ramp may have a maximum slope of 8.3% and shall not exceed 15' in length unless stated otherwise in the plans.

* The elevation of point TCR shall always be higher than the elevation of point TTOC unless specified otherwise in the plans. The curb ramp length dimension as shown in the plans shall be adjusted as necessary to meet all slope and length requirements based on field geometrics.

The cross slope of the ramp shall not be steeper than 2%. Plans are designed using a 1.5% slope unless stated otherwise in the plans.

** The slope in the turning space shall not be steeper than 2% in any direction of pedestrian travel. Plans are designed using a 1.5% slope unless stated otherwise in the plans.

**** The ramp width is 5' unless stated otherwise in the plans.

CURB AND GUTTER-CURB RAMP-DIRECTIONAL

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RG014
CURB & GUTTER-RAMP-DIRECT. 2



DETAIL RG015-CURB & GUTTER-CURB RAMP-DIRECTIONAL-3

GENERAL NOTES:

For illustrative purpose only, type 1 detectable warnings are shown in the drawings.

The curb ramp depicted on this standard plate may be used with a PCC fillet section or curb and gutter. The curb ramp shall be placed at the location stated in the plans.

Sidewalk shall not be placed adjacent to the curb ramp flares when a 2' curb transition is used unless shown otherwise in the plans.

- * Care shall be taken to ensure a uniform grade on the curb ramp, free of sags and short grade changes.

Surface texture of the curb ramp shall be obtained by coarse brooming transverse to the slope of the curb ramp.

The normal gutter line profile shall be maintained through the area of the ramp opening.

Joints shall be sawed or tooled into the concrete adjacent to the detectable warnings to alleviate possible corner cracking.

Care shall be taken to ensure that the surface of the detectable warnings are clean and maintains a uniform color.

The detectable warnings shall be cut as necessary to fit the plan specified limits of the detectable warnings. Cost for cutting the detectable warnings shall be incidental to the corresponding detectable warning bid item.

There will be no separate payment for curb ramps. The curb ramp shall be measured and paid for at the contract unit price per square foot for the corresponding concrete sidewalk bid item. The square foot area of the detectable warnings shall be included in the measured and paid for quantity of sidewalk.

If rebar is placed in the Turning Space as depicted in DETAIL E, the cost of the materials, labor, and equipment to furnish and install the rebar shall be incidental to the contract unit price per square foot for the corresponding concrete sidewalk bid item.

The curb transitions and ramp opening shall be measured and paid for at the contract unit price per foot for the corresponding curb and gutter bid item when curb and gutter is used. The curb transitions and ramp opening shall be measured and paid for at the contract unit price per square yard for the corresponding PCC fillet section bid item when a PCC fillet section is used.

All costs for furnishing and installing the transition area at the base of the curb ramp shall be incidental to the contract unit price per foot for the corresponding curb and gutter bid item when curb and gutter is used and shall be incidental to the contract unit price per square yard for the corresponding PCC fillet section bid item when a PCC fillet section is used.

The type 1 detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type 1 detectable warnings including labor, equipment, materials, and incidentals shall be paid for at the contract unit price per square foot for "Type 1 Detectable Warnings".

The type 2 detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type 2 detectable warnings including labor, equipment, and materials, including adhesive, necessary sealant or grout, and necessary grinding shall be paid for at the contract unit price per square foot for "Type 2 Detectable Warnings".

CURB AND GUTTER-CURB RAMP-DIRECTIONAL

NOT TO SCALE



CITY OF BOX ELDER

STANDARD DETAIL RG015

CURB & GUTTER-RAMP-DIRECT. 3



DETAIL RG016-CURB & GUTTER-CURB RAMP-PARALLEL-1



CURB AND GUTTER-CURB RAMP-PARALLEL
NOT TO SCALE

CITY OF BOX ELDER


STANDARD DETAIL RG016

CURB & GUTTER-RAMP-PARALLEL 1




DETAIL RG017-CURB & GUTTER-CURB RAMP-PARALLEL-2


- * The curb transition slope shall match the curb ramp slope. Curb ramp slopes are designed at 7.5% unless stated otherwise in the plans. The curb ramp may have a maximum slope of 8.3% at any location of the curb ramp and shall not exceed 15' in length unless stated otherwise in the plans. The curb transitions and curb ramp lengths shall be adjusted as necessary to meet all slope and length requirements based on field geometrics.
- ** The cross slope of the ramp shall not be steeper than 2% and the ramp width is 5' unless stated otherwise in the plans. Plans are designed using a 1.5% cross slope for the ramp unless stated otherwise in the plans.
- *** The slope in the turning space shall not be steeper than 2% in any direction of pedestrian travel. Plans are designed using a 1.5% slope unless stated otherwise in the plans.
- **** The turning space is 5' x 5' unless stated otherwise in the plans.
- ☒ The curb height shall be 6" unless stated otherwise in the plans.




SECTION A-A



DETAIL D




DETAIL C



DETAIL D

(Use this detail when the curb height is greater than 6" and less than 12")



SECTIONAL VIEW B-B

CURB AND GUTTER-CURB RAMP-PARALLEL

NOT TO SCALE

CITY OF BOX ELDER

STANDARD DETAIL RG017

CURB & GUTTER-RAMP-PARALLEL 2



DETAIL RG018-CURB & GUTTER-CURB RAMP-PARALLEL-3

GENERAL NOTES:

For illustrative purpose only, type 1 detectable warnings are shown in the drawings.

For illustrative purpose only, a PCC fillet section is shown in one of the drawings.
The curb ramp depicted on this standard plate may be used with a PCC fillet section or with curb and gutter.

The curb ramp shall be placed at the location stated in the plans.

Sidewalk adjacent to the curb ramp shall be as shown in the plans.

Care shall be taken to ensure a uniform grade on the curb ramp, free of sags and short grade changes.

Surface texture of the curb ramp shall be obtained by coarse brooming transverse to the slope of the curb ramp.

The normal gutter line profile shall be maintained through the area of the ramp opening.

Joints shall be sawed or tooled into the concrete adjacent to the detectable warnings to alleviate possible corner cracking (see plan view for joint location).

Care shall be taken to ensure that the surface of the detectable warnings are clean and maintains a uniform color.

The detectable warnings shall be cut as necessary to fit the plan specified limits of the detectable warnings. Cost for cutting the detectable warnings shall be incidental to the corresponding detectable warning bid item.

When curb height is greater than 6" and less than 12", reinforcing steel is required in accordance with the detail on sheet 2 of 3. The reinforcing steel shall conform to ASTM A615, Grade 60. Cost for furnishing and installing the reinforcing steel shall be incidental to the contract unit price per square foot for the corresponding concrete sidewalk bid item.

There will be no separate payment for curb ramps. The curb ramp shall be measured and paid for at the contract unit price per square foot for the corresponding concrete sidewalk bid item. The square foot area of the detectable warnings and the curb along the short radius shall be included in the measured and paid for quantity of sidewalk.

The curb transitions and ramp opening shall be measured and paid for at the contract unit price per foot for the corresponding curb and gutter bid item when curb and gutter is used. The curb transitions and ramp opening shall be measured and paid for at the contract unit price per square yard for the corresponding PCC fillet section bid item when a PCC fillet section is used.

The type 1 detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type 1 detectable warnings including labor, equipment, materials, and incidentals shall be paid for at the contract unit price per square foot for "Type 1 Detectable Warnings".

The type 2 detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type 2 detectable warnings including labor, equipment, and materials, including adhesive, necessary sealant or grout, and necessary grinding shall be paid for at the contract unit price per square foot for "Type 2 Detectable Warnings".

CURB AND GUTTER-CURB RAMP-PARALLEL

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RG018

CURB & GUTTER-RAMP-PARALLEL 3



DETAIL RG030-CURB & GUTTER AND TRANSITIONS FOR FUTURE CURB RAMP-1



GENERAL NOTES:

For illustrative purpose only, the curb opening location is shown at the center of the fillet section. The curb opening shall be placed at the location(s) stated in the plans.

For illustrative purpose only, PCC fillet sections are shown in the above drawings. The curb opening depicted on this standard plate may be used with a PCC fillet section or with curb and gutter.

*The curb transition shall be a minimum of 6' long, a maximum of 10' long, and the curb transition slope shall not be steeper than 10% unless stated otherwise in the plans. The curb transition length shall be adjusted as necessary to meet the slope and length requirements based on the field geometrics.

**The curb opening width is 5' unless stated otherwise in the plans.

The normal gutter line profile shall be maintained through the area of the curb opening.

The curb transitions and opening shall be measured and paid for at the contract unit price per foot for the corresponding curb and gutter bid item when curb and gutter is used. The curb transitions and opening shall be measured and paid for at the contract unit price per square yard for the corresponding PCC fillet section bid item when a PCC fillet section is used.


CURB OPENING AND TRANSITIONS IN CURB AND GUTTER FOR FUTURE CURB RAMP AND CURBSIDE SIDEWALK

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RG030
CURB & GUTTER-OPEN & TRANS. 1



DETAIL RG031-CURB & GUTTER-OPENING AND TRANSITIONS FOR FUTURE CURB RAMP-2



GENERAL NOTES:

For illustrative purpose only, the curb opening location is shown at the center of the fillet section. The curb opening shall be placed at the location(s) stated in the plans.

For illustrative purpose only, PCC fillet sections are shown in the above drawings. The curb opening depicted on this standard plate may be used with a PCC fillet section or with curb and gutter.

* The curb opening width is 5' unless stated otherwise in the plans.

The normal gutter line profile shall be maintained through the area of the opening.

The curb transitions and opening shall be measured and paid for at the contract unit price per foot for the corresponding curb and gutter bid item when curb and gutter is used. The curb transitions and opening shall be measured and paid for at the contract unit price per square yard for the corresponding PCC fillet section bid item when a PCC fillet section is used.




CURB OPENING AND TRANSITIONS IN CURB AND GUTTER FOR FUTURE CURB RAMP AND BOULEVARD SIDEWALK

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RG031
CURB & GUTTER-OPEN & TRANS. 2



DETAIL RL001-LIGHTING-DETECTOR LOOP-PREFORMED




LIGHTING-DETECTOR LOOP-PREFORMED
NOT TO SCALE


CITY OF BOX ELDER
 STANDARD DETAIL RL001
 LIGHTING-DETECTOR LOOP-PREFORM



DETAIL RL002-LIGHTING-DETECTOR LOOP-SAWED IN



SAWED SLOT LAYOUT




WIRING DIAGRAM


GENERAL NOTES:

See Specifications Section 635.3 Q.

All costs associated with furnishing and installing the lead-ins shall be incidental to the contract unit price per each for "Sawed-In Detector Loop".



LEAD-IN THROUGH SHOULDER DETAIL



LEAD-IN THROUGH CURB AND GUTTER DETAIL

LIGHTING-DETECTOR LOOP-SAWED-IN

NOT TO SCALE



CITY OF BOX ELDER

STANDARD DETAIL RL002

LIGHTING-DETECTOR LOOP-SAWED



DETAIL RL003-LIGHTING-DETECTOR LOOP-SAWED IN PCC



GENERAL NOTE:

All costs for constructing the sawed-in detector loop protection including labor, equipment, and materials shall be incidental to the contract unit price per each for "Sawed-In Detector Loop".

LIGHTING-DETECTOR LOOP-SAWED-IN PCC

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RL003


LIGHTING-DETECTOR LOOP-SAWED



DETAIL RL004-LIGHTING-CONDUCTOR CABLES-CONDUIT



PLAN VIEW



SECTION VIEW

GENERAL NOTE:

The Buried Cable Marker shall be plastic, approximately 6" wide, and shall be capable of sustaining a minimum of a 350% tolerance of elongation without tearing. The Buried Cable Marker shall have a life expectancy approximately equal to that of the conductor(s) beneath it. A phrase indicating the presence of a buried electric circuit below shall be printed in a contrasting color on the cable marker. The Buried Cable Marker shall be subject to approval by the Engineer. All costs associated with furnishing and installing the Buried Cable Marker shall be incidental to the contract unit price per Foot for the bid item used for the electrical conductor.

LIGHTING-CONDUCTOR CABLES-DIRECT BURY

NOT TO SCALE



CITY OF BOX ELDER

STANDARD DETAIL RL004

LIGHTING-CONDUCTOR CABLES-BURY



DETAIL RL005-LIGHTING-CONDUCTOR CABLES-DIRECT BURY



GENERAL NOTE:

The Buried Cable Marker shall be plastic, approximately 6" wide, and shall be capable of sustaining a minimum of a 350% tolerance of elongation without tearing. The Buried Cable Marker shall have a life expectancy approximately equal to that of the conductor(s) beneath it. A phrase indicating the presence of a buried electric circuit below shall be printed in a contrasting color on the cable marker. The Buried Cable Marker shall be subject to approval by the Engineer. All costs associated with furnishing and installing the Buried Cable Marker shall be incidental to the contract unit price per Foot for the bid item used for the electrical conductor.

LIGHTING-CONDUCTOR CABLES-CONDUIT

NOT TO SCALE

CITY OF BOX ELDER

STANDARD DETAIL RL005



LIGHTING-CONDUCTOR CABLES-CON.



DETAIL RR001-RAILROAD-PAVEMENT MARKINGS AT CROSSINGS

KEY	ITEM
	24" White
	White

Posted Speed Limit (M.P.H.)	L (Ft.)
≤ 30	100
35	100
40	125
45	175
50	250
55	325
60	400
65	475
70	550



GENERAL NOTES:

The railroad crossing pavement markings will be placed symmetrically about the centerline of the railroad crossing.

When pavement markings are used, a portion of the RXR symbol will be placed directly opposite of the advance warning sign W10-1.

On multi-lane roads the transverse bands will extend across all approach lanes and individual RXR symbols will be placed in each approach lane.

The railroad crossing pavement markings will consist of all the transverse bands, stop bars, and RXR symbols.

When pavement marking paint is used for marking the railroad crossing, all costs for furnishing and painting the markings, materials, labor, and necessary equipment will be incidental to the contract unit price per gallon.

When pavement marking tape is used for marking the railroad crossing, all costs for furnishing and placing the markings, materials, labor, and necessary equipment will be incidental to the contract unit price per each..

RAILROAD-PAVEMENT MARKINGS AT CROSSINGS

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RR001

RAILROAD-PAVEMENT MARKINGS



DETAIL RR002-RAILROAD-TYPICAL APPROACH



RAILROAD-TYPICAL APPROACH

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RR002


RAILROAD-TYPICAL APPROACH



DETAIL RR003-RAILROAD-EXCAVATION PROFILES



EXCAVATION PROFILE ALONG ROADWAY



EXCAVATION PROFILE ALONG RAILROAD


RAILROAD-EXCAVATION PROFILES

NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RR003
RAILROAD-TYPICAL GRADING



DETAIL RR010-RAILROAD-DETECTABLE SIDEWALK WARNINGS ADJACENT TO CROSSING-1



PLAN VIEW

- *The cross slope of the sidewalk shall not be steeper than 2%. Plans are designed using a 1.5% cross slope unless stated otherwise in the plans.
- **If the sidewalk is curbside, then the surface of the curbside sidewalk shall match the slope of the curb transition. The longitudinal slope of the sidewalk and curb transition, where the sidewalk transitions to the railroad crossing elevation, is designed at 4.5% and shall not be steeper than 5% unless stated otherwise in the plans.
- **The longitudinal slope of the sidewalk, where the sidewalk transitions to the railroad crossing elevation, is designed at 4.5% and shall not be steeper than 5% unless stated otherwise in the plans.

RAILROAD-DETECTABLE SIDEWALK WARNINGS ADJACENT TO CROSSINGS-1

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RR010

RAILROAD-DETECTABLE SIDEWALK 1



DETAIL RR011-RAILROAD-DETECTABLE SIDEWALK WARNINGS ADJACENT TO CROSSING-2



SECTION A-A

GENERAL NOTES:

For illustrative purpose only, type 1 detectable warnings are shown in the drawings.

Ballast material shall not be disturbed during construction work adjacent to the railroad crossing unless the adjacent work involves reconstruction or maintenance of the railroad crossing.

The sidewalk shall be placed at the location stated in the plans and shall be perpendicular to the railroad crossing.


Care shall be taken to ensure that the surface of the detectable warnings are clean and maintains a uniform color.

If curb and gutter is required adjacent to the railroad crossing, the curb transition shall be measured and paid for at the contract unit price per foot for the corresponding curb and gutter bid item.

The type 1 detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type 1 detectable warnings including labor, equipment, materials, and incidentals shall be paid for at the contract unit price per square foot for "Type 1 Detectable Warnings".

The type 2 detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type 2 detectable warnings including labor, equipment, and materials, including adhesive, necessary sealant or grout, and necessary grinding shall be paid for at the contract unit price per square foot for "Type 2 Detectable Warnings".

The square foot area of the detectable warnings shall be included in the measured and paid for quantity of sidewalk.



DETAIL B

RAILROAD-DETECTABLE SIDEWALK WARNINGS ADJACENT TO CROSSINGS 2

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RR011


RAILROAD-DETECTABLE SIDEWALK 2



DETAIL RS001-SIDEWALK-CONCRETE-1



- B Width of boulevard as specified in the plans.
 T Thickness of PCC sidewalk as specified in the plans.
 W Width of PCC sidewalk as specified in the plans.
 * Type as specified in the plans.



GENERAL NOTES:

The PCC sidewalk shall be constructed in accordance with the Specifications.

***The cross slope of the sidewalk is designed at 1.5% and the maximum slope allowed is 2% unless specified otherwise in the plans.

The maximum length between expansion joints in PCC sidewalk is 75 feet.

PCC sidewalk placed adjacent to intersection of roadways shall have an expansion joint placed transversely a maximum of 37.5 feet from the intersection. See PLAN VIEW.

An expansion joint in PCC sidewalk shall consist of a 1/2 inch thick preformed expansion joint filler material placed full depth and width of the PCC sidewalk.


** Large areas of PCC pavement adjacent to PCC sidewalk may require a different joint treatment than shown in the detail. If a different joint detail is necessary, plans will contain the joint detail and the Contractor shall construct the joint treatment in accordance with the plans.

SIDEWALK-CONCRETE **NOT TO SCALE**


CITY OF BOX ELDER
STANDARD DETAIL RS001
SIDEWALK-CONCRETE 1




DETAIL RS002-SIDEWALK-CONCRETE-2




ELEVATION VIEW
(PCC sidewalk adjacent to asphalt concrete pavement)



ELEVATION VIEW
(PCC sidewalk adjacent to earthen material, landscape rock, or other compressible materials)



ELEVATION VIEW
(PCC sidewalk adjacent to building or other rigid structure)



ELEVATION VIEW
(PCC sidewalk adjacent to PCC pavement)


Detail A
(Use Appropriate Detail(s))

SIDEWALK-CONCRETE
NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RS002
SIDEWALK-CONCRETE 2



DETAIL RS010-SIDEWALK-DRAIN



GENERAL NOTES:

Concrete shall be Class M6 in accordance with the Specifications.

Reinforcing steel shall conform to ASTM A615, Grade 60.

Structural Steel shall conform to ASTM A36. The sidewalk drain cover shall conform to ASTM A786.

Welding and weld inspection shall be in conformance with the current edition of the AWS D1.1 Structural Welding Code—Steel.

The cover plate assembly shall be galvanized after fabrication. Galvanizing shall be in accordance with ASTM A123.

All costs associated for providing the required curb cut shall be incidental to the contract unit price per foot for the corresponding curb and gutter bid item.


SIDEWALK-DRAIN

NOT TO SCALE


CITY OF BOX ELDER
STANDARD DETAIL RS010
SIDEWALK-DRAIN



DETAIL RS011- REINFORCED CONCRETE SIDEWALK ADJACENT TO PRECAST CONCRETE TYPE S DROP INLET



PLAN VIEW
(Curbside Reinforced Concrete Sidewalk)



PLAN VIEW
(Reinforced Concrete Sidewalk With Boulevard)

N.T.S.



CITY OF BOX ELDER

STANDARD DETAIL RS011 - REINFORCED CONCRETE SIDEWALK

ADJACENT TO PRECAST CONCRETE TYPE S DROP INLET



DETAIL RS012-SIDEWALK-ADJACENT TO TYPE S DROP INLET LID-2



SIDEWALK-ADJACENT TO TYPE S DROP INLET LID

NOT TO SCALE


CITY OF BOX ELDER

STANDARD DETAIL RS012

SIDEWALK-TYPE S DROP INLET LID 2



DETAIL RS013 - RESIDENTIAL DRIVEWAY APPROACH (PROPERTY LINE SIDEWALK)



Notes:

1. Driveway widths shall be per Box Elder Infrastructure Design Standards.
2. Contraction joints in the PCC approach pavement shall be a minimum of 1/4 the thickness of the approach pavement.
Additional contraction joints not shown in the Plan View will be spaced as follows:
 - a. Joints shall be equally spaced across the driveway. Driveways up to 36' in width shall have a maximum joint spacing of 12'.
 - b. Driveways greater than 36' in width and up to 40' in width shall have 4 equally spaced joints.
3. All costs for furnishing and placing the PCC approach pavement and constructing the expansion and contraction joints including labor, equipment, excavation, and materials including the earthen backfill will be incidental to the contract unit price per square yard for the corresponding PCC Approach Pavement contract item.
4. The sidewalk width through the full width of the driveway opening shall be 5' wide minimum.



N.T.S.

CITY OF BOX ELDER

**STANDARD DETAIL RS013 - RESIDENTIAL DRIVEWAY
APPROACH (PROPERTY LINE SIDEWALK)**



DETAIL RS014 - 6" REINFORCED DRIVEWAY APPROACH AND SIDEWALK



SECTION A-A

Notes:

1. Minimum depth of granular material placed under reinforced driveway approach shall be 4".
2. When removing existing curb & gutter for new approach construction, an expansion joint shall be constructed.
3. Reinforced driveway and sidewalk shall be placed at all alley entrances and at driveways into property which is multi-family, commercial, light industrial and heavy industrial.
4. No. 4 rebar shall be placed as per detail and tied together. 2" clearance shall be maintained between bottom of concrete and rebar.


N.T.S.

CITY OF BOX ELDER


STANDARD DETAIL RS014 - 6" REINFORCED
DRIVEWAY APPROACH AND SIDEWALK



DETAIL RS015 - RESIDENTIAL DRIVEWAY APPROACH (CURBSIDE SIDEWALK)



SECTION C-C
(Optional Curb Shown)



DETAIL B
(Optional Curb Shown)

PERSPECTIVE VIEW
(Optional Curb Shown)

DETAIL C
(Optional Triangle Pavement Shown)

Notes:

1. Driveway widths shall be per Box Elder Infrastructure Design Standards.
2. Detail C shall be used unless otherwise shown in the plans and specifications or as directed by the Engineer.
3. Contraction joints in the driveway approach pavement shall be a minimum of 1/4 the thickness of the approach pavement.
Additional contraction joints not shown in the Plan View will be spaced as follows:
 - a. Joints shall be equally spaced across the driveway. Driveways up to 36' in width shall have a maximum joint spacing of 12'.
 - b. Driveways greater than 36' in width and up to 40' in width shall have 4 equally spaced joints.


N.T.S.

CITY OF BOX ELDER

**STANDARD DETAIL RS015 - RESIDENTIAL DRIVEWAY
APPROACH (CURBSIDE SIDEWALK)**






DETAIL RS016- DRIVEWAY PROFILE GRADE



CITY OF BOX ELDER STANDARD DETAIL RS016 DRIVEWAY PROFILE GRADE



DETAIL RS017- RESIDENTIAL DRIVEWAY APPROACH



- * Sidewalks to be constructed adjacent to the curb shall be a minimum of 5' in width for lane, place and local roads and a minimum of 6' for all other roads. The cross slope of the sidewalk is designed at 1.5% and will not be steeper than 2% unless specified otherwise in the plans.
- ** The slope of the driveway approach pavement in these areas will match the slope of the concrete curb transition and the length will not be longer than 15'. The slope is designed at 7.5% and will not be steeper than 8.3% unless specified otherwise in the plans.

N.T.S.


CITY OF BOX ELDER
STANDARD DETAIL RS017
RESIDENTIAL DRIVEWAY APPROACH



DETAIL #RS017

REVISED 09/2025

DETAIL RW001-CONCRETE RETAINING WALL-TYPE C-1



* The sidewalk width of the Type C Concrete Retaining Wall shall not be wider than 8 feet or narrower than 5 feet.

In the areas where the retaining wall footing is to be placed, a 2 inch thickness of cushion material shall be placed and compacted.

All concrete shall be Class M6 and conform to Section 462 of the Specifications.

All reinforcing steel shall be epoxy coated and shall conform to ASTM A615, Grade 60. The smooth bar may conform to ASTM A615, Grade 40. The epoxy coating shall conform to ASTM A775.

For variable height walls, the top b1 bar shall be placed parallel to the top of the wall.

The b1 bars shall be lapped a minimum of 12 inches.

A 3/4 inch chamfer shall be provided on all exposed retaining wall edges.

Use Detail B on sheet 2 of 2 for constructing corners in the retaining wall.

The maximum expansion joint spacing shall be 90 feet and the maximum contraction joint spacing shall be 30 feet. The contraction and expansion joints shall be placed to match pavement or curb joints where possible.

The exposed retaining wall surfaces shall receive a finish in accordance with 460.3 L of the Specifications. The exposed surface of the retaining wall footing, when used as a sidewalk, shall receive a broom finish.

The Type C Concrete Retaining Wall shall be measured to the nearest square foot of front face area of the wall. The front face of the footing is excluded from the measurement.

All costs for excavation, furnishing and placing backfill and cushion material, labor, equipment, preformed expansion joint filler, all reinforcing steel including the smooth bars, and all concrete except in the areas of PCC driveway and approach pavement, shall be incidental to the contract unit price per square foot for "Type C Concrete Retaining Wall".

The concrete used for the retaining wall footing that extends into the approach and/or driveway pavement shall be paid for at the contract unit price per square yard for the corresponding "PCC Approach Pavement" and/or "PCC Driveway Pavement" bid items.

CONCRETE RETAINING WALL-TYPE C



NOT TO SCALE

CITY OF BOX ELDER
STANDARD DETAIL RW001
RETAINING WALL-CONC.-TYPE C 1




DETAIL RW002-CONCRETE RETAINING WALL-TYPE C-2



Use No. 4 bars for all reinforcing steel unless specified otherwise.




DETAIL B
PLAN VIEW OF WALL CORNER DETAIL




SECTION D-D




VIEW F-F



PLAN VIEW
TYPE C CONCRETE RETAINING WALL ON P.C.C. APPROACH PAVEMENT



SECTION E-E



PLAN VIEW
TYPE C CONCRETE RETAINING WALL ON P.C.C. DRIVEWAY AND APPROACH PAVEMENT

CONCRETE RETAINING WALL-TYPE C

NOT TO SCALE

CITY OF BOX ELDER

STANDARD DETAIL RW002

RETAINING WALL-CONC.-TYPE C 2

